

AUSTRALIA'S DYNAMIC ELECTRONICS MONTHLY!

eti

AUGUST 1984

\$2.50*
NZ \$2.95

Electronics Today

INTERNATIONAL


**WIN THIS
Sanyo
Betamovie
Home Video
Outfit!**

**NEW SERIES
STARTING
ELECTRONICS**

**STEREO
TV: Better
Sound Now!**

**\$599 CD
PLAYER
REVIEWED**

**PERTH
ELECTRONICS
SHOW**
Special Report



PROJECTS
Tug-O-War Game
Bass Guitar Amp
Electronic Mousetrap

COMPUTER CLUB LIST

FOR QUALITY, PERFORMANCE & VALUE, AARON MUST BE YOUR FIRST 'SCOPE CHOICE

(and for after sales service too!)



1 BS601 - 20MHz/5mV with Built-in Component Tester

\$465 ex tax \$538 tax paid

- Check components on screen
- 19 range timebase • Triggers to over 30MHz • 17nS risetime

2 BS810 - 100MHz/1mV with 4 Channels and 8 Traces

\$2295 ex tax \$2708.10 tax paid

- 2nS/div max sweep time
- Alternate time base with B ends A mode • Variable trigger hold-off
- Independent position controls
- Signal delay

3 BS625 - 45MHz/1mV with Signal and Timebase Delay

\$998 ex tax \$1155 tax paid

- Single sweep • Trigger delay
- 7.7nS risetime • X, Y, Dual, Chop, Add, Subtract etc

4 BS310S - 15MHz/2mV Battery Portable

\$625 ex tax \$724 tax paid

- Ideal for field service use
- 2 hour operation from built-in NiCads • Automatic re-charging
- Auto trigger free run • TV sync

5 BS320 - 15MHz/2mV with Digital Storage and DMM

\$2295 ex tax \$2708.10 tax paid

- Built-in 3½ digit multimeter
- Digital storage mode • Trigger delay • X-Y mode component tester • 3 channel operation for 3-phase measurements

6 BS635 - 35MHz/1mV with Alternate and Delayed Timebase

\$675 ex tax \$781 tax paid

- 21 range timebase • 100mS-1uS trigger delay • Front panel trace rotate • Multi-mode display

Optional carrying cases available for all 'scopes.

Coline Probes

A comprehensive range of probes and accessories is available. Modular types have pencil slim heads and detachable earth leads. They offer excellent pulse responses and very wide bandwidths. A comprehensive catalogue is available on request.

SP100 - 100MHz Probe

\$25 ex tax \$29.00 tax paid

With x1, ref, x10 positions. 1.5m lead, BNC connector and selection of tips in heavy duty pouch.

All prices are plus sales tax if applicable and subject to change without notice.

SOLD & SERVICED IN AUSTRALIA BY

ELMEASCO

Instruments Pty. Ltd.

NEW SOUTH WALES

15 Macdonald Street,
MORTLAKE
P.O. Box 30, CONCORD
NSW 2137
Tel: (02) 736 2888
Telex: AA25887

VICTORIA

12 Maroondah Highway,
RINGWOOD
P.O. Box 623, RINGWOOD
VIC 3134
Tel: (03) 879 2322
Telex: AA36206 ELMVIC

QUEENSLAND

243 Milton Road,
MILTON
P.O. Box 2360, BRISBANE
QLD 4001
Tel: (07) 369 8688
Telex: AA44062

SOUTH AUSTRALIA

99 King William Street,
UNLEY
P.O. Box 1240, ADELAIDE
SA 5001
Tel: (08) 271 1839
Telex: AA88160

WESTERN AUSTRALIA

P.O. Box 95, GOSNELLS
WA 6110
Tel: (09) 398 3362

N.S.W. Ames Agency 699 4524 • George Brown 519 5855, (049) 69 6399 • Davred 267 1385 • DGE Systems (049) 69 1625 • Macelec (042) 29 1455 • Radio Despatch 211 0191 • Sheridan Electronics 699 6912 N.T. Thew & McCann (089) 84 4999 A.C.T. George Brown (062) 80 4355 VIC. Browntronic 419 3986 • G.B. Telespares 328 4301 QLD. Colourview Wholesale 275 3188 • St. Lucia Electronics 52 7466 • Electronic Shop (075) 32 3632 • W.G. Watson (079) 27 1099 • Nortek (077) 79 8600 • ECO Electronics 376 5677 • Northern Circuits (070) 51 9063 • Fred Hoe & Sons 277 4311 S.A. Redarc Electronics 278 7488 • Trio Electrix 51 6718 • Protronics 212 3111 W.A. Atkins Carlyle 321 0101 TAS. GHE Electronics (002) 34 2233 & (003) 31 6533.



QUICK INDEX

IT IS PROBABLY time that the magazine's background and history were explained (again) for the benefit of readers, 'old' and new alike.

Electronics Today was conceived by a 15-year-old schoolboy! Back in 1968, Kim Ryrie tried to convince his publisher father, Colin, that there was a market for an alternative to the long-established Electronics Australia (which had the market to itself, then). Collyn Rivers responded to an advertisement (in Electronics Australia!) for 'an electronics journalist' with sound practical experience (a true rarity still) and joined Modern Magazines in 1970.

Electronics Today was born on March 23, 1971. It was put together then by a staff of two — Collyn Rivers, as Editor chief-sublayout-secretary-cleaner, and Barry Wilkinson doing the projects and drawings. Twelve months later, in 1972, a British edition was set up, followed six months later by a French edition. (This was sold to the French publishers a few years later.) In 1977, Canadian, German and Dutch editions appeared. Each is now autonomous. The word 'international' was added to the title with the launch of the British edition. Many readers have identified us as 'ETI' ever since.

A few years ago PT Centronics began publishing a series of project books in Indonesia using material from mostly the Australian editions.

Despite what some might make of the 'international' in our title, Electronics Today — this magazine you're reading, is wholly Australian owned, produced and printed. Fair dinkum!

The British, Canadian, German, Dutch — and Australian, editions all continue to flourish, despite the onslaught of a plethora of computer magazines.

Kim Ryrie, the perspicacious schoolboy, is now the Director of Fairlight Instruments, makers of the world-famous Fairlight Computer Musical Instrument.

Collyn Rivers, founder-Editor/Editorial Director/Managing Editor now runs a thriving technical writing/publishing firm with his wife, called Vernon Rivers & Associates.

Barry Wilkinson formed a company in 1976 to produce the projects for ETI and do freelance design. He gave away the ETI projects in 1978 (when we re-established our own lab.) and was recently behind the design of the Dulmont Magnum computer. At present he is 'semi-retired'.

Our current Managing Editor, Jim Rowe, as many readers will well know, is an ex-Editor of Electronics Australia. Strange, the twists of fate, eh?

Here we are, 13 years old (which event we celebrated on Friday, April 13), perhaps the *enfant terrible* of Australian electronics publishing, looking toward to a vigorous and prosperous, but *never* dull, future.

Roger Harrison
EDITOR

SERVICES

TECHNICAL INQUIRIES: We can only answer readers' technical inquiries by telephone after 4.30pm Mondays to Thursdays. The technical inquiry number is (02) 662-4267. Technical inquiries by mail must be accompanied by a stamped, self-addressed envelope. There is no charge. We can only answer queries relating to projects and articles as published. We cannot advise on modifications, other than errata or addenda. We try to answer letters as soon as possible. Difficult questions may take some time to answer.

COPYRIGHT: The contents of *Electronics Today International* and associated publications is fully protected by the Commonwealth Copyright Act (1968). Copyright extends to all written material, photographs, drawings, circuit diagrams and printed-circuit boards. Although any form of reproduction is a breach of copyright, we are not concerned about individuals constructing projects for their own private use, nor by bands (for example) constructing one or more items for use in connection with their performances. Commercial organisations should note that no project or part project described in *Electronics Today International* or associated publications may be offered for sale, or sold in substantially or fully assembled form, unless a licence has been specifically obtained so to do from the publisher, The Federal Publishing Company, or from the copyright holders.

GENERAL INQUIRIES: For all inquiries about back issues, subscriptions (\$24.00 for 12 months/12 issues), photocopies of articles, artwork or submitting articles, call (02) 663-9999 or write to: ETI Reader Services, 140 Joynton Avenue (PO Box 227), Waterloo, NSW 2017.

CONTRIBUTIONS: Submissions must be accompanied by a stamped, self-addressed envelope. The publisher accepts no responsibility for unsolicited material.

LIABILITY: Comments and test results on equipment reviewed refer to the particular item submitted for review and may not necessarily pertain to other units of the same make or model number. Whilst every effort has been made to ensure that all constructional projects referred to in this edition will operate as indicated efficiently and properly and that all necessary components to manufacture the same will be available, no responsibility is accepted in respect of the failure for any reason at all of the project to operate effectively or at all whether due to any fault in design or otherwise and no responsibility is accepted for the failure to obtain any component parts in respect of any such project. Further, no responsibility is accepted in respect of any injury or damage caused by any fault in the design of any such project as aforesaid.



FEATURES

Win a Betamovie home video outfit from Sanyo	12
Perth Electronics Show	15
Stereo TV: good sound cometh ..	27
TOPO robot review	36
Starting electronics: beginners' series, Part 1	42

AUDIO/VIDEO

SMPTE conference report:	
film vs video	35
Yamaha CD-X1 compact disc player review	54
Denon CD test disc review	60

COMPUTING

Memotech computer review	112
Know your computer nut!	118
Microbee arcade games	122
PROLOG, Part 2	127
Computer club list update	133
Commodore column	136

PROJECTS

807: Tug-O-War game	74
1524: Electronic mousetrap	80
1410: Bass guitar amp, Part 1	92

ELECTRONICS

Idea of the month	99
Ideas for Experimenters	102

COMMUNICATIONS

How the BBC and CIA keep tabs on the world	146
Satellites and shortwave	149

NEWS

News Digest	8
Sight & Sound	53
Equipment	65
Component	71
Computing Today	107
Communications	142

GENERAL

Advertisers' Index	5
Mail order books	130
Shoparound	156
Letters	160
Mini-Mart	161
Dregs	162

SPECIAL OFFERS

Babani books: buy 3-1 free	39
Denon test disc	63

EDITOR

Roger Harrison VK2ZTB

ASSISTANT EDITOR

Jennifer Whyte B. App. Sc.

EDITORIAL STAFF

Jon Fairall B.A.

Geoff Nicholls B.Sc./B.E.

Peter Ihnat B.E., B.Sc.

Robert Irwin

ASSOCIATES

David Tilbrook VK2YMI

Jonathan Scott

B.Sc./B.E. (Hons) VK2YBN

DRAUGHTING

David Currie

PRODUCTION

Peter Maxwell

Mark Davis

ADVERTISING SALES

John Whalen (National)

Steve Collett

ART DIRECTOR

Ali White B.A.

ART STAFF

Toni Henson

Brian Jones

Vicki Jones

READER SERVICES

Carmel Gatt

ACOUSTICAL CONSULTANTS

Louis Challis and Associates

MANAGING EDITOR

Jamieson Rowe

HEAD OFFICE

140 Joynton Avenue, (PO Box 227)

Waterloo, NSW 2017.

Phone: (02) 663-9999 Sydney.

Telex: 74488, FEDPUB.

ADVERTISING OFFICES**AND AGENTS:**

Victoria and Tasmania: Virginia Salmon and Mel Godfrey. The Federal Publishing Company, 23rd Floor, 150 Lonsdale Street, Melbourne, Vic. 3000. Phone: (03) 662-1222 Melbourne. Telex: 34340, FEDPUB.

South Australia and Northern Territory:

The Admedia Group, 24 Kensington Road, Rose Park, SA 5067. Phone: (08) 332-8144 Adelaide. Telex: 82182, ADMEDIA.

Queensland: Geoff Horne Agencies, PO Box

247, Kenmore, Qld 4069. Phone: (07)

202-6813 Brisbane. Telex: AA41398

HORNAG.

Western Australia: Cliff R. Thomas, Adrep

Advertising Representative, 62 Wickham Street, East Perth, WA 6000. Phone: (09) 325-6395 Perth.

New Zealand: Chris Horsley, 4A Symonds

Court, Symonds Street, Auckland. Telex:

NZ60753, TEXTURE. Phone: 39-6096.

Auckland.

Britain: Peter Holloway, John Fairfax and

Sons (Australia) Ltd, Associated Press House, 12 Norwich Street, London EC4A 1BH. Phone: (01) 353-9321 London. Telex: 262836, SMHLDN.

Japan: Genzo Uchida, Bancho Media

Services, 5th Floor, Dai-ichi Nisawa Building, 3-1 Kanda Tacho 2-chome, Chiyoda-ku, Tokyo 101. Phone: (03) 252-2721 Tokyo. Telex: 25472, BMSINC.

**ELECTRONICS TODAY INTERNATIONAL**

is published monthly by the Electronics Division of the Federal Publishing Company Pty Limited, 140 Joynton Avenue, Waterloo, NSW 2017. Typeset and printed by ESN-The Litho Centre, Sydney. Distributed by Gordon and Gotch Limited, Sydney. Cover price \$2.50 (maximum and recommended Australian retail price only; recommended New Zealand price, \$2.95). Registered by Australia Post, Publication No NBP0407. ISSN No 0013-5216.

COPYRIGHT © 1984, THE FEDERAL PUBLISHING COMPANY




Perth show. Car CD players — when?

Electronic mousetrap to build!

**SPECIAL OFFERS**

BABANI BOOKS: BUY 3-1 FREE39

DENON TEST DISC63

Black Magic! The Memotech MTX500

Know your computer nut!

**NEWS**

NEWS DIGEST	8
SIGHT & SOUND	53
EQUIPMENT	65
COMPONENT	71
COMPUTING TODAY	107
COMMUNICATIONS	142

COLUMNS

COMMODORE	136
-----------	-----

DEPARTMENTS

IDEA OF THE MONTH	99
IDEAS FOR EXPERIMENTERS	102
SHOPAROUND	156

This page is to assist readers in the continual search for components, kits, printed circuit boards and other parts for ETI projects and circuits. If you are looking for a particular item or project and it is not mentioned here, check with our advertisers.

MINI-MART 161

• We'll publish up to 24 words (maximum) free of charge for you, your club or your association. Copy **must** be with us by the first of the month preceding the month of issue. Please — **please** — print or type advertisements clearly, otherwise it may not turn out as you intended! Every effort will be made to publish all advertisements received; however, no responsibility for so doing is accepted or implied. Private advertisements only will be accepted. We reserve the right to refuse advertisements considered unsuitable.

• **Conditions:** Your name and address plus phone number (if required) must be included with the 24 words. Reasonable abbreviations, such as 25 W RMS or 240 Vac, count as one word. Advertisements must relate to electronics, audio, communications, computing, etc — general advertisements cannot be accepted. Send your advertisement to:

ETI Mini-Mart,
P.O. Box 227,
Waterloo NSW 2017.

MAIL ORDER BOOKS	130
LETTERS	160
DREGS	162



CONTENTS

FEATURES

Sanyo/Electronics Today Betamovie contest

Win a Betamovie home video outfit from Sanyo.

Perth Electronics Show

Industry asks the marketplace: Which way to go?

Stereo TV

Good sound cometh, says the Minister, but not on the ABC.

SMPTE conference report

Film vs video: conference conflict.

Starting electronics

Our new series for beginners: Part 1 — your basic toolkit.

Know your computer nut!

A guide to identifying computer programmers by their personality traits.

PROLOG — a programming language, Part 2

Basic framework consolidated with familiar examples to illustrate the use of recursion.

Computer club list update

How to contact computer clubs throughout Australia and New Zealand.

How the BBC and CIA keep tabs on the world

Knowing when and where to listen to local broadcasts gives the shortwave listener an advantage.

Satellites and shortwave

Satellites may be used as platforms for shortwave sound broadcasting transmitters.

PROJECTS

807: Tug-O-War game

Hours of fun with this intergalactic decision maker.

1524: Electronic mousetrap

Despatches the furry freeloaders in milliseconds and automatically resets.

1410: Bass guitar amp, Part 1

It delivers 150 watts into 4 ohms, has a 6-band graphic, limiter, line out and bi-amp facilities.

REVIEWS

TOPO robot

A walking, talking computer-controlled robot.

Yamaha CD-X1 compact disc player

You don't have to wait any longer. The CD-X1 has the performance and at the right price.

Denon CD test disc

It gives you the equivalent of more than \$10 000 worth of test equipment for \$20.

Memotech computer

The British-made Memotech MTX500 has some unusual features not found on machines around the same market price.

Microbee arcade games

A review of some new arcade-style games using the Microbee PCG.

ADVERTISERS' INDEX

12	ACME Electronics	161
15	ACE Electronics	29,30,31,32
27	Active Electronics	106
35	Applied Technology	40,41
42	Amtex	67
118	Aust. Government	IBC,24,25
127	Altronics	82,83,138,139,153
127	All Electronic Components	98
133	Antenna Engineering	157
146	Avtek Electronics	132
149	B.W.D.	38
	Centre Industries	111
	Datatel	11
	Delsound	42
	Dick Smith	50,51
	Electromark	62
	Ellistronics	86,87
	Elmeasco	IFC
	Email	70
	Energy Control	140
	Exciting Lighting	62
	GCS Computers	137
	Hewlett Packard	7
	Hi-Com Unitronics	95
	Hi-Tech Light & Sound	52
	Independent Software Duplication	140
	Jaycar	58,59,90,91,144 145,154,155,159
	Lawrence & Hanson	6,73
	Mag Media	140,141
	Mayer Kreig	95
	MaGraths	45
	Mini Tools Aust.	11
	Paris Radio	109
	Philips	21,26
	Pioneer	20
	Promark	68
	Prepak	70
	Rod Irving	46-47,64,69,79 94,100-101,103,104-105 110,116,121,125,126
	Rose Music	OBC
	Sanyo	14
	Scientific Devices	111
	Scope	23
	Soanar	157
	Sony (Aust)	16
	Stewart Elect	66
	Truscott Elect	62
	Warsash	157
	Warburton Franki	34
	Wireless Inst. Aust.	148

NEXT MONTH

STEREO TV SETS REVIEWED

Louis Challis reviews two top-line stereo TV receivers, from Sony and Philips. Does the news in stereo really grip you? Will Amanda leave John and cause Kevin to run away with Jill all in stereo? Is the French soundtrack better than the English on *Les Misérables*? Find out in the next exciting episode of "Louis Challis Finds Out"!

SIMPLE STEREO PROJECT

Next month we'll be describing a beaut stereo record player and amplifier system that's perfect for the beginner. Costing well under \$100, including the turntable, you can build this good-looking little unit that's just great for use in the bedroom, den, etc. It uses all readily available parts and is simple to build — just the thing for a weekend project, yet doesn't look 'home-made'.

IT PAYS TO HAVE THE RIGHT CONNECTIONS

LSA-PLUS from Krone. The telecommunication connection system of the future.

LSA-PLUS is an amazingly quick, Australian made connection system with modular and variable assemblies for wire termination, testing, patching and over voltage protection. A universal, non-soldering, non-screwed quick connection technique for indoors and out, perfect for telephone and intercom cabling, computer systems, studio cabling, alarm or signalling systems and process control cabling in the manufacturing industry to name but a few.

TELECOM APPROVED (PERMIT NO. CN83/144)

Telecom Australia has specified Krone LSA-PLUS Connection Systems for installations across the country, replacing solder, wire wrap and screw terminations.

A COMPLETE SYSTEM


Mounting brackets, frames, modules for 10 and 20 pair capacity, connectors for printed circuit boards or cable joining, isolation plugs, test cords, markers; and a host of useful accessories are available.

SAVES TIME - SAVES MONEY

Using a special mistake proof tool, cable guides in each module make connections extraordinarily easy.

Wires are simply pressed into the contacts, one action cuts the insulation and pushes the



stripped wire between spring loaded contact jaws. It could not be simpler or safer.



For more details of this amazing system, contact your nearest Lawrence & Hanson Sales Centre or State Technical Sales Branch.

They're your best connections in the business!

KRONE LSA-PLUS



LAWRENCE & HANSON

QLD. (07) 369 3899 N.S.W. (02) 699 1699 VIC. (03) 697 1599 TAS. (002) 34 2666 S.A. (08) 297 4566

N.T. (089) 52 2878 W.A. (09) 446 5400

LL BROWN & ASSOC 1137

Real-time analysis in any high-level language speeds your software development projects.

If you're developing software for complex microprocessor designs, the HP 64000 Logic Development System lets you take full advantage of the productivity benefits inherent in high-level languages such as Pascal and C. That's because the HP 64620 Logic State/Software Analyser (an integral part of the HP 64000 Logic Development System) lets you debug programs in the same high-level language in which you develop them.

It's the first real-time software analyser to offer detailed triggering and store qualification based on high-level statement line numbers and module names.

Virtually all high-level language compilers can interface with the HP 64620 analysis package, so it's source-language independent.

You can develop code on your favourite mainframe computer, then download portions of the code to the HP 64000 system (with an installed HP 64620 subsystem) for detailed real-time program flow analysis.

You get the economy of mainframe time-sharing, along with the unsurpassed diagnostic, emulation, and analytical features of the HP 64000 Logic Development System.

Contact your local HP sales office for complete details.




**HEWLETT
PACKARD**

LBV6131

Trace List
State 7, 60 channel, 68000 Mnemonic
Label: ADDRESS hex symbols
Base: 1012 supr data write
Mag: SRC_ADDR: Mon 68K FFFE supr program r
+002 MAGIC_SQU+00001C
+003 MAGIC_SQU+E68000 - line
Pascal program to generate a magic square.
matrix of numerical entries is constant. The squ
column, or diagonal is constant. The squ
of entries on a side, specified by the c
BEGIN (M_Square_Gen) (star
COL := SIZE/2;
+004 MAGIC_SQU+00001E MOVE.W 0000C
+005 STATA: Mon 68K 0000 supr da
+006 MONITOR_CONTROL: 8000 supr p
+007 MAGIC_SQU+000020 000B supr p
+008 MAGIC_SQU+000022 EXT.L D0
STATUS: Awaiting state command - user
-source on
display <LINE #> disassemb _source

Trace List
State 7, 60 channel, 1750A emulation bus
Label: line # ADDRESS 1750A Mnemonic time cov
Base: hex
Mag: ADDR_MAP and symbols ADDR_MAP and symbol
+011 12* aHANDIa+1109 LISP R2,1
+012 NUMBER_DISKS:aHANDIa 0014 mem
+013 12 aHANDIa+110A STB R
Jovial routine for solution of the
L3: IF NNK>1;
+014 13* aHANDIa+110B LISP
+015 NUMBER_MOVES:aHANDIa
+016 13 aHANDIa+110C CB
+017 13 aHANDIa+110D BEZ
+018 NUMBER_DISKS:aHANDIa
Begin NO(JP)=NN;
+019 14* aHANDIa+110E LT
STATUS: Awaiting state command - user id
-source on
display <LINE #> disassemb _source

Trace List
State 7, 60 channel, 68000 Mnemonic
Label: ADDRESS hex symbols
Base: 0000C
Mag: MOVE.W 0000C
+007 MAGIC_SQU+00003E MOVE.W 0000C
+008 MAGIC_SQU+000040 000B user program read
+009 MAGIC_SQU+000042 MULS.W D1,D1
+010 MAGIC_SQU+000044 MOVE.W 2006C
+011 MAGIC_SQU+000046 2006 user program read
MAGIC_SQU+E68000 - line 40 thru 42
this procedure, written in -C- fills out the square matrix
ROW = 0; /* initialize the row pointer */
for (COUNT = 1; COUNT <= SIZE*SIZE; COUNT++) (
+012 M_SQUARE3:3:MAGI CMP.W D1,D2
+013 MAGIC_SQU+00004A BGT.W MAGIC_SQU+00009A
+014 MAGIC_SQU+00004C 004E user program read
+015 MAGIC_SQU+00004E MOVE.W 2002C
+016 MAGIC_SQU+000050 2002 user program read
STATUS: Awaiting state command - user id CONTROL
-source on
display <LINE #> disassemb _source
show execute



It's the "frisbee" satellite!

The world's first "frisbee" satellite was to be sent spinning into orbit from the cargo hold of the space shuttle Discovery last month. The gigantic satellite, over 4 m diameter and 6 m high, is too big to launch by conventional rocket.

Called "Leasat", the satellite is the first of four communications spacecraft for the US Navy under a lease arrangement with owner-operator Hughes Communications Services Inc., a wholly-owned subsidiary of Hughes Aircraft Company. All are scheduled for launch by the space shuttle before the end of 1985. The Leasat network will provide global communications to the US armed forces.

Because of its 4.3 metre

diameter, Leasat is too large to launch on any vehicle other than the space shuttle. It is the first geosynchronous communications satellite to have its own in-built propulsion mechanism* while its compact design significantly reduces shuttle launch costs.

The 4.3 m diameter cylindrical satellite is spin-stabilised, rotating at 30 rpm when in final orbit to provide gyroscopic stability and thermal control. The

spinning 'barrel' of the satellite contains the solar array (for powering the batteries), Sun and Earth sensors to keep its 'attitude' correct, plus propulsion and attitude control systems. A 'de-spun' platform contains the antennas, communications and telemetry equipment. The antennas always point Earthward.

The Leasat is placed in orbit in five stages. Carried on its side in the shuttle bay, attached to a

U-shaped cradle, an explosive spring mechanism flings the Leasat from the shuttle bay with a spinning motion, like you launch a frisbee. This spins the satellite at 1.7 rpm, stabilising it and preventing solar over-exposure (i.e. sunburn). A timer puts up the bird's command and telemetry antennas and sets off a thruster which increases the spin rate to 33 rpm.

After the satellite has drifted half-way round the world at the shuttle's orbit height, a perigee 'kick' motor is set off that boosts it to a 'transfer' orbit with an apogee of 16 500 km.

Two liquid fuel motors then take the bird through three successive orbits, raising the apogee to 19 700 km, 26 000 km and finally, geosynchronous orbit over the equator at 35 800 km, after a few manoeuvres.

Once in place, the satellite is re-oriented, its antenna and electronics platform de-spun and the antenna deployed. The main body of the satellite spins at 30 rpm throughout its 10-year design life.

Two 3.7 m-long helical antennas provide receive and transmit capability in the UHF band from 240 to 340 MHz. Telemetry, command, and the fleet broadcast uplink and beacon are in the SHF band.

The communications subsystem consists of four functional groups: The fleet broadcast (25 kHz), wideband (500 kHz), relay (25 kHz) and narrowband (5 kHz). The fleet broadcast uses a 35 W transmitter and produces an effective isotropic radiated power (EIRP), or signal strength, of 26 dBW. The single wideband channel uses a 53 W transmitter, for an EIRP of 28 dBW, and the six relay channels use 35 W transmitters for an EIRP of 26 dBW. The five narrowband channels share a 20 W transmitter for an EIRP of 16.5 dBW.

After seven years in orbit, Leasat's solar array will generate 1200 W of electrical power. Three 24 Amp-hour Nickel-Hydrogen batteries supply full power during eclipse operations when the satellite passes through the Earth's shadow for up to 72 minutes during the equinox. The redundant three-battery system permits full load support with the loss of two batteries.

World's largest telescope

The University of California announced plans to build the world's largest reflecting telescope on Mauna Kea, a 4300 metre peak in Hawaii. It will be operating by 1990, according to the university, though the design is so radical that some scientists doubt it can be done. The telescope will be 10 metres across, almost twice as large as any existing reflecting telescope. It will gather four times more light and survey eight times the volume of space.

Astronomers expect to see light from events that occurred up to 17 billion years ago, thereby opening up new knowledge about the origins of the Universe.

The telescope will be called the Maximillian E. and Marion Hoffman Observatory.

The telescope will not be made of one mirror, like conventional telescopes. Instead it will comprise 36 hexagonal segments arranged in a parabola. The continuous alignment of the 1.6 metre mirrors will be established by actuators and sensors controlled by a computer.

Each of the mirrors' six sides will have two sensors. The computer will interpret signals from the sensors 100 times a second and then command three motors on the back of each mirror to make any necessary minute adjustments.



Ace in the hole! Terry Evans of Ace (left) signs with Ron Parker of Fairchild.

Ace in the hole for Fairchild

Sydney-based electronic components distributor, Ace Electronics Pty Ltd, has been appointed Fairchild distributor for NSW.

This was announced recently by Mr Ron Parker, Managing Director of Fairchild Australia.

Mr Parker said that the newly-formed Ace Electronics has the financial backup to make a major, long-term contribution to the supply of components to the electronics industry.

The General Manager of Ace Electronics Mr Trevor Evans

stated that the new agreement became effective 1st June and initial orders for over one million devices have been placed.

"Fairchild components will represent a large percentage of the total business activities of Ace Electronics. To fully provide the service and facilities needed to handle and satisfy customers' orders, a well-stocked warehouse and a fully computerised stock and accounting system have been installed."

He said that in the present

market there was an opportunity for an aggressive, active and service-orientated company to cater for the needs of the industry.

Ace will be carrying in excess of 3000 Fairchild lines.

Ron Parker said that his company believed that Ace Electronics' policy of service, keen prices and expertise complemented their own policies and that both companies will benefit from the agreement.

Ace Electronics is located at 69-75 Reservoir St, Surry Hills NSW 2010. (02)211-1144.

Rendezvous with Halley's Comet

Pictures from two Russian spacecraft may be used to ensure that a western European probe can get close to the core of Halley's Comet.

Halley's Comet is only seen from Earth once every 76 years. It was last seen in 1910 and is due to approach Earth again in early 1986. It has already been spotted on its orbit back towards Earth.

Russia and Japan are each planning to send up two craft to rendezvous with the comet on the night of March 13-14, 1986,

and these will be joined by two others built by the US and the European Space Agency (ESA).

The \$54 million ESA craft, named Giotto, is now under construction at the British Aerospace centre at Bristol in western England, and promises to be the most important and most elaborately instrumented of the six Halley probes.

Scientists predict that this craft may get as close as 500 kilometres to the Halley core as it goes through its 2000 kilometres wide dust cloud at a pas-

sing speed of 68 kilometres per second.

It may be helped by the two Russian Vega craft which will approach Halley first. They have a camera on board and the pictures could provide valuable information about Halley's exact position in space, so enabling the Giotto craft to be positioned with sufficient accuracy to get in closer to the comet than any of the others.

The 700 million kilometres journey from Earth will take eight months and Giotto's 10 experiments will have just a four-hour operational life as the craft approaches and passes

Halley.

At the speed the two will pass, dust particles from the comet will present a hazard to the spacecraft and despite being protected by a shield, computer models indicate that Giotto may not survive the encounter.

Before it is destroyed, however, it is hoped that the Giotto's instruments will provide unique data on the chemical composition of the cloud of dust surrounding the comet's core, and of its tail. A camera will also take colour pictures of the surface of the comet and measurements will be made of its magnetic field.

The Russians are Coming

The Museum of Victoria, Melbourne, is hosting the Soviet Space Exhibition from August 24, 1984.

The exhibition covers Soviet space achievements from the launch of Sputnik 1 through the first soft landings on Mars and Venus up to the exploits of Salyut 6.

The show will consist of replicas of most of the important space craft of the last three decades, plus some moonrock from Lunahod and a working model of the Baikonur space launching station. There will be videos and an eighty minutes film on the history of space flight.

School and students bulk bookings are available from the Education Department of the Museum. Other group bookings are available as are guided tours of the exhibition.

For more information phone the Museum on (03) 654-3341.



NEW FACES AT ETI

Jonathan Fairall
Technical Writer

Jon was born, raised and did various silly things while growing up in all sorts of funny places around the world. All without the slightest interest in electronics. The first thing he did when he left school was join the Navy, having grown up with visions

of steaming about the world sorting out foreigners. He learned very quickly however, that ships don't paint themselves. After two years of putting grey paint on the side of a ship he very nearly went colour blind and left the service to become a lay-about in Sydney. Well, a student actually.

During his years at Uni he learned his second great lesson about life, i.e: an inebriated arts student falls down just as fast as an inebriated sailor, only the student uses longer words to describe the situation.

Having learnt even more about life by driving a taxi while at Uni, he was admirably equipped to enter the glittering world of TV, where all the beautiful people work. After a while, the beautiful people turned out to be pretty ordinary workaholics who work so hard during the day they barely have the energy to crawl into bed at the end of it.

Anyway, sitting in the control room day after day as yet another show lurched calamitously to air, he became intrigued by the technology around him. So, on the basis that 'if I find it interesting someone else probably will too', he began writing science-type documentaries. It pretty soon dawned on him though, that after x million years in school and far too many at Uni, he was a real babe

in the woods when it came to the things that really make the world go round.

So, always being a sucker for punishment, he started all over again with educational establishments and rediscovered that both Shaw's and Peters' dictims apply very well to our great institutions of technical education. In spite of, or because of, their best endeavors he did learn about bytes, betas and bits, and picked up a magazine called. Er, Ah, . . . ETI on the news stand.

There followed a stint with Telecom, during which he discovered why the world doesn't so much go around as lurch through bends, before being accosted by your eager Editor, who said things like: "Ve haf veyes of makink you vork," and "I vill nails your hands to ze typewriter."

Somewhere along the line, and by methods still not altogether clear, he acquired offspring (I can loan you a good book, Jon . . . Jennie) and all the other paraphernalia of modern urban existence.

He likes good books and Australian movies (some of them, anyway), bushwalking, astronomy and music. He hates commercial TV and agrees totally with Oscar Wilde who once (more-or-less) said that anyone who opens his mouth before ten in the morning is a blithering idiot.

.....Brits follow later

Britain will be a key participant in IREECON '85, the 20th International Convention and Exhibition held by The Institution of Radio and Electronics Engineers Australia (IREE Aust).

This is the first time overseas exhibitors will be represented as a group with government backing, which reflects the rapidly growing international interest in IREE's biennial event.

From a small beginning in 1938, IREE Conventions have expanded to become Australia's largest and most comprehensive exhibition of professional electronic equipment, uniquely providing both a showcase for the latest electronic machinery and a meeting place for leading scientific minds.

IREECON '85 will take place in Melbourne's Royal Exhibition Building from September 30 to October 4 next year. Bookings and inquiries indicate that the number of exhibitors will exceed the record established last year at IREECON '83, which was held in Sydney at the Royal Agricultural Society

Showground. The organisers also expect a record number of technical papers for the concurrent lecture program.

The theme for IREECON '85 is: "The Australian position in the new era of communications".

IREECON '83 saw the first team of government-backed exhibitors, when representatives of Western Australian industry participated with the support of the Western Australian Government through the Department of Industrial Development.

Other states are understood to be studying the possibility of a similar arrangement at IREECON '85 and it is thought that Britain's decision to provide support for an industrial group could prompt other countries to follow suit.

IREECON '85 will feature a number of guest speakers complementing technical papers on a broad range of subjects.

For further information contact Heather Harriman, Executive Officer, The Institution of Radio and Electronics Engineers Australia. (02) 29-4051.

IEEE centennial medals

In celebration of its Centennial Year, the US-based Institute of Electrical and Electronics Engineers (IEEE) has awarded 1984 centennial medals, world wide, to outstanding individuals in recognition of their exceptional service to the Institute and to the profession.

Eight Australians have been chosen to receive this award.

They are: Ian P. Bates, of the State Electricity Commission of Victoria, for his contribution to control electric power systems,

Professor Lou Davies of AWA, for research into solid state electronics, Dr Bob Frater, of the CSIRO for work on signal processing, Professor Doug Lampard and Professor Hugo Messerle for contributions in education, Walter Samlo of the CSIRO for contributions to microwave measurement, Sir William Tyree for services to heavy electrical engineering and Jim Vasseleu of Power Electronics for leadership of the IEEE in Australasia.

Electronics & automation Trade Fair

The Electronics and Automation Trade Fair will be held in Oslo, Norway, 9-13 October, 1984.

This year's fair offers an extensive range of specialised, yet interacting, products and services. Exhibitors will be invited from the fields of hydraulics and pneumatics, process

control and monitoring, control engineering, instrumentation, computer technology, chemical engineering and electronics.

Further information from the Royal Norwegian Consulate General, 77 Pacific Highway, North Sydney NSW 2060. (02)92-6915.

Hitachi and Bridgestone have developed a prototype of a new robot arm that uses special rubber bearings to give it ultra-smooth operation. The macromolecular rubber used in the arm was specially developed by Bridgestone for the robot.

Over 2200 metres of optical fibre has been laid by Data Cable in the Melbourne and Metropolitan Board of Works head office. The installation makes the building the biggest single fibre optics site in Australia. The fibres will be used for interconnection between the Board's seven large computers.

The Institute of Diagnostic Engineers is holding its first annual convention in London between the 4th and 7th September, 1984. Further details are available from IDE, 3 Wycliffe St, Leicester LE1 5LR, England.

Ness Security Products has been awarded the Australian Design Award for Security Alarm control systems for its Necessity System 5+. The unit conforms to AS2201.


Tandy Corp has just released figures for its sales to April. Spokesman for Radio Shack, the parent company, called the \$198 million sales figure "disappointing". The figure represents a one percent rise in sales from last year.

The second method is to send Tom Moffat \$12 and ask for the 'universal' RTTY decoder tape. It's so cunning, it works out what model Microbee you've got and adjusts the value of 04AC accordingly! Send your rustproof shekels to: **Tom Moffat, 39 Pillinger Drive, Fern Tree Tas. 7101.**

	Were	Are
2 x Texas Instruments Thermal Printers with Memory Model 765 KSR	\$3665	\$1480
10 x Texas Instruments 16" Carriage Dot Matrix Printers, Model 840 RO	\$1280	\$490
3 x M.P.I. 80 Column Dot Matrix and Graphics Printers, Model 99 G	\$934	\$395
1 x DEC Dot Matrix and Graphics Printer, Model LA1ZD	\$1938	\$990
1 x DEC V.D.U. Model VT 101 (Requires fix for screen Jitter)	\$1973	\$495
1 x Microprocessor System—Twin Floppy Disk Complete With Beehive Burroughs Emulation V.D.U. Model DM 83	\$5976	\$3350

Sales Tax Additional 20% if applicable
Phone Don Mantack (03) 690 4000
to Reserve Your Selection

datatel pty. ltd.—
19 Raglan St., Sth Melb. 3205 Ph: (03) 690 4000
80 Chandos St., St. Leonards 2065 Ph: (02) 439 4211

**datate** h_{FE}

\$104

[inc. postage
& handling]

TTL/CMOS
Latch function

5 Hz/500 Hz

Expiry Date /
(Includes Postage)

Bankcard No. or Cheque

0
1
2
3
4
5
6
7
8
9

Signed _____

Name _____

Address

54
51
50
49

AUSTRALIA PTY. LTD.
134A AVR STREET,
DONCASTER. VIC. 3108
Tel 1021 950 9987

**For our readers:
a fabulous chance to**

WIN

Sanyo Australia, in conjunction with Electronics Today, is offering a Betamovie camera pack outfit and a VTC-M10 video cassette recorder with cord remote control as a prize in this great contest.

**Sanyo/ETI Betamovie
Home Video Contest**

All you have to do to enter the contest is answer these simple questions and tell us in 50 words or less, what you would like to do with the Sanyo Betamovie Home Video Outfit.

(1) What is unique about the Betamovie systems?

(2) Does the Beta video tape format use 'M-loading' or 'U-loading' to take the tape from the cassette?

Now tell us in 50 words or less just what you would like to do with the Sanyo Betamovie Home Video outfit described here. (Betamovie camera pack and VTC-M10 recorder with cord remote.)

Contest closes 1 October, 1984

SEND YOUR ENTRY TO:

**Sanyo Electronics Today
Betamovie Home Video Contest
P.O. Box 227,
Waterloo, NSW 2017**

• I have read the contest rules and agree to abide by their conditions:

Signature

A complete home video provides hours of enjoyment for families, for friends — in fact, for everyone. Especially when it's the brilliant Betamovie package from Sanyo! The outfit comprises the famous Betamovie camera plus accessories, AND the very popular VTC-M10 VCR. You could win the lot — simply by entering our great new contest.

DON'T DELAY — ENTER NOW!

You may enter as many times as you wish but you must use a separate entry form for each entry and include the month and page number cut from the bottom right hand portion of this page. You must put your name and address on the entry form and sign it where indicated.

Please read the contest rules carefully, especially if sending multiple entries.

RULES

This contest is open to all persons normally resident in Australia with the exception of members of the staff of Sanyo Australia, the Federal Publishing Company, Eastern Suburbs Newspapers, The Litho Centre and/or associated companies.

Closing date of the contest is 1 October, 1984. Entries received within seven days of that date will be accepted if postmarked prior to and including 1 October, 1984.

The winning entry will be drawn by the Managing Editor of ETI, whose decision is final. No correspondence will be entered into regarding the decision.

The winners will be notified by telegram the same day the result is declared. The name of the winner, together with the winning answers, will be published in the next possible issue of Electronics Today International.

Contestants must enter their names and addresses where indicated on each entry form. Photostats or clearly written copies will be accepted but if sending copies you must cut out and include with each entry form the month and page number from the bottom of the page of the contest. In other words, you can send in multiple entries but you will need extra copies of the magazine so that you can send an original page number with each entry form.

This contest is invalid in states where local laws prohibit entries.

Entrants must sign the declaration, accompanying the contest, that they have read the above rules and agree to abide by their conditions.

SANYO'S



BETAMOVIE

Home video outfit



Betamovie

BETAMOVIE CAMERA PACK

This includes the famous Betamovie camera with an attractive carrying strap, rechargeable battery and ac adaptor/charger pack. The Betamovie camera is the only video camera currently available that will record on a standard video cassette (Beta) which can be transferred direct from your camera to your VCR for instant viewing immediately after shooting. This system is just perfect for family shots, holiday scenes, around the home, etc. The camera will take any standard Beta cassette and gives up to one hour's shooting with the battery pack. Worth \$2386.

VCR WITH CORD REMOTE

One of Sanyo's most popular Beta video cassette recorders. The recorder features front loading, a 12-channel tuner and an 8-day/single programme timer for recording while you're not around. The controls include fast forward/reverse 'search' modes and a pause/still-frame button. The digital display features seven-segment fluorescent numerals for easy viewing in clock or programme mode. The display shows the time when not in the programme mode. To record a programme in your absence, simply set the start and stop times and enter them in the memory. Worth \$637 (rrp).



Total Value: Over \$3000

We've got a winning system.

Midi Component System with stereo Double cassette deck, AM/FM Stereo Receiver, Linear tracking turntable and 2-way, 2 speaker system from the Giants in Audio.

SYSTEM WO7

Double-Cassette Deck

Double-cassette deck with continuous and synchronous dubbing. The music never stops when you're listening to tapes on the Sanyo WO7. With the ingenious continuous play function, you simply place a cassette in each deck, press the play button for the tape you want to hear first and then the play button for the other deck. When the first tape has ended, the second one will begin automatically—slip a new tape into the first deck, preset the play button and you've started a cycle of music that can go on as long as you like. And it's just as easy to make copies of your tapes. With just one push of the auto play button, synchronous dubbing begins—and when the recording procedure is over, the unit switches itself off automatically.




Direct Call Function.

Take your pick of radio, tapes or records and then simply press the button for that source—instant operation with no fuss! With auto play

activated, all you need to do is press the turntable start button for playing records, the AM or FM button for radio listening, or the play button on the deck for tapes.

5-band Graphic Equalizer.

The WO7's amplifier section delivers a hearty 28 watts of power per channel to fill your room with lively sound brilliance. And to fine tune those sounds, Sanyo provides the tone control freedom of five separate sound adjusters that boost or cut selected frequencies by 10dB.



Synchronous Recording.

Once again, the auto play button makes life easier. For perfect recordings of records, just press auto play, place the record on the platter, prepare the deck for recording and start the turntable. The deck will begin recording as soon as the needle is in the groove.

Linear Tracking Turntable.

Your records will sound better than ever with the WO7's highly accurate linear tracking system. And they're easier to play, too. With the Auto Speed Selector, the turntable determines the correct record speed from the size of the record. When Sanyo says "fully automatic," they really mean it!



Flat Speaker System.

There's yet another delightful surprise awaiting you in the WO7—rectangular, flat woofers! Flat, so the sound reaches you with full brilliance. And with the 5cm cone tweeters, sound is reproduced with the realistic balance only a 2-way system can offer. The passive radiator is also flat, and helps deliver powerful bass for a truly vivid musical experience. You can't lose when you're on the winning system—but that's life.



SANYO

That's Life!

The Consumer Electronics Show, August 1-5, in Perth could become a turning point for almost every sector of the consumer electronics industry in this country. Compact disc has been a major success but laservision has failed to take off, the home computer is suffering from savage price competition, but the car sound market seems set for a boom. What might be waiting in the wings?

WHICH WAY NOW?

The Industry asks the Marketplace

Jon Fairall &
Roger Harrison

Hi-fi video. Hitachi's VT-88E VHS video recorder features a dynamic range of 80 dB, full-range frequency response of 20 Hz to 20 kHz and extended 8-hour recording/playback with E-240 tape. It's also got a stereo tuner.



THE MANY 'strands' of the consumer electronics industry can be likened to an octopus — lots of long tentacles reaching out from a central body. There are times when the tentacles, moving independently, move the central body forward, but it seems there are also other times when all the tentacles are frantically active, but no progress is made.

It seems that that's where the Australian consumer electronics industry is at right now.

Reverse in a fifth of a second! Aiwa's AD-R550 auto-reverse cassette deck features an ultra-quick reverse time of 0.2 second! In addition it has Dolby B-C noise reduction and an "edit-assist" function amongst its sophisticated controls. ▶



CDP-101

COMPACT
disc
DIGITAL AUDIO

Hear digital perfection.

Introducing the Sony Compact Disc Player.

When we used our long experience in digital technology to create the CDP-101 Compact Disc Player, we wanted to give you something more than the world's clearest sound.

WIRELESS REMOTE CONTROL Full-function remote control.

3-WAY MUSIC SEARCH □ Instant direct access to any selection with the 10-key pad on remote control unit. □ AMS (Automatic Music Sensor) allows access to the beginning of next or previous selection. □ 2-speed bi-directional search to find any desired music passage.

REPEAT FUNCTION Program to repeat the entire disc, one selection, or a specific portion of music.

3-FUNCTION DIGITAL READOUT DISPLAY □ Selection number. □ Time lapse of selection being displayed. □ Remaining time on the disc.

LINEAR SKATE DISC LOADING Just press the button, platter control and cueing are automatic.

Get even more perfect sound with the Sony Digital Audio Component System, "Precise Series".



SONY

AUD 0391

CD — booster for hi-fi

The hi-fi arm received a good 'booster' shot from the injection of the compact disc last year. Most importers of CD players report they can't get enough stocks — almost regardless of the price bracket of the machines. Funny thing though, it has also given a boost to turntable sales! Buyers who see and appreciate the advantages of the CD player, but for a variety of reasons don't want to get one right now, upgrade their turntable. Coincidentally, there has been a boost in cartridge sales.

For those who've joined the rush to CD, it seems they then find deficiencies elsewhere in their systems and some are coming back to upgrade amplifiers and speaker systems. The occasional customer does it all at once!

The introduction of CD has made the designers and manufacturers of other equipment in the hi-fi stable re-examine their products. As a result, amplifier specifications have been pushed to yet new heights as has the performance and features of things like cassette decks. Prices are dropping, too. Amplifiers with unprecedentedly low hum, noise and distortion figures will become commonplace in the next year. They'll have to, just to match the performance of CD players.

Yamaha's new range of control preamps and power amps — C40/M40, C60/M60 and C80/M80, are a case in point. They boast vanishingly low distortion, hum and noise figures well below that achieved by many previous systems and the peak output levels necessary to cope with the compact disc. Actually, Pioneer was one of the companies to lead the way in new amplifier technology, with their A-8 amplifier (and lower-powered siblings) featuring 'nested feedback loop' distortion-reducing circuitry. In years gone by, you'd pay six months salary for the sort of performance now offered.


The way ahead here is fairly clear — features and performance will go up, but prices will come down. But how far is it *really necessary* to go before the real benefits stop and the sales gimmicks begin? At an engineering conference last year, Professor Edward Cherry of Melbourne's Monash University ably demonstrated that it is impossible for listeners to distinguish between systems with markedly different distortion levels once the distortion is down to thousandths of a per cent.

Some manufacturers now offer specialised 'equaliser' controls on their amps — designed to compensate for the deficiencies of your listening room. These are not new, by any means, but were previously offered mainly as a separate component. It remains to be seen whether equaliser controls will become an issue with the hi-fi buyer.


Cassette decks have improved markedly in performance over the last year or two and



CD for the car? Next move for CD players is to put them in the car. But vibration presents a technical problem with mistracking. Sony have solved that, they say. This is their CDX-5 in-car CD player, released at the US Chicago Electronics Show in June. Who knows when we'll see it here.



August release. Marantz is releasing their CD-84 compact disc player this month. It features an infrared remote control 'commander' and a 24-track programming facility. Expected retail price is \$899.




Amps for the digital age. Sansui's new crop of amps feature 'X-balanced' circuitry to obviate problems with ground-related distortion. The amp circuitry is balanced from input right through to output. The B-2301 here delivers 300 W/ch. at 0.003% THD and has a signal-to-noise ratio of 120 dB, Sansui claim.

in addition, now offer 'music search' and control features rivalling those on the most sophisticated (and expensive) compact disc players. Here too, prices are coming down while performance and features are going up (see the ETI reviews of Nakamichi's RX-202 auto-reverse cassette deck, April '84 issue, and the Aiwa F990, July '84).

It's quite clear that CD will have little effect on cassette deck sales. Until, that is, someone releases the play-and-record compact disc. And that might be closer than you think.

Digital recording (known also as 'PCM' — for 'pulse code modulation') for the domestic market is still in its infancy. At the ▶



Something really new. There are very few record/replay digital audio machines on the market at present. This machine might represent the 'face of things to come'. It is a low cost digital PCM recorder that uses 5 1/4" computer floppy disks on which to record/playback. Thus it has the advantage over compact disc, but it can only accommodate about 20 minutes per side. Compusonic of the US released it at the June Chicago Electronics Show this year. Who knows where it will lead?

moment, it's for the well-heeled, dedicated audiophile who's into recording. But a recent development in the US might just change that. A firm called Compusonic demonstrated at the Chicago Electronics Show in June a digital audio recorder that uses computer floppy discs as the recording/playback medium. Could be an interesting new direction.

VCRs — Japan winning

Video cassette recorders are alive and well in the market place. Model-wise, the manufacturers are going the traditional way — evolving in two directions, upmarket and downmarket. Prices are edging down while features are being retained or enhanced in the lower end of the market. At the top end, sophisticated features and functions are appearing at regular intervals. Stereo sound, however, was only cautiously

released by a few manufacturers, probably owing to the impending introduction of stereo/dual-channel sound for TV stations. Hi-fi video has also been cautiously released, but now that the stereo question has been more or less settled, we'll see a rash of models with 'hi-fi' stereo sound. But laserdisc is hanging pregnantly round the wings.

Meanwhile, a few firms are offering add-on units that dramatically improve the sound on older model VCRs as well as providing pseudo-stereo.

Manufacturers estimate there are about 50 million consumer VCRs in use in the world. They predict the product will be popular for several years yet. About 95% of all machines are made in Japan. Philips VHS VCRs sold here are made by Sharp.

Heavy promotion and aggressive marketing are given as the keys to the success of the Japanese. They first develop the basic product carefully and take an evolutionary approach to improvements. Thus, consumers are encouraged to buy new models as the additional features meet their needs (like infrared remote controls, hi-fi sound,

Laserdisc — when?

We have seen some five releases of laservision here in as many years. And it's still waiting in the wings. Pioneer's history of attempting to launch the product here reads something like a mirror-image of Nellie Melba's farewells! Full marks for trying, though.

The confusion over standards in videodisc, the high introductory price compared to competing products (which would include swimming pools) and the sophistication of the technology has probably held the consumer at bay. As the sophistication of other consumer electronics products grows and grows, it shouldn't be too long before it approaches laserdisc, at which stage public acceptance should rise to meet it. The compact disc, the latest crop of VCRs and the home computer, all well-accepted items now, should contribute to the acceptance of videodisc. But just when that's going to happen is the \$64 million question.

The play-only facility of laserdisc is seen as a possible drawback, but it's been no bar-

DON'T LET YOUR DINGLE-DONGLE DANGLE IN THE DIRT

The irrepressible Sir Clive Sinclair (British consumer electronics whizz more famous than Dick Smith and with a knighthood who has actually designed and manufactured products for sale), has the US computer market on a string.

Or maybe it's that he's stringing them along.

At the Chicago Summer CES this year, he showed off his QL (for 'Quantum Leap') home computer. He had just four on display, securely locked under plastic covers with just the keyboards showing.

Interested trade buyers were reportedly impressed by price and performance. But they didn't notice, and the Sinclair sales staff were omitting to mention, the little dingle-dongle hanging on a wire string out the back of the machine. Packed in there was the ROM Sinclair's engineers couldn't fit inside the case. Tsk, tsk.

28-day multi-programme programming etc). The consumer is not forced to buy through rapid obsolescence. Philips made this mistake with their V2000 system in Europe, and paid for it (see accompanying panel).

rier to CD. The market relationship between audio cassette recorders and record/CD players should be mirrored in the video market between VCRs and videodisc. But the question is, will it? And if so, when?

AH SO. HONOURABLE FOE

The Dutch electronics giant, Philips, has admitted defeat and bowed to the rising Sun. Having invented the world's first domestic VCR over a decade ago, Philips has had to bow to the might of Japanese technology and marketing. It is now selling Japanese-made (from National Panasonic) VCRs in Europe in direct competition with its failing V2000 system. They've been selling VHS VCRs, made by Sharp, in Australia for almost the past two years.

When Philips launched its V2000 domestic VCR system in Europe in 1979, it had damn near 100% of the market. The Japanese "video home service" (hence, VHS) came in late two years after them and rapidly stole 70% of the market (Beta came later still and only got a minor share there).

Philips' V2000 market share dropped to around 2% by last year so they went to Matsushita (National Panasonics' parent) last December and got a quarter million VHS machines to sell in Britain as a stop-gap.

Philips' factories in Austria and West Germany are currently assembling Matsushita VCR kits prior to tooling up to make their own components.



The picture here is from a British advertising billboard!

Home computers — a shakeout?

The home computer market is going through a bust overseas. The giant Warner Brothers' Atari home computer division has hit hard times and laid off over a thousand workers and pulled in the reigns heavily over the past nine months. Texas Instruments' TI-99/4, dubbed the 'Ti-tanic' by some sections of the industry, is no more and TI has had to close plants down. Tandy's TRS-80 MC-10 Color Computer lasted less than six months in the market place before they had to start 'sale-ing' it out at around a quarter its introductory price. Commodore's VIC-20 will be discontinued but had a dream run of around *five years*. The C64, popularly voted the best home computer in a magazine reader survey conducted in the US and Europe earlier this year, dominates the marketplace and certainly has the most prolific support from 'outside' software and hardware add-on producers.

The signs of what happened in the CB market shakeout a few years back — savage price competition, followed by rapid model run-out, then steeply falling sales — are all there in the bottom end of the home computer market at the moment.

The industry has a buffer, however. The bottom end of the home computer market is



Into the serious stuff. Atari's push into 'serious' computing in that no-man's land between the bottom-end 'toys' and the upmarket business machines is their 800XL. It features 64K of memory, thousands of programs available and the disk system option runs the popular CP/M operating system. It's also a NSW Education Dept. preferred computer.

HOME COMPUTERS: SHAKEOUT OVER?

According to Atari's Australian distributor, Futuretronics, the company has lifted its March sales figures for home computers to more than double its December '83 sales.

Atari's US market share in December was reported as 11.6%, but it rose to 23.2% in March. Futuretronics says that Atari and Commodore now account for almost 70% of the under-\$1000 US home computer market between them. So it looks like the shakeout is over.

The closeout of opposition manufacturers, allowing a degree of stability to return to the market, is the reason for Atari's lift, according to Futuretronics' Managing Director, Peter Alpar.

"BREATHE INTO THE BAG, SIR"

Controversial US hi-fi equipment designer, Bob Carver, has pulled another of his now-famous shrinking tricks.

He first shrunk the monstrous hi-fi power amplifier to the volume of a couple of house bricks with his M-400 'cube'. This product used his power-switching 'magnetic amplifier' technique that delivers power output only when the input signal demands it. In this way he eliminated the huge heatsinks and heavy transformers necessary in conventional hi-fi power amp designs. The M-400 delivered 200 watts per channel.

At the Chicago Summer CES in the States this year, he produced a *beer-can sized* stereo amp that delivers 200 watts per channel! Carver says he did it to prove that the technology exists.


Dubbed the 'Cubelet', he will not be selling it because he says it will cost at least US\$1000 and be a throw-away item if anything went wrong. The components are nested together inside a metal case and potted with resin. Apart from that, here, the law wouldn't believe it.

"But officer, I didn't have the volume wound up past 2!"




Get behind the wheel. Video games are alive and well, led by CBS-Colecovision. The popular Colecovision games unit can be turned into a racing car cockpit with this add-on "Turbo" module.

The game's graphics really puts you behind the wheel at Indianapolis.



IT'S BEEN WORTH WAITING FOR.



Pioneer's extraordinary second generation Compact Disc Player is here.

Time flies. Only 18 months ago, the hi-fi world was stunned by Pioneer's Compact Audio Disc player. Its laser and digital technologies introduced near-perfect stereo sound reproduction. "How will they top that?", they asked.

With the extraordinary new PD-70, Pioneer's second generation Compact Disc player.

We started by making the compact disc player more compact. The PD-70 loads horizontally (not to mention automatically), making system mounting much more practical.

The PD-70 is also an incredibly stable compact disc player. Comprehensive internal damping and robust construction means the PD-70 won't "skate" during operation.

The PD-70 is more intelligent too. Its memory can be programmed to repeat tracks up to 10 times and that programme can be interrupted or amended at any time.

The PD-70's 16-bit Digital Binary Display is the most sensitive and versatile metering system yet devised.

It breaks signal values down into 6dB increments - and switches to a 'peak metering' mode at the touch of a button.

And, because all of the displayed information is both sourced and expressed digitally, the PD-70 can claim to have the most accurate metering display system available.

The PD-70's specifications speak for themselves: Dynamic range has been improved to 95dB. Signal-to-noise ratio has been improved to 95dB. T.H.D. is down to 0.004%, 1kHz.

Compact Disc has taken the next step. Pioneer's new PD-70 gives you music that is virtually distortion free, and laser technology means that your music need never deteriorate.


Pioneer's PD-70 means simply better stereo sound; a step closer to musical perfection.

In our opinion, that's always worth waiting for.

 **PIONEER®**

Leads the world in Sound and Vision.

Smart electronic components for your next challenge



Maybe you're not preparing Australia III for the next cup challenge, but if you're an Australian manufacturer you are well aware of the international competition that you face. Their strategy and techniques to drive you out of the race will be very crafty indeed.

Perhaps you're wondering, "What could electronics really do for my product?" Up to this point, you've got by very nicely with conventional solutions. But just for a moment, think about the benefits you could offer your customers. If you build a unique product that has intelligence and is better suited to your market requirements, your product could stand head and shoulders above the rest.

Now, if you have considered electronic solutions before, but your production manager and technical advisors have said it's just not feasible to pay for the development of specialist electronics, then things have changed.

Our catalogue of 200,000 products, in conjunction with our local design laboratories, offer options and solutions to Australian manufacturers. We offer "hybrid technology" using discreet chip components with, standard or custom designed, integrated circuits. A specialist design group and factory right here in Australia can quickly give you a unique customised electronics package. Something very difficult for your competitors to copy.

Take the lead. Don't wait for your competitors to make a dash for the line, because you can win the tactical battle and carry off the prize.

Philips Elcoma are keen to join your crew.

Phone us in:

Sydney **427 0888**

Adelaide **243 0155**

Brisbane **44 0191**

Melbourne **542 3333**

Perth **277 4299**

We make electronics in Australia



**Electronic
Components &
Materials**

PHILIPS

CONSUMER ELECTRONICS SHOW



A keyboard genius. Lowrey's Model G100 'Genius' electronic keyboard instrument is claimed to be the forerunner of a completely new generation of electronic musical instruments. It offers ten voices, from piano to synthesiser, plus cartridge software to give you differing style or rhythm formats. A 20 W amp is built-in.

really chock full of 'toys'. Once the boom 'trendy/curiosity' phase is over, and it seems imminent, then the 'useful' computers will find their place as virtual 'tools' in the home. Consumer spending will move up-market once again. That's already started to happen, in fact. Those machines in the 'no-man's land' between the \$99-\$299 toys and the \$2000+ business machines are enjoying strengthening sales at present. They're no toys and it's the 'educated/aware' consumer buying them for self-education, wordprocessing etc. Many are second-time buyers upgrading from a toy they've dabbled with over the past year or two.

The industry is only just beginning to tap the vast education market and this will be another chink in its armour against the shakeout at the bottom end.

What else?

The next product area slated to make big inroads in the home electronics scene is — electronic musical instruments; keyboard

instruments in particular. Electric/electronic home organs and pianos have been around for yonks. But they have traditionally been big-buck items, the purchase decision always riding behind the second car/dishwasher/pool etc.

Digital electronics, advances in technology and mass production have dropped the prices and dramatically upped the features while allowing the development of a broad product range. It's the same old story that's happened with every other sector of the consumer electronics market.

The 'toys' appeared about 18 months ago, pioneered by Casio (the calculator people) and Yamaha. Roland, big in the pro music scene, has produced both an electronic piano and a synthesiser under the 'magic' \$500 price point, for example.

Car sound, too, is getting ever more sophisticated while the prices are moving both up and down market. Car CD players, fondly test-marketed by Philips, National, Mitsubishi et al, will likely make a real

appearance in the next twelve months.

Meanwhile, top-of-the-range car radio/cassette players get evermore features and better in performance. Pity the cars don't.

Stereo/dual-sound for television looks likely to give 'the box' a long-deserved shot in the arm. (See article elsewhere in this issue). At present, the cost of stereo TV sets launched onto the market is high. But, initially at least, importers/manufacturers are looking to sell them as 'second or replacement' sets. The current models featuring stereo with hi-fi sound are all top-line products, with a host of other sophisticated features accounting for the high prices. Later, lower-priced models with fewer features will sport stereo sound. Conversion units are available for some existing sets, but are relatively costly and this is not seen as a significant market (or maybe they don't want it to be!).

Personal hi-fi products — Walkmans, 'ghetto blasters' and the like — have rapidly found their market since being introduced over the past two years and it's all fallen rather flat. No significant new developments are on the horizon so it seems this line of products is ripe for innovation. But what?

The question

The question is now, will the market point the way ahead or will the industry find something to excite the market? It seems to us that the ball's in anybody's court. He who serves first will win the service, no doubt. ●



Digital-age speakers. The Danish-designed Jamo speakers feature a unique bass-reflex design with the port venting around the woofer rim. The model 1702 is shown here.

HOLD IT!

Anywhere you want it...

SCOPE PANAVISE

Work holding system with Interchangeable heads and bases.

1 TAKE A BASE

NOTE 300 & 305 CAN BE SCREWED DIRECT TO BENCH

300
BASE

315 PCB HOLDER

312
TRAY



300



305



380



336

380 VACUUM BASE

Moving the black-tipped lever arm attaches the Vacuum Base instantly with a firm grip, without marring, to smooth non-porous surfaces.

300 STANDARD BASE

Holds all regular PANAVISE heads and Circuit Board Holders. The patented load control knob and exclusive split-ball feature have a range of tension which permits moving of work to any position desired.

336 UP/DOWN CONVERTER BASE

An attachment for the 325 Up/Down Positioner giving the additional dimension of variable height (14" or 355mm).

305 LOW PROFILE BASE


The Low Profile Base has all the tilts, turns and load control features as in the Standard PANAVISE base. Only 2 1/2" (64mm) high.

2 ADD A HEAD


5 INTERCHANGEABLE HEADS tilt, turn and rotate, then lock in any position.




303




315



366



337



376

303 STANDARD HEAD

The top selling head, it has jaws 2 1/2" (63.5mm) wide which open 2 1/4" (57.2mm). The tough yet gentle nylon jaws have a satin finish to improve grip.

315 CIRCUIT BOARD HOLDER

(Extra Arms Available)
Holds p.c. boards any shape and size to 12" (304mm) wide (including the S100) exactly where you want them - flat, vertically, or any angle in between, when used in a PANAVISE base.

366 WIDE OPENING HEAD

Opens a full 6" (152mm) with jaw width of 1 1/4" (44.5mm). The contoured neoprene jaws provide a cushion over the steel jaw plates to gently yet firmly hold delicate items.

337 FIXTURING HEAD

Permanent fixturing for production line assembly or repetitive repair work can be designed and bolted to this head easily with its six slots and bolt holes. The flat ground surface is 5 1/4" (137mm) in diameter.

376 SELF-CENTERING HEAD

'Extra Wide Operating Head' Double Action Jaws. Allows fast opening and closing. Large Capacity - Opens to a full 9" Reversible Jaw Pads - Flat one side Fits all PANAVISE series 300 bases.

HERE ARE SOME TYPICAL COMBINATIONS

303



300

303




380

366




300

304



300

315



380

AVAILABLE FROM:

N.S.W.

Geo. Brown & Co (02) 519 5855
Pauls Merchants (02) 709 2311
Scruttons P/L (02) 667 0511
D.J. Coulter (049) 67 1455
J. Blackwood (02) 609 0030
A.E. Baker (02) 621 0044

WESTERN AUSTRALIA

Atkins Carlyle (09) 277 0511

VICTORIA

Radio Parts Group (03) 329 7888
(03) 211 8122
Geo. Brown & Co (03) 419 3986
Ellistronics (03) 602 3499
Ames Agency (03) 328 3001

TASMANIA

G.H.E. Electronics Hobart 34 2233
L'ton 31 6533

QUEENSLAND

L.E. Boughen & Co (07) 369 1277
Fred Hoe & Sons (07) 277 4311
Delsound (07) 229 6155

SOUTH AUSTRALIA

Gerard & Goodman (08) 223 2222
Protronics (08) 212 3111
A.J.F. Electrical Dist. (08) 269 1244
Graphic Electronics (08) 42 6655



SCOPE
BOX 63 NIDRIE
VIC. 3042
TEL: (03) 338 1566
TLX: AA38318

The military coup



of Lieutenant Wilson. Aged 20.

When you talk to Geoff Wilson about his 18 months in the Army you can't help but feel he's a young man who's come a long way in a short time.

Already he's graduated from Officer Cadet School, Portsea, with a commission as a Lieutenant. And already he commands an Infantry Platoon of thirty men.

It's a tremendous responsibility. Especially for a 20 year old. But as Geoff says, "You get enormous satisfaction from using what you've learnt in your training to help bring out the best in your team. And in achieving results together."

"Obviously situations which I haven't had experience in crop up all the time. And that's when I have a real responsibility to myself and my men to make decisions based on sound knowledge rather than guesswork. As a result you constantly find yourself learning and mastering new skills. And that's a challenge I always enjoy accepting. You really begin to realise your full potential and believe in your ability."

"I suppose you might say my decision to take on a career as an Army Officer is my personal 'military coup'."

"It's hard to visualise another career as exhilarating, varied and satisfying. Or which provides as many opportunities to be recognised and rewarding for a job well done."


"Think about it carefully. I know I did before joining!"

Armour, Artillery, Engineering, Survey, Signals, Transport, Infantry, Intelligence and Aviation are just some of the fields open for you to enter.

If you're aged between 18½ and 23 on the first day of the month in which the course commences (or up to 25 with a degree or diploma), have your HSC or equivalent, (at a level acceptable to the Army), and think you have what it takes to pull-off your own military coup, contact your nearest Army Careers Recruiting Centre or fill in the supplied coupon.

There are two courses per year. Applications close mid-March for a July entry and early August for a January entry.

For more information post coupon to GPO Box XYZ, in your Capital city. Sydney 2195555, Newcastle 25476, Wollongong 286492, Albury 552248, Lismore 21 6111, Canberra 822333, Melbourne 6979755, Geelong 21 1588, Bendigo 438008, Ballarat 31 1240, Brisbane 2262626, Townsville 724566, Adelaide 2121455, Perth 3256222, Hobart 347077, Launceston 31 1005.



Name _____
Address _____
Postcode _____ Phone _____
Birthdate _____ Educ. Std. _____

Army Officer. A leading profession.

All enquiries treated in confidence.

OCS 14-DPS.44

Imagine a stereo television with more features than MGM.

The last bastion of mono sound has fallen.

Stereo has come to television with stereo films, stereo concerts, stereo sports broadcasts. Even the weather will soon be in stereo.

Just one thing before you buy your stereo TV. Don't only listen to the sound; look at the picture.

Philips and only Philips have the famous Natural Colour picture to match the Natural Stereo sound.

Stereo is just the tip of the iceberg. Each Philips stereo set is a treasure trove of new features, accompanied by a dictionary full of new terms.

SPATIAL STEREO.

While the kids are hogging the front of the screen you can sit to one side and still hear perfect stereo.

The Philips amplification system electronically enlarges the stereo effect spreading the sound throughout the room.

ENHANCED SPATIAL MONO.

The stereo you have when you're not having stereo. Of course at first many TV programmes will still be in mono.

But this Philips invention separates the sound signal by frequency into two groups and pumps each group to a separate speaker. Dramatic sound, even in mono.

VST.

It doesn't stand for Very Simple Tuning, but it could.

Every Philips Stereo Television is pretuned to all mainland capital city channels. But tuning for places where frequencies are different, or to tune a VCR is as easy as pressing a button.

No more twiddling little wheels and knobs. This Philips system automatically searches the airwaves, finds a channel and then stores the frequency. So every time you switch on it's perfectly tuned.

TELETEXT.

Teletext is like a push-button newspaper. With Teletext you can receive pages of constantly updated information. And for the hearing

impaired, Supertext Subtitles on programmes can be received.

Teletext today (buy it already fitted), or tomorrow (an optional kit can be fitted when you're ready).

FRINGE SWITCH.

Out of town no longer means out of tune.

For people living in fringe areas which only get weak signals, a switch dramatically improves the reception by boosting the power of the signal once it's received.

BILINGUAL SWITCH.

Here's a feature for the future. Already channels are gearing up for dual language broadcasts.

When two languages are being broadcast, you'll be able to switch from what you'd normally hear to hearing the other language.

RGB.

An invention which cleans up TV graphics making them crystal clear and razor sharp.

Because now add-ons like video games, computers and Teletext avoid all the broadcast circuitry and plug straight into the high resolution picture tube.

EXTRA PLUGS.

Plugs that mean that your Philips

Stereo TV will always be the state of the art.

Use the Scart plug to connect either a VCR, videodisc, computer or hi-fi system to your TV. It is also vital for direct satellite broadcast reception.

A DIN plug means that with one connection you can play TV sound through your hi-fi system.

A headphone socket means that you can listen at a higher volume or to a different language, without disturbing the rest of the family.

And yet another plug allows you to connect extension speakers, for even greater stereo sound separation.

REMOTE CONTROL.

The whole shooting match is controllable from the most sophisticated remote control ever created.

Everything from Teletext to bilingual selector to left-right stereo balance is incorporated into this one little box of tricks.

THE BIG DECISION.

When you come to buy your stereo TV do three things. First use your ears; can you hear Natural Sound? Then use your eyes; can you see Natural Colour? Finally use your head; does it have the features for today and tomorrow?

Only Philips has all three.

Philips stereo television.




We want you
to have the best

PHILIPS

PMPV176

STEREO TV

*Good sound cometh
Says the minister*



SOUND HAS ALWAYS been the poor cousin of TV. Conceived in a lo-fi world, the receiver industry has matured with tacky little speakers and more of a sound disaster than a sound system.

But times, as Dylan said, are a-changing. Hi-fi stereo sound is now available on all but the cheapest music systems in Australia. Whether the music is pre-recorded or broadcast, we expect it to sound good. Even lowly AM radio is trying to improve its image with a new generation of wideband receivers on the market, and the promise of

Jon Fairall

stereo waiting in the wings.

The sluggard in all this has been TV. In spite of a wideband FM sound signal TV audio still manages to sound as if it was recorded in a bathroom. One move to overcome the problem has been to link the programme sound with a stereo FM radio transmitter in a so-called *simulcast*. Such an approach works well, but it is expensive, both in financial terms and in terms of spec-


trum usage.

A far more sensible approach is to record and transmit the original programme material in stereo and try to persuade TV receiver makers to pay some attention to audio design.

Recently there have been signs that these moves are all taking place. A number of TV sets have appeared in recent times with good quality speakers mounted in well-designed enclosures; albeit small, but it is a start. And at long last, stereo TV is a reality.

But not on the ABC

THE SOUND THAT SURROUNDS



The Philips KR 863 Stereo TV. This model is typical of the new generation of television set that has been released within the last year or so. As well as exceptional video qualities which result in a fine resolution, high brightness picture, it also offers tremendous audio potential.

In the standard mode it has twin outputs capable of delivering 10 W RMS into 8 ohms. However, there is provision for sending the audio to an external amplifier, and thus the integration of the TV into a hi-fi unit, where it would form part of a total entertainment centre.

The idea of the entertainment centre is that all the typical domestic electronic components should be compatible with each other, so that the TV, VCR, record player, and cassette deck can all be played through one amplifier and one set of speakers. To get around the limitations imposed by the programme material, the KR 863 has the ability to synthesise stereo when receiving mono transmissions.

We'll be reviewing this TV set in next month's issue — don't miss it!

In the beginning

The first experimental transmissions were made, predictably enough, by the Japanese national broadcaster NHK, in 1978. Other countries have been playing with the idea as well. In 1981 the West German broadcaster, IRT of Munich, began transmissions using a system totally different from the Japanese. The BBC have also developed a system of their own.

With so many different systems competing on technical, political and financial grounds, it has been impossible to develop an industry-wide set of standards for the implementation of stereo TV sound. The big standards committees like CCIR and the EBU seem content to sit on the fence until the dust settles a bit.

In Australia, a decision has been made to adopt the German system. In December 1983 Michael Duffy, the Minister for Communications, announced that his department was prepared to undertake the licencing of two-channel sound transmission that conformed to the standards laid down by the Germans. They seem, on the basis of present knowledge, to offer the best performance characteristics of the competing systems.

The choice that had to be made was between the Japanese and German systems. The BBC system, called *sound on syncs*, was probably the most technically sophisticated, and probably offered the greatest potential for development, but it was ruled out of court as being too difficult to implement.

The Japanese system is called *FM/FM multiplex*. Essentially, it involves a double system of modulation in which the original carrier is modulated by a second sub-

carrier. Tests carried out overseas seemed to show that the second sub-carrier was badly affected by multipath distortion and had a considerably worse signal-to-noise ratio. (About 10 dB, in fact).

The third alternative, the one selected for Australia, is called the *dual carrier method*. It seems to have significant advantages over the other systems. Proponents say it is easy to graft onto an existing system, it offers identical performance on both channels, and most important of all, it is cheap for both broadcaster and consumer.


The dual carrier system

To understand how the system works, consider the construction of a typical TV channel in Australia. The channels are 7 MHz wide, situated in 'bands' in the VHF and UHF regions of the spectrum. Within the channel, all the components have the same relative positions so that we can express the frequency of the various components with respect to the bottom edge of the channel.

On this basis, the most important element in the channel, the vision carrier, is situated at 1.25 MHz above the 'bottom' channel edge. It is amplitude modulated by the luminance information, the sync pulses and a number of other carriers. All this requires 5 MHz of sideband, so if nothing further were done we would need a 10 MHz wide channel to accommodate both the upper and lower sidebands. However, there is no need to transmit one sideband, since the same information is contained in both of them. This is the rationale behind single sideband radio.

However, the single sideband approach is not viable in television, since it involves a sharp filter to attenuate one sideband while leaving the other intact. Unfortunately, it is impossible to design a filter without creating some phase distortion in the roll-off region. This is not a problem in radio, where the low frequencies carry very little information. But in TV it is disastrous, since the low frequency video signal is where most of the picture information is transmitted.

The answer is to compromise between the two systems. The lower sideband is attenuated by a filter, but not too sharply, and not at a rate that induces phase distortion into the upper sideband. In practise, this means that all the upper sideband, the picture carrier, and about 1.25 MHz of the lower sideband, get transmitted. The system is known as *vestigial sideband transmission*. (to page 33) ▶



What's new in electronics distribution today?




TREVOR EVANS -

General Manager


Highly experienced in electronics component parts, sales and supply. Entered the industry in Britain with Electronic Engineering qualifications before representing major companies, such as RIFA, STC and PLESSEY in Australia, marketing connectors and semi-conductors for 17 years.

**LES SHORT**

After gaining trade qualifications, spent 12 years as a service technician and manager. Put this practical and theoretical insight to good use with PLESSEY and UTILUX in sales representation for 14 years before coming to Ace Electronics.

**PETER STEEL**

Impressive track record in the industry since he gained college qualifications in Electronics and Communications. From Purchasing Officer in Mining and Manufacturing, spent 11 years with AWA and EMI in electronics, and a further 9 years with RIFA as a sales representative before joining Ace Electronics.

**NARELLE BOWER**

Hails from Dubbo and, post studies at a metropolitan business college, gained 3 invaluable years experience in customer liaison with an import, manufacturing and distribution company as a Secretary and Administrator.



Reliability and expertise in customer service.

Ace Electronics was formed to meet the specialised needs of the electronics industry in Australia today. We live in exciting times of potential growth, where automation and sophisticated data collation, retrieval and control have an increasingly important role in business management at all levels.

With the Australian economy showing signs of recovery, today's industries demand distributors with a wide knowledge of available technology, a comprehensive stock of components, prompt delivery efficient service and keen prices.

You, our customer, can only benefit from our ability to fulfil these demands now and in the future.

Trevor Evans

**SUE TINYOW**

A Sydney Accountancy student with already more than 4 years experience with import and export companies in the electronics industry. Handles Ace Electronics extensive stock control and other computerised systems like a veteran.




A new name behind the top electronic products in Australia.


Ace Electronics - established to bring the latest electronic technology and components of world industry leaders to your fingertips. We already represent Robinson, Nugent, Fairchild, Taiwan Liton and Dowty (UECL) and have orders placed initially for over one million devices.

But that's just the start. Negotiations with other international component manufacturers are increasing our impressive inventory - arguably the largest offered by any single supplier in Australia. Details of these new agreements will be released immediately they are finalised.

Our financial resources ensure that our service to the electronics industry in Australia will be long term. We're here to stay. You can count on it. Whether your particular need as a designer or engineer is a micro-chip from Maryland or an actuator from Albuquerque we can save you time and money. Our on-line warehouse and fully computerised stock and accounting system puts a comprehensive choice of electronic components and computer products from world-wide manufacturers on your doorstep, backed by staff who are fully familiar with the latest American, European and Asian advances.



**RN ROBINSON
NUGENT, INC.**



NEW LEADLESS CHIP CARRIER SOCKET

- To accept new generation of memory devices which occupy minimal PCB area.
- Open design allows maximum thermal performance and easy testing.
- Lid incorporates heatsink.
- Positive polarization and keying.

TAIWAN LITON ELECTRONIC CO. LTD.


Manufacture a large range of high quality, low cost LED products.

Including discrete LED indicator lamps, single and dual numeric displays, dot matrix displays, clock displays and other customer designed products.



**DOWTY
UECL**

INDIRECT PRINTED
CIRCUIT
CONNECTORS



Features

- Designed to conform to BS9525F0004 and DIN 41612 Types B and C
- Inlaid gold on contact zone
- Twin cantilever socket contacts
- Flame retardant and solvent resistant polyester mouldings
- Full or partial contact loading available
- Choice of contact finishes
- Pre-tinned solder terminals - standard on pins, optional on sockets
- Premating earthing contacts available
- 0.6 mm section PCB terminals

Mechanical Endurance: - (engaging and separating)
Up to 500 operations with 1.9 µm gold

ACE

ACE ELECTRONICS PTY. LTD.


69-75 Reservoir Street, Surry Hills, NSW 2010,
Sydney Australia

Telephone (02) 211 1144 Telex AA75160 ACESYD

AN ALL AUSTRALIAN COMPANY (Inc. in N.S.W.)

FAIRCHILD

ONE OF THE WORLD'S LEADING SEMICONDUCTOR MANUFACTURERS



CMOS CIRCUITS DIGITAL CIRCUITS LINEAR CIRCUITS
MOS MEMORY MICROPROCESSOR TRANSISTORS
DIODES CHARGE COUPLE DEVICES HYBRID CIRCUITS


FAIRCHILD

A Schlumberger Company



ACE ELECTRONICS PTY. LTD.
69-75 Reservoir Street, Surry Hills, NSW 2010,
Sydney Australia
Telephone (02) 211 1144 Telex AA75160 ACESYD

AN ALL AUSTRALIAN COMPANY (Inc. in N.S.W.)



2,187 CHOICES

In IDC Connectors, **RN** gives you "The Choice."

Nobody can match the 2,187 choices that RN offers in IDC Flat Cable Connectors! Surprised? Many people are. But, if Robinson Nugent hasn't got it, you probably don't need it. Whatever you do need in IDC Flat Cable Connectors, you are safe in making RN your choice. There are 2,187 chances that we have it off-the-shelf, ready for delivery today.

Advanced manufacturing techniques make it possible to price our IDC Connectors very competitively and assure you of consistent prompt delivery. And every single IDC Connector in the RN line intermates with other major suppliers. Whatever you are now using—you now have the "RN Choice."

ROBINSON NUGENT PTY LTD

(Incorporated in New South Wales)

P.O. Box 429, Epping, N.S.W., 2121. Telephone: (02) 875-2566. Telex: 70962

Check the wide variety of RN IDC Connectors.

SOCKET CONNECTORS: Two pin grid options available (Standard .1" x .1" and new backplane .1" x 2").

HEADER CONNECTORS: Partial and fully shrouded types.

LOW PROFILE HEADERS: Fully shrouded and unshrouded types.

TRANSITION CONNECTORS: Available with both staggered pin pattern and new space saving dual-in-line pattern.

"D" SUB MINIATURE CONNECTORS: Popular all plastic versions, both male and female types.

CARD EDGE CONNECTORS: Variety of mounting options including slotted and through hole flange.

CABLE PLUGS: Available with strain relief and retaining clips for rugged applications.

CABLE: Five styles available: standard grey, color coded, ground plane, ground plane with drain and shrouded jacketed.

OPTIONS: Strain reliefs, polarizing keys, lock and ejection latches and mounting hardware are available options for RN IDC products.

RN offers many unique advantages.

- State-of-the-art plating technology minimizes use of gold, reduces costs.
- Two contact options: economical phosphor bronze or beryllium copper for maximum reliability.
- Compatible with MIL-C-83503 specs.
- Semi-automatic terminating equipment cuts assembly costs.
- Available worldwide thru local stocking distributors.



**Robinson
Nugent**

Vestigial transmission has a number of advantages. Firstly it reduces the bandwidth required for the channel to a satisfactory 7 MHz. As a bonus, it also concentrates signal power in the low video frequencies where the most important video information is located.

The upper sideband, as already mentioned, contains all the luminance information necessary for the creation of a monochrome picture. The colour information is carried on a sub-carrier at 5.68 MHz from the channel's bottom edge. The sound information is also on a sub-carrier, located at 6.75 MHz from the channel edge.

The German system involves placing another carrier at 6.992 MHz from the channel bottom and then decoding it in exactly the same way as the 6.75 MHz carrier. Whatever else may be said of it, this way of doing things ensures that the two sound signals have exactly the same characteristics.

Both the sound carriers (called Sound 1 and Sound 2) are frequency modulated, the maximum deviation being 75 kHz. The bandwidth of the baseband signal is 40 Hz to 15 kHz. Sound 1 is transmitted at a level 13 dB below the picture carrier. Sound 2 is 20 dB down. This difference in level reflects the fact that both sound carriers are crowded into the top of the channel, and care has to be taken to stop the second sound carrier from interfering with the adjacent channel higher in frequency.

The processing of the two sound signals is done in an entirely conventional way. The only difference is that additional circuitry is needed for the second IF strip, the audio detectors two-channel decoding and amplifiers.

The demodulated picture carrier infor-

mation is available at the video detector. From here it is fed to the various sections for processing. The sync separator seizes the sync pulses, the video amplifier the luminance information and the chroma amplifier the colour information. The sound is picked off by two resonant circuits, the traps.

Since the sound carriers always have a constant relationship to the picture carrier, they will 'beat' with it in a constant manner, irrespective of the channel of reception. For Sound 1, this is $6.75 - 1.25 \text{ MHz} = 5.5 \text{ MHz}$. For Sound 2, this is $6.992 - 1.25 \text{ MHz} = 5.742 \text{ MHz}$. By tuning the traps to these values it is possible to select both carriers, and then to further select and amplify them in IF amplifiers.

In order to obtain the baseband sound signal it is now necessary to demodulate the output of each IF stage, just as in a radio. Usually this is done by a ratio or quadrature detector. The output from the detector can then be fed to the stereo matrix decoder.

The matrix encoding of the signal is necessary because the stereo signal is not sent as left (L) and right (R) channels, but as (L+R) and R. This is done so that mono receivers can still receive the full sound system on the first sound carrier (L+R), thus retaining compatibility. These two signals are fed into the matrix where the appropriate subtraction is done to derive L and R.

One of the main advantages of this way of doing things is economics. Stereo transmission is simply an add-on to existing equipment and facilities. In the domestic receiver it means no more than the inclusion of a few components. (But that's not the same as saying that stereo TV sets will be cheap). The commercial television stations have




Diagram 2. Detecting the dual carrier sound system to produce stereo or dual-channel sound.

... AND THE US GOES ONE BETTER

THIS MONTH, television broadcasters in the US plan to start transmitting stereo sound. But the technology they're going to use will be quite different to the Japanese, British and German systems (the last of which has been adopted here). The US system will allow no less than *three* channels of sound to be transmitted — two channels for stereo and a third channel for separate audio programming, such as a foreign language.

In addition, a noise reduction system will be employed to improve the signal-to-noise ratio on the sound channels. This will be a system from the Massachusetts-based firm of **dbx** which makes noise reduction systems for hi-fi equipment (tape recorders in particular). All US TV manufacturers will have to take a licence under patents to dbx. This, along with the different technology, is hoped to shield the manufacturers against heavy foreign competition.

In the US system, the normal sound carrier signal will convey mono sound (R+L) that can be received by any of the existing 130 million sets. A sub-carrier will provide the extra information needed to produce stereo sound (left and right), rather like the Japanese approach. A *second* sub-carrier at a much higher frequency provides for the third audio channel. This channel can carry complementary commentary to the stereo programming in another language, for example, or sound dubbed from a foreign film.

The twin sub-carrier system, transmitted in the space originally allocated for the mono sound carrier, caused problems of background hiss and whistle. By treating the two added sub-carriers with a modified version of the dbx noise reduction system, developed to reduce tape hiss, the problem is overcome. At the transmitter, quiet sounds are made louder before being broadcast so that they stand proud of the background mush. A 'mirror' circuit in the receiver cuts them back by the same amount, so losing the mush.

leapt at the chance to increase their appeal and in the first six months of licensing, the Department of Communications has licensed five stations: Channel 9 in Sydney, Melbourne and Perth, ATN 7 in Sydney and WIN 4 in Woollongong.

The public broadcasters have been a bit more conservative. Both the ABC and the Special Broadcasting Service (SBS) are acquiring the equipment necessary to record two-channel sound, but government sponsored restraint, and concern about the standards adopted, has made them hesitant.

The SBS, of course, has a special interest in stereo because of the possibility of becoming the world's first multi-language transmission channel (as well as the world's first multi-lingual, if you see the difference).

The dual carrier method of stereo broadcasting gives a worst-case cross-talk figure of 40 dB, according to the Department of Communications. While not spectacular by modern hi-fi standards (compact disc players are quoting 80 dB these days), it is sufficient for the job the SBS require of it. Thus it would be possible to use one channel for an original programme voice track, and the second sound channel for an English translation. Current SBS policy, however, is that this would be limited to foreign language documentaries. French film buffs can relax.

TAKE A SHORT 20,000-HOUR DRIVE.



And wave goodbye to the competition. Presenting the Shugart 712. Our new 5.25" half-height 10 Mbyte Winchester.

It's high performance compact that redefines reliability. So much so, it outdistances all other half-height Winchesters.

For starters, it runs at an MTBF of 20,000 power-on hours. That's 60% longer than other drives.

And it's roomy. With 10 Mbytes of formatted storage.

Plus four-point shock and vibration mountings, for a very smooth ride. And rugged enough to withstand up to 40 G's.

The 712 is based on 3370 flexure technology, bringing mainframe horsepower down to size.

And our new, low-mass head design complete with pre-amp is standard equipment, too. This makes flying height more uniform. And data integrity a given.

All this was made possible by our venture group approach. A specially chartered engineering and manufacturing team that

makes sure the bugs are out the first time out.

And we make sure they have everything they need. Like the \$40 million investment we made in capital equipment.

Which includes more progressive assembly lines. Class 100 clean tunnels. Even a more advanced spindle motor.

In short, everything you need for single-user personal computers. Intelligent workstations. And, down the road, multi-tasking software.

You won't have to reinvent the wheel every time you want to redesign, either. Thanks to our 1600 controller with built-in SCSI. Plus the drive level interface standard.

So test drive the 712 today. Or its 5 Mbyte version, the 706.

Contact your local Warburton Franki office and find out how a little drive can take you a lot further.

Shugart

Right from the start.



Warburton Franki

A DIVISION OF THE ANI CORPORATION LTD (INCORPORATED IN N.S.W.)

• ADELAIDE (08) 356-7333 • BRISBANE (07) 52-7255 • HOBART (002) 28-0321
• MELBOURNE (03) 795-9011 • PERTH (09) 277-7000 • SYDNEY (02) 648-1711
• AUCKLAND N.Z. (09) 50-4458 • WELLINGTON N.Z. (04) 69-3016

FILM VS VIDEO

The Bosch FGS 4000.
A video graphics machine on display at the SMPTE conference.



Conference Conflict

THE CONFERENCE was devoted to a discussion of the new technologies that will affect the production of film and television in the near future. One of the major themes to emerge was that the fight between film and electronic techniques continues.

Much was made of the increasing flexibility of video gear. Ray Mobsby from the BBC gave an account of experiments his organisation has been conducting on replacing film units with video. It seems that while the lightness of video gear is a positive boon to cameramen, there were many complaints, particularly about the amount of noise they generate.

To counterpoint the arguments of the video enthusiasts Eastman Kodak rolled out some of their new lo-light film stocks that offer an extraordinary ability to film in ultra low light. The point was made, and emphasised by some stunning visual presentations, that film has a far greater flexibility and higher definition than video. For instance, a contrast range of 400:1 is average for the latest generation of film, but video can only manage 50:1. A 35mm film frame contains 4.9 million pixels, versus the few hundred thousand on broadcast television. Even the proposed high definition TV standards would not approach these figures.

On the other hand, video has a far greater capacity to generate special effects and graphics than film. A number of speakers demonstrated the versatility of new animation and graphics generating machines. Highlights of the show were the Bosch FGS 4000 and the Fairlight Video Synthesiser. Doug Harrison from Bosch

The Society of Motion Picture and Television Engineers (SMPTE) held their first international conference in Sydney recently. Jon Fairall reports.

showed a demonstration tape produced on the FGS 4000 that featured some remarkable colour graphics. It demonstrated to any remaining doubters that these machines will become an indispensable tool in the advertising, music and TV industries.

Even in this area though, film has some remarkable abilities. Peter Parkes, the director of Oxford Scientific Films, showed off some of the remarkable effects he has achieved by filming the very small, the very fast and the very slow. It turns out that it is possible to fool all the people all the time, as his work on Pink Floyd's 'The Wall' and Ken Russell's movie 'Altered Stats' has shown.

The *enfant terrible* of the movie industry, Gareth Brown, was also out in force with his latest invention. He calls it the Skycam, and it consists of a camera, with associated guidance and control systems, suspended from wires. The idea is that the four suspension wires are run through pulleys attached to the highest extremities of a sports ground, e.g: the tops of flood light towers or grandstands. By winding the appropriate wires in and out the camera can then be guided to any point in the stadium, at any height up to almost the level of the pulleys. The length of the wires is controlled by motors which are themselves controlled by a microprocessor responding to a joystick control. The pro-

cessor is also used to control servo motors on the unit that keep it steady and control pan and tilt. A demonstration tape produced on the Skycam showed that, in spite of the Heath Robinson-ish sound of the invention, it does, in fact, add a quite striking view to sports coverage.

Other speakers at the conference looked at some of the changes that will be affecting Australian TV in the next few years. Satellite transmission occupied a lot of attention, as did Teletext and associated text transmission systems.

Ted Thomas, General Manager at ATN 7, underlined Australia's contribution to the development of practical broadcast systems with a catalogue of achievements over the last few years. The Racecam system is probably the most spectacular. Racecam is a camera mounted in a racing car, together with associated transmission equipment. It has been successfully transplanted to the US where the CBS network now use ATN expertise in this area. Another area where considerable advances have been made is the use of helicopters, especially as mobile relay stations.


Mr Thomas said that the single most pressing problem which management of TV stations could give to engineers was the development of a storage method for films and videotape. He said that the amount of space needed for storage of the accumulation of years of transmission material was becoming a major financial burden on TV stations around the world. What we need, he said, is the ability to store an hour's worth of programme material on something no bigger than a credit card.

TOPO

A Walking, Talking Robot

An apple for TOPO?

The robot is controlled through a computer interface and infrared transceiver system (spaceship-looking thing at far left). Software for Apple II is only available at present.



Dennis Lingane

MANY YEARS AGO, a machine such as TOPO was only seen in the movies or was controlled by huge banks of computers. With the incredible increase in technological know-how the machine of the year 2000 is now with us — or is it?

TOPO is a computer-controlled robot costing around \$3000. That puts paid to the affordable part. But then that's only one aspect. And it might change if production increases.

After all, we are always being told how calculators and computers are now a fraction of their original price. When the hand calculator came out it had addition and subtraction and cost well over \$300.

Now the calculator has trigonometric functions, displays letters of the alphabet, is as thin as a credit card and is solar powered. And it costs less than a night at the movies.

If the robot technology is refined at the same rate then we may see an affordable robot by 1990.

But back to the present. TOPO is the offering and unfortunately it really isn't much more than a big electronic toy — although that could change if the inventors keep working on it.

Rocking on

TOPO has a new system of movement which consists of two wheels which sit at an angle of 30 degrees to the horizontal. This new system is called Andromotion. A novel idea which certainly works efficiently. It enables TOPO to turn on the spot or turn through any desired angle.

The only problem with a robot having wheels is that your home must have ramps between all levels so it can visit all the rooms. This is a fault in all robots that use wheels as transportation.

But this style of wheel is certainly a lot more reliable and efficient than that used by previous robots which had wheels like shopping trolleys and usually went where they wanted to, rather than where you wanted.

The sloping wheels enable TOPO to turn on the spot and very accurately at that. But there is a problem with forward and backward movement.

When moving forward TOPO has no front wheel for balance so it has a tendency to rock backwards and forwards. This unsteady movement is TOPO's main weakness. However, it is only a prototype problem and will most probably be fixed in later

models.

Even though the rocking movement is only slight it stops TOPO from carrying objects. We had visions of it fetching coffee for the office staff, but most of the coffee was spilt on the floor so we eventually had to fit TOPO with flippers.

However, Androbot has found a way around this. Put the drink in a can — and our editor agreed, nodding happily at the thought of a Fosters for morning tea.

The TOPO hand is shaped to carry cans; in fact, in Chicago at the Electronics Show last year BOB (the most intelligent member of TOPO's family) was able to waddle to a special fridge, collect a cool drink and bring it back.


Theoretically, TOPO can do the same trick but you'll need to buy the special Androbot fridge.

TOPO is a friendly creature. When you turn it on it answers by repeating its name four times, followed by a big hello in a southern accent.

On the top of its head is a switch pad. This is for when you do not have a computer. It allows TOPO to behave like a radio controlled car. When you press the button




At the moment this computer-controlled robot isn't much more than a big electronic toy. It doesn't wash windows, but it is a programmer's dream come true. Promised add-ons will make it less of a gimmick and more useful.



Above. The electronics slots inside the robot's body.

The guts of the matter. At left is the founder of Androbot Inc., Nolan Bushnell, who started the giant Atari company. He's with BOB (for Brains On Board), TOPO's up-market sibling.



Traction system. The unusual drive system puts the wheels at 30° to the horizontal, giving exceptional lateral stability.

at the front of its head it pronounces the word 'forward' and commences forward motion.

When pressing the left and right buttons TOPO pronounces the corresponding word and turns in the correct direction. To stop it you press the rear switch and it says 'stop' and comes to a halt.

TOPO can also combine the three major functions, forward, left and right, together so that it arcs to the left or right.

You might think that is a rather expensive way to do nothing significant. It is from these basics that TOPO can do more of the type-cast robotic chores. It is true that on its own it doesn't do much and it is more like a radio controlled car. However, when you plug it in to your computer the world is your oyster.

Speak to me

At the moment TOPO only runs on an Apple II with 48K of RAM, using the Super Serial card with an RS232 interface. But programs will soon be available for the Atari and Commodore computers.

When plugged into a computer TOPO

can say anything you want. It does this with a phonetic alphabet which it uses to analyse what you typed in.

This format has its faults. To say a word like psychiatrist TOPO must read it as "sy ky uh trist". This is no different to most voice synthesisers. The problem will arise when ordinary people want to use the speech facility. They might find it rather difficult to find the set of letters which makes the right sound.

Androbot has come to their aid, to a degree, by including several tables of the correct letter sequence so you can create the right sound. These tables will be vital to the novice user of voice synthesisers.

The advantage of using phonetics is that TOPO is multilingual. It can speak in many languages such as French, German, Spanish, Italian, Chinese, Japanese and Arabic. No matter where you are in the world TOPO will 'parlez-vous'.

TOPO can be programmed using a language called TOPOSOF. It is very similar to Logo but was originally developed as a FORTH-based applications program. It adheres very closely to the FORTH-79 standard, and was written to be easy to

transfer to other computer systems.

If you want TOPO to move fifty centimetres forward then you type in '50 FWD'. If you want it to turn 117 degrees to the left then type '117 left'. Simple, isn't it?

Whole statements can be strung together by placing spaces in between each command. You can name such procedures, then every time you call the name TOPO will go through that procedure.

Commands such as GET-POSITION and SET-SPEED can give the programmer a great deal of control over TOPO. The commands can test for which switch is being pressed on its head, test to see if TOPO is talking or not, and so on.

Applications which TOPO is capable of include teaching in an educational situation, going to the bar and getting a drink, escorting guests to the dinner table and vacuuming the floor.

That's some of the things that TOPO can do, but what can't it do?

Well, he can't wash windows, but who wants to?

In brief, TOPO is not ready for the average home user, as indeed the average home user is not ready for TOPO. And neither is ▶

ROBOTICS

their home, unless it has ramps instead of stairs. TOPO cannot travel between rooms of different levels which do not have ramps joining them.

Its arms are not really capable of carrying unusual or heavy objects. Its batteries only last several hours before they need recharging. And it has a voice synthesiser which requires a lot of patience to get it sounding just right.

A gimmicky toy?


With its faults some might think that TOPO is an overpriced toy.

But it is cute looking, good with kids and has all the patience in the world. It is the programmer's dream come true. It is light and can be carried from room to room.

Special devices will eventually be built so that it can carry heavy or unusual products. In fact, there is a robot trolley that fits to its back for carrying shopping; this also steadies the robot in its rocking and rolling during motion.

It might need some refining but what could you expect from a world-first that so far the world has only seen in science fiction movies?

Wasn't the Apple first considered to be a millionaire's toy when it first came out? The fact that this robotics company is



Home, Jeeves! TOPO with the special carry cart.

headed by the US electronics industry's leading entrepreneur, Nolan Bushnell, (who started Atari in a garage in Silicon Valley and then sold it a few years later for \$27 million to Warner) is an indication that this company has the talent to convert science fiction to reality.

Bushnell himself admits that his robots are a bit of a gimmick now. But he promises that new add-ons will follow to make them less of a toy.

These add-ons will be for TOPO and its big brother BOB. BOB has a microprocessor on board so that it doesn't need to be in constant sight of an infrared remote control module.

I leave you with a quote from the manual (due to its length some of it has been omitted): "In 1950 science fiction author, Isaac Asimov, published a book called 'I, Robot'. In the introduction Asimov stated that the major manufacturer of robots would be in existence in 1982.

"He was right about the date, but not about the name. Our name is Androbot Inc, not US Robot or Mechanical Men Inc. There is, however, a major difference between the two products — we are real and so are our products. Robots are just science fiction.

"So allow us to welcome you to a new era — the Age of Androbotics."

bwd
INSTRUMENTS


THE INNOVATIVE AUSTRALIAN

BWD's Model 821 oscilloscope is a dual-trace unit with 50 MHz bandwidth, 1 mV to 20 V per division sensitivity and a special 'mix-mag' expanded trace function

The mix-mag facility, unique to the BWD 821, enables you to get a 10 times magnification of any proportion of the trace from 0% to 80% simply by pulling and turning a knob.

Normal x10 magnification is incorporated and the trace can be expanded to x100 using the mix-mag function to provide facilities similar to a delayed sweep CRO but without the complexity.

The mix-mag facility can be used to magnify each line to examine teletext, sync pulse or video signals of VCRs, television receivers or studio equipment.



821 50MHz MIX-MAG

Superb value... Just **\$850**
Plus Tax

Other features of the BWD 821 include: a 7ns rise time from 5 mV/div., 20ns/div maximum sweep speed, 75MHz triggering, TV line and frame triggering selection, bright trace with 6kV EHT and internal tube graticule.

Two 100MHz probes are included, a x1 and a x10. High sensitivity vertical amp inputs enable low level signals to be viewed, such as from tape recorder heads, pickups and microphones, etc.

The BWD 821 is suited to use in communications, industrial control, research and development, video and microprocessor applications.

Designed and manufactured in Australia by
BWD Instruments Pty. Ltd.

PO Box 325, Springvale, Vic 3171
Miles Street, Mulgrave, Vic 3170 Australia
Phone National (03) 561 2888 Telex 35115
International 613 561 2888

For further information on the BWD 821 or any instrument in the BWD range, please contact: —

Vic. (03) 561 2888	Qld. (07) 369 1277	W.A. (09) 277 7000
N.S.W. (02) 684 1800	S.A. (08) 268 2766	Tas. (002) 23 2842

★ ★ ★ ASK FOR OUR FREE COMPREHENSIVE CATALOGUE ★ ★ ★

SOAR

ANALOG MULTIMETERS

The SX 120 and SX 220 are quality analog multimeters designed and manufactured by the Soar Corporation.

The SX 120 is a compact economical 5 function pocket model, whilst the SX 220 is a 9 function, 20 K Ω /V VOM with added features such as overload protection, continuity buzzer and a facility for temperature measurement using an optional temperature probe.

With an ABS plastic housing the high quality, core-magnet type meter movement is protected from shock and the elements as well as being free from the influence of outside magnetic fields.

See these and others in the Soar instrument range at your nearest L&H Sales Centre. With nearly 100 Australia wide, there's bound to be one near you.



LAWRENCE & HANSON

L. L. BROWN & ASSOC. 981

Budget Book Bonanza!

What an offer! Purchase any 3 of the famous BABANI electronics books shown below, and receive a fourth title from this special selection absolutely FREE!* Don't delay — the great BABANI Bonanza applies only while stocks last.

Buy 3 - get 1 free

50 SIMPLE LED CIRCUITS — BOOK 2

£F346B \$4.95
Fifty useful circuits and applications using the LED to complement Book 1 (ETI Book Sales No. E0108B). Includes diode tester, unijunction LED flasher, car voltage probe, SCR tester, fuse tester.

52 PROJECTS USING IC741

DF386B \$3.95
Projects include remote thermometer, servodriver, rev counter for petrol and diesel engines, voltage amplifier and a record amplifier with bass boost.

POPULAR ELECTRONIC PROJECTS — BOOK 1

DF060B \$6.95
A collection of the most popular types of circuits and projects to interest most electronics constructors. The projects cover a wide range.

SOLID-STATE NOVELTY PROJECTS

CF043B \$4.95
A number of novelty projects using modern ICs and transistors. Includes a musical instrument played by reflecting a light beam with your hand, water warbler for pot plants, music tone generator, LEDs and ladders game, touch switch, electronic roulette wheel, etc.

ELECTRONIC GAMES


CF040B \$5.95
How to build many interesting electronic games, using modern ICs. Covers both simple and complex circuits for beginner and advanced builder.

MULTI-CIRCUIT BOARD PROJECTS

DF063B \$6.75
All circuits are based on one specially designed pc board. Recommended to the less experienced hobbyist.

50 CMOS IC PROJECTS

£F080B \$5.95
Projects include multivibrators, amplifiers and oscillators, trigger devices and other special devices.



Simply fill out the reply-paid card insert and send to:

ETI Book Sales,
140 Joynton Ave, Waterloo NSW 2017
All phone enquiries: (02) 663-9999, ext 242

**More great books on
pages 130, 131**

*Please note preference for free book on reply-card. We will try to supply the title indicated — but no guarantees can be given.

ETI August 1984 — 39

Meeting the challenge of change



Four award winning models to choose from.

microbee really is "meeting the challenge of change" with two ROM and two DISK based models, each guaranteed expandable to any level. From arcade games through to word processing and business management, you can choose the level of development to suit your needs.

Tomorrow looks equally bright for microbee owners . . . with new technology and advances . . . with reports and literature on new software and peripherals . . . and with training courses for each level of development.

HI RES Economy Green Screen Monitor



16K Educator \$449

Now with **WORDBEE!**

The **microbee Educator** is specifically designed for the education market and has been chosen by NSW, Western Australia, Queensland and the Australian Schools Commission as a computer for use in schools.

microbee Educator boasts high quality graphics and sound effects capability, exceptional performance at a realistic price plus powerful software designed for Australian curriculum needs.

32K Personal Communicator \$499

microbee's top selling portable computer now features:

Telcom 1 firmware **WORDBEE**, Microworld **BASIC**, machine code **MONITOR**, **ADM-3A** terminal emulation, self-test in 28K of ROM with 32K of CMOS battery backed user memory, high resolution **PCG GRAPHICS**, **SERIAL AND PARALLEL I/O** ports, programmable cassette interface and direct monochrome video output.

A vast library of educational, entertainment and utility software is now widely available.

Microworld **BASIC** supports full high resolution graphics, colour if required, music, I/O data can be directed at will and best of all, **MW BASIC** is a breeze to program yourself.

The low cost

BEEMODEM can be added enabling your **microbee** (via your phone line) to communicate with other computers worldwide!

Software and your microbee

Whichever **microbee** model you choose there is a vast and growing array of software to use with it . . . some built-in and included in the price of your computer. Games and family entertainment, education programmes, communication, information systems, personal and business finance, word processing and much, much more.

Ask at your **microbee** Computer Centre for the current range of software included with each model or ask for the catalogue of "Software Available".

Options and Peripherals

Advanced "State of the Art" peripherals and options are available to interface with your **microbee** such as:

- microbee** HI RES Economy Green Screen Monitor . . . \$149.50
- Adjustable Monitor Stand . . . \$19.95
- BEEMODEM** . . . \$149.50
- microbee MB80** Dot Matrix Printer
 - Parallel . . . \$399.00
 - Serial . . . \$449.00
 - (Includes cables)
- microbee** High Resolution Anti Glare Ergonomically Designed Amber Screen Monitor . . . \$249.00

Now with Dynamic RAM to meet today's user demands

64K Advanced Personal Computer

(with Single 400K Disk Drive and all manuals) **\$1,595**

The **microbee 64K Advanced Personal Computer** with a Single 400K Disk Drive is the ultimate configuration for the serious enthusiast.

It is supplied 'bundled' with world class software such as CP/M, MICROSOFT BASIC, MULTIPLAN, WORDSTAR and a powerful library of support programs. Comprehensive user manuals are also supplied. No wonder this model **microbee** is regarded as the most powerful and best price/performance computer in its class.

microbee 128K

(with Dual 400K Disk Drives and all manuals) **\$1,995**

Designed for the serious home and small business user, the package consists of the **microbee** with 128K of dynamic RAM controlled by the proven Z80A processor plus a dual 400K disk drive, with the increased power more sophisticated programs can be executed including a whole host of bundled software for word processing, terminal emulation and communication with other computers worldwide, spreadsheet analysis and networking.



**microbee 128K
Computer with
Dual Disk Drive**

microbee computer centres

1 Pattison Ave,
Waitara 2077, N.S.W.
Phone (02) 487 2711

729 Glenferrie Rd,
Hawthorn 3122, Vic.
Phone (03) 819 5288

141 Stirling Highway,
Nedlands, W.A.
Phone (09) 386 8250

Coolman Court,
Weston A.C.T. 2611.
Phone (062) 88 6384

151 Unley Road,
Unley 5061, S.A.
Phone (08) 272 1384

455 Logan Road,
Stones Corner, Qld 4120
Phone (07) 394 3688

Koala Crescent,
West Gosford 2250.
Phone (043) 24 2711

Authorised Dealers in:—
NSW: Carlingford,
Coffs Harbour, Concord,
Hurstville, Lismore,
Sydney.

QUEENSLAND:
Townsville, Cairns,
Milton.

VICTORIA:
Melbourne.

SOUTH AUSTRALIA:
Adelaide, Edwardstown,
Port Lincoln.

WESTERN AUSTRALIA:
Mount Tom Price.

TASMANIA:
Launceston

ACT:
Belconnen, Weston.



bankcard
welcome here

DIRECT ORDERS
PHONE (02) 487 2711
TELEX AA72767

**APPLIED
TECHNOLOGY
RETAIL PTY LTD**

AUSTRALIAN IMPORTERS

CLIFF AUDIO CONNECTORS

S2 SERIES 6.5MM NYLON
INSULATED SOCKETS



- ★ MONO & STEREO TYPES AVAILABLE
- ★ BREAK, MAKE OR SINGLE CONTACT CONFIGURATIONS (PC MT.-OPTION)
- ★ COLOURS: GREY, BLACK, RED, WHITE, GREEN

S6 series 3.5mm NYLON INSULATED SOCKETS



- ★ BREAK OR SINGLE CONTACT CONFIGURATION (PC MT.-OPTION)

6.5MM PHONE PLUGS


SHATTERPROOF NYLON
BACK COVER



- ★ COLOURS: RED, BLACK, GREEN, BLUE, WHITE, GREY, YELLOW
- ★ MONO/STEREO AVAILABLE

3.5MM PHONE PLUGS

(SAME CONSTRUCTION AS 6.5MM
TYPES)



THE CLIFF QUICKTEST

FOR:

- ★ RAPID CONNECTION OF PLUGLESS LEADS TO MAINS
- ★ RAISED LID CUTS CURRENT FOR SAFETY
- ★ 240V @ 13A RATING
- ★ SPECIAL — \$23.00 + 7.5% TAX




DELSOUND PTY. LTD.

1 WICKHAM TERRACE
(CNR. WHARF ST)

BRISBANE. 4000

(07) 229-6155 TELEX AA44442



YOUR BASIC TOOLKIT!

Here are pretty well all the basic tools you'll need for constructing electronic projects. On the left (A) is a low-cost 20 watt continuous-heat soldering iron. In the foreground are long-nosed pliers (B), side cutters (C) and snub-nosed pliers (D). At top-centre is a "Tyrannosaurus" wire-stripping tool (E) — an extremely handy and time-saving device. To the left of it are two nut drivers (F-G) and to the right are four screwdrivers — two Philips-head types (H-I) and two flat-blade types (J-K). All you need add perhaps is a small drill and a 'hobby' knife.

YOUR BASIC TOOLKIT

Want to 'get started' in electronics? You've come to the right place! This elementary series *shows* you how to get into the fascinating hobby of electronics without the necessity of having mountains of money, unlimited time or a university degree.

Roger Harrison

WELCOME TO the wide, wonderful world of electronics! Once you've 'dabbled' a while with a project or two and enjoyed the satisfaction of putting together a project *yourself*, and got it working, you'll be *hooked*. Join the millions of hobbyists worldwide. Electronics must surely rate as the world's biggest, most popular hobby. Virtually everybody employed in any aspect of the electronics industry either started out as a hobbyist — or is employed pursuing their hobby!

Well, where *do* you start? For the beginner starting out in electronics (. . . good name for a series!) it can seem bewildering when you're confronted by a profusion of terms and phrases — seemingly like another language. How do you sort out a resistor from a capacitor, a transistor from a transient, an electron from an electrolytic, or a printed circuit from a polypropylene capacitor? Well, that's our job. This series is designed to introduce you to the 'bits' and 'how to' of electronics with as little pain as possible. You learn as you go. You can start by tackling relatively simple projects at first, learning how to use the tools as you proceed.

Now that seems like the best place to start — with the tools.

The soldering iron

Electronic components are connected to conductors, tags, terminals etc, by *solder-*

ing. Solder is an alloy of tin and lead, mixed in the ratio, for electronic applications, of 60:40. It melts at a temperature lower than the melting point of either metal alone, that temperature being around 188° C. A soldering iron is used to heat the parts to be joined and melt the solder so that it covers the joint. The solder acts as filler and bonding agent, creating an electrical contact between the parts being joined and filling the irregular surface.

To make a proper bond to the joint, the solder has to 'wet' the surfaces.

As metals oxidise, or tarnish, on the surface as a result of being exposed to air, 'flux' is used to remove the tarnish. For electronic work this is composed of resin (sometimes spelt rosin), which is obtained from the sap of pine trees plus additives called 'activators'. At soldering temperatures, the activators decompose, liberating an acid that dissolves the tarnish faster than pure resin. Other fluxes are also made for non-electronic uses, usually sheet-metal work, copper and brass-ware manufacture. These fluxes are usually highly corrosive (such as hydrochloric acid) and must *never* be used for electronics work as even minute amounts rapidly corrode component leads and printed circuit board tracks.

Solder for electronics work is made as different gauge wires, most have a resin core along their length, some have up to five separate cores.

The resin core melts before the solder ►

[Soldering iron courtesy Altronics, Micron T2420; Wire stripper courtesy Jaycar, TH-1824; sidecutters and snub-nosed pliers courtesy Dick Smith Electronics, T-3205 and T-3565 respectively; other tools courtesy of local hardware store]



GET THE DRILL?



A small, handheld 'mini' drill, having a chuck speed of 5000 to 10 000 rpm is handy for drilling holes in printed circuit (or 'pc') boards. Ready-made pc boards have pre-drilled holes so a drill is not essential to start with, unless you go 'the whole hog' with your projects and make your own boards. (We'll show you later).

and flows onto the joint, wetting both the joint and the solder, excluding the air. At the same time the activators dissolve the tarnish on the surface, allowing the solder to flow freely and properly wet the joint. When the solder melts, the increase in temperature deactivates the flux, limiting the possibility of corrosion.

Resin-cored solder is obtainable in a variety of wire gauges. For general and heavy work, such as on sockets, chassis, switch contacts, etc, 16 gauge is suitable. For fine work on printed circuit boards, miniature components, etc, 20 or 22 gauge is best. It pays to have several different gauges handy. Experience will show which is the best under different circumstances.

It is important to select a suitable soldering iron — after all, it will probably be the tool you use the most! A bewildering variety of types and sizes are available.

The most suitable rating for electronics work is between 15 and 30 watts. Irons below this rating generally do not have sufficient heat capacity, while those above have high tip temperatures that can result in damaged components and poor joints. Irons of the *continuous heat* type, that have ratings above 80 watts, are best for sheet metal work. Irons advertised as 'universal' (mostly having a rating of 40 or 50 watts) should be avoided as they are usually too bulky for electronics work, particularly on printed circuit boards, and have too much heat capacity and high tip temperatures with the likelihood of component damage. The handle also usually gets too hot for comfort.

Choose an iron which is comfortable to hold. As well as being light, the iron should preferably have a lightweight power cord to reduce drag on your wrist when moving the iron around. The length of the cord should be adequate — about 1.5 m to 2 m is a good length.

Low wattage, continuous heat irons are probably the most widely used despite a few

drawbacks. They are heated by a wire resistance element located in the barrel just behind the tip.

Continuous heat irons are slow to heat to soldering temperature — they are usually left running continuously. This causes tip oxidation which therefore requires constant maintenance and fairly frequent replacement. These are minor drawbacks, however, if you cannot afford a more expensive iron.

Some irons of this type are obtainable with a temperature select switch in the handle. This usually doubles the power when needed to provide sufficient heat to make the occasional heavy joint. They are normally used on the lower power position for routine soldering.

Quick-heat irons operate from a low voltage at a high current, usually supplied from a transformer, and take only a few seconds to reach soldering temperature. They take only a few more seconds to reach red heat if the operating button is held on too long!

Quick-heat irons are made in two basic styles — the soldering gun and the low-voltage iron.

Quick-heat irons are suitable for intermittent handyman use or applications requiring their large heating capacity. They are not recommended for general electronics use, particularly on printed circuit boards, except perhaps for the 'mini' models. Quick-heat irons require some skill to control the heat so as not to damage components by overheating.

Despite their limitations, quick-heat irons can be useful in an electronics workshop. If you contemplate purchasing one make sure the transformer has an electrostatic screen.

Soldering guns have the disadvantage that the transformer in the handle tends to make them a little unwieldy, especially for prolonged use.

Battery-operated soldering irons have become widely available, and these find

application where power is unavailable or inconvenient to supply. These irons can be used where components sensitive to leakage currents (i.e: MOS devices, CMOS ICs, etc.) are employed, though the other types mentioned are OK provided the tip and/or barrel are earthed.

Rechargeable nickel-cadmium batteries, usually contained in the handle, supply the current. They are not suitable for prolonged use.

Temperature-controlled irons are made specifically for electronics work. They are unsurpassed for good soldering, convenience and minimum possible damage to components. They are more expensive than the other types but get one if you can afford it.

The best 'general purpose' tip is a 'wedge' or 'chisel' shape with an edge about 2.5-4 mm wide, and a shaft about 5-7 mm in diameter.

We'll go into the subject of soldering and soldering irons in more detail in the next part of the series.

Mechanical tools

You'll need some tools to hold things, cut things, screw things and strip wire insulation. Not essential to start with, but very handy to have is some type of small drill, too.

The quintessential mechanical tool for electronics construction is the *sidecutter*. Also called 'wire cutters', which also applies

THE ANALOGUE MULTIMETER



These were the 'standard' test instrument for many years. Multimeters are used to measure the basic quantities involved in electronics — voltage, current, resistance. Analogue multimeters cost anything from as little as \$10 to over \$100. This Univolt model from Benelec costs around \$20.

SUPER BARGAINS AT MAGRATHS!

NEW RANGE OF TRIO OSCILLOSCOPES



CS-2110 **\$2,869²⁵** Inc. Tax

100MHz
A NEW STANDARD IN 100MHz SCOPE PERFORMANCE

- High sensitivity 1mV all the way to 100MHz.
- 2nS/div maximum sweep speed.
- Delayed sweep for partial waveform expansion.
- 4-Channels, 8 Traces with wide range of waveform display functions.
- Dual sweep functions
- Accuracy $\pm 2\%$ for precise waveform measurements.
- Bright, sharp, 150mm rectangular CRT (20kV).
- Push-button switches with LEDs for simplicity and reliability.
- Guaranteed channel-to-channel time accuracy.
- All position controls are on the front panel for operator convenience.
- Optimum multi-clamping of video signals.

PROBES MODEL 88100 DC to 100MHz
(suits all scopes) **\$39⁶⁰** Inc. Tax

CS-1060 **\$1,719²⁵** Inc. Tax

40-60MHz
A THOROUGHLY UPDATED DESIGN IN A 3-CHANNEL, 6-TRACE SCOPE

- 3-channel, 6-traces using alternate delayed sweep.
- Extremely high sensitivity of 1mV.
- Bright, sharp, autofocus 16kV CRT (12kV for CS-1040).
- Maximum sweep speed 5nS/div (10nS/div for the CS-1040).
- $\pm 3\%$ accuracy for precise waveform measurements.
- Eight full divisions of dynamic range.
- Vertical axis signal output.
- Video clamping.
- Delayed sweep can have zero delay enabling magnification of even the leading edge of a signal.

CS-1022 **\$746³⁵** Inc. Tax

20MHz
Economy and Style in an all-new workhorse 20 MHz scope.

- High sensitivity - 1 mV/div.
- 150mm rectangular CRT (6kV) with illuminated innerface graticule.
- 20nS/div maximum sweep for display of fast changing signals.
- $\pm 3\%$ accuracy for precise waveform measurements.
- Video clamping for reliable synching.
- Eight divisions of dynamic range.
- Ergonomic front panel layout.
- Observation of intensity modulated signals.
- X-Y mode.
- Vertical signal output.

SEMICONDUCTORS

MEMORY

TMS 4116	16K DYNAMIC	\$2.30
TMS 4164	64K DYNAMIC	\$7.76
8416(6116)	2K X 8 CMOS	\$8.05
2732	32K EPROM	\$7.75
2516	16K EPROM	\$4.27
2532	32K EPROM	\$8.05
MB8118	16K X 1 RAM	\$4.54

MISC. SEMICONDUCTORS

76477	SOUND SYNTHESIS	\$4.23
76488	SOUND SYNTHESIS	\$4.23
76489	COMPLEX SOUND GENERATOR	\$7.73
TMS 4500	DYNAMIC RAM CONTROLLER	\$26.45
TMS 9929	VIDEO DISPLAY PROCESSOR	\$38.13
6801L1		\$43.38

OPTO

FND 357	C.C. 3" RED	\$2.13
FND 507	CA. 5" RED	\$1.73
RND 807	CA. 8" RED	\$6.33
MAN 72A	CA. 3" RED	\$1.73
MAN 74A	C.C. 3" RED	\$1.73
MAN 8610	CA. 8" ORANGE	\$5.61
MAN 8630	CA. 8" ORANGE \pm OVERFLOW	\$3.19
MAN 8650	C.C. 8" ORANGE \pm OVERFLOW	\$4.04
MS131C	CA. 3" RED	\$1.73
IL6	CHROME BEZEL LED RED/OR GREEN	90
TIL 31	PHOTO DIODE	\$1.73
TIL 81	PHOTO TRANSISTOR	\$1.52
BPW50	PHOTO DIODES	\$1.73
ME7121	IR LED	\$1.73
MCA7	REFLECTIVE OBJECT SENSOR	\$5.32
MCT8	SLOTTED OPTICAL LIMIT SWITCH	\$2.30
MCT81	SLOTTED OPTICAL LIMIT SWITCH	\$2.30
2N5777	PHOTO TRANSISTOR - DARLINGTON	78
MCP 3022	TRIAC DRIVER	\$2.06
FCD820D	OPTO COUPLERS	\$1.66
MCC670	(6N138) OPTO COUPLER	\$2.93
MCT2	OPTO COUPLER	\$1.04
4N26	OPTO COUPLER	\$1.10
5mm LEDs	GENERAL PURPOSE RED/GREEN	
	YELLOW	23
MV5491	RED/GREEN DUAL LED	\$3.31

FIGARO GAS SENSORS

812 # 813 \$13.46 ea.

THIS MONTH ONLY!

TGS APPLICATIONS

Combustible Gas-Leak Alarm
Carbon Monoxide Detector
Automatic Fan Control
Fire Alarm (Detecting combustible gases contained in smoke)
Air Pollution Monitor

TGS FEATURES

Long life. Sensors in continuous use for 8 years are still functioning normally.
High reliability even when exposed to toxic gases.
Detects low concentrations of Natural Gas, Carbon Monoxide and a range of toxic gases.


#812 General purpose combustible gas detection. Carbon Monoxide detection. High CO sensitivity enables most types of smoke to be detected.

#813 General purpose combustible gas detection. Methane detection. High CH₄ sensitivity makes it suitable for Natural Gas detectors.

ARISTA ELECTRONICS TV-VIDEO ACCESSORIES

Video Dubbing Kit.
For recording from any video machine to any video machine.

KIT INCLUDES:
Video Cable 1.5m 1 PC.
Audio Cable 1.5m 1 PC.
RCA-UHF Adaptor 2 PCS.
RCA-BNC Adaptor 2 PCS.
RCA-3.5mm Adaptor 2 PCS.
Cable Adaptor, 5 PIN DIN Plug to RCA Jacks (in/out) 2 PCS.



ONLY A LOW

\$16¹¹

Books & Magazines.

GREAT VALUE

WE HAVE A LARGE RANGE OF MAGAZINES IN STOCK!

FAIRCHILD

Bipolar Memory Databook	\$8.00
COS Databook	\$9.00
A Linear Databook	\$12.50
MOS Memory Databook	\$8.00

MOTOROLA

CMOS Databook	\$9.00
Schottky TTL Databook	\$8.00

PHILIPS

Building Hi-Fi Speaker Systems	\$6.50
Semiconductors, Pt 2	\$10.00
Semiconductors, Pt 3	\$10.00
General Catalogue 84/85	\$10.00

DATA BOOKS

TEXAS INSTRUMENTS	
Software Design for Micro Processors	\$14.95
1981 Supplement - TTL Data	\$6.25
Linear Control Circuits	\$3.90
Interface Circuits	\$16.00
MOS Memory	\$8.35
Bipolar Microcomputer Components	\$9.99
TTL Date Book	\$12.50
Understanding Solid State Electronics	\$7.95
Understanding Computer Science	\$7.95
Understanding Communications Systems	\$7.95
Understanding Optonics	\$7.95
Beginners Basic TI-99 4A	\$14.95

NATIONAL SEMICONDUCTOR

Audio Radio Handbook	\$6.50
Advanced Bipolar Logic	\$6.50
Linear Applications Handbook	\$18.00
Transistor Data Book	\$7.50
Voltage Regulator Handbook	\$8.00
Memory Data Book	\$7.00



SUPER BARGAINS AT MAGRATHS



BANKCARD ORDER FORM

NAME

ADDRESS

Signed

Please Charge my Bankcard No. ☐

NOW OPEN!

NEW QUEENSLAND STORE
SHOP 5, 59 BARRY PARADE
BRISBANE 4006
PHONE (07) 832 3700


MAGRATHS ELECTRONICS Phone or Mail.
55 A'BECKETT STREET, MELBOURNE, 3000
Phone (03) 347 1122, Telex AA31001
Prices subject to change without notice.



Mail or phone orders add 2.00 up to 1 kg pack post. Special rates for heavy items on request

ALL ITEMS INCLUDE S/TAX UNLESS STATED OTHERWISE.

MC/MAG/045 P



SEMI-CONDUCTORS ARE GETTING SCARCER



Integrated Circuits & Transistors

REVISED	74S253	4.90	74C83	2.30	74LS49	1.80	74LS299	3.90	6840	6.50	LM380 14PIN	1.90	RC4194	3.90	BDV648	5.50	MPSU02	1.75	
	74S257	3.30	74C85	2.30	74LS51	70	74LS320	3.95	6844	15.00			MM 5369	4.95	BDV658	5.50	MPSU52	1.90	
7/11/83	74S258	3.30	74C86	1.50	74LS54	80	74LS321	3.95	6845	25.00					BDX63	6.50	MPSU56	1.75	
ICL7106	13.50	74S260	2.90	74C89	8.90	74LS55	80	74LS322	6.75	6847	7.50	LM381	2.00			Y96 (BUX 80)	4.90	MPU131	1.75
ICL7116	19.50	74S274	P.O.A.	74C90	1.90	74LS56	2.80	74LS323	6.75	6850	3.50	LM382	2.20						
ICL7117	21.50	74S275	P.O.A.	74C93	1.90	74LS57	1.00	74LS324	2.20	6850		LM383	3.90						
ICL7118	6.95	74S280	5.90	74C95	2.00	74LS74	0.80	74LS326	2.20	6860	10.00	LM384	3.50	SC1410	1.50	BDY97 (BUX 80)	4.90	MRF221	19.50
ICL7600	6.95	74S281	P.O.A.	74C107	1.20	74LS75	1.00	74LS327	2.20	6875	15.50	LM386	1.95	SC141E	1.95	BF115	1.50	MRF237	3.90
ICL7601	4.90	74S283	7.90	74C150	6.50	74LS76	1.00	74LS352	2.20	Z80CPU	7.00	LM387A	LM395	SC142E	2.95	BF167	1.20	MRF238	19.50
ICL7602	4.90	74S287	4.90	74C151	4.20	74LS77	1.00	74LS353	2.20	Z80BCPU	8.00	LM387	2.00	SC146D	2.85	BF173	1.20	MRF245	43.50
ICL7604	4.90	74S288	4.90	74C154	6.00	74LS78	1.10	74LS354	3.95	Z80BCPU	16.00	LM390	2.95	SC146M	2.95	BF177	1.20	MRF454	34.00
ICM721	12.50	74S299	13.90	74C157	3.75	74LS83	1.50	74LS365	1.00	Z80P10	4.50	LM391	2.90	SC150D	4.95	BF180	1.20	MRF455	27.00
ICM7216A	48.50	74S301	13.90	74C160	1.90	74LS85	1.75	74LS366	1.00	Z80P10	4.50	LM393	1.00	SC151D	2.95	BF182	1.20	MRF455A	47.00
ICM7216B	44.50	74S314	P.O.A.	74C161	1.90	74LS86	80	74LS367	1.00	Z80CTC	6.50	LM394	4.95	SC103YY	90	BF182	1.20	MRF475	2.70
ICM7217A	44.50	74S330	P.O.A.	74C162	2.00	74LS90	1.20	74LS368	1.00	Z80ACTC	8.50	LM395T	9.95	C103B	90	BF183	60	MRF603	19.50
ICM7218A	18.50	74S331	P.O.A.	74C163	2.00	74LS91	1.20	74LS373	2.00	Z80DMA	16.00	LM396K	22.50	C106B	90	BF184	60	MRF641	32.00
ICM7224A	21.50	74S373	9.90	74C164	2.50	74LS92	1.20	74LS374	2.00	Z80ADMA	19.00	LF398	5.90	C106D	90	BF198	60	MRF646	43.00
ICM7226A	48.50	74S374	9.90	74C165	2.50	74LS93	1.50	74LS375	1.50	Z80AS10	13.00	NE544	6.50	C122D	2.50	BF199	60	MRF901	2.75
ICM7227A	19.50	74S381	9.90	74C173	1.90	74LS95	1.20	74LS377	2.15	Z80S10	15.00	NE555	8.00	C122E	2.95	BF200	1.20	MPF131	1.60
ICM7213A	15.50	74S387	3.30	74C174	1.90	74LS96	1.20	74LS378	1.90	AD570	69.50	NE558	6.90	C1260	9.90	BF245	1.50	TIP31A	1.90
ICM7240	7.50	74S412 / 8212		74C175	1.90	74LS107	90	74LS379	1.20	AD572A	17.50	NE560	4.60	C2646	1.20	BF337	1.50	TIP31B	1.20
ICM7242	3.90		5.90	74C192	2.00	74LS109	90	74LS386	1.00	AY-3-8910	14.50	NE561	4.60	C2646	1.20	BF338	1.90	TIP31C	1.00
ICM7250	7.90	74S428 / 8228		74C193	2.00	74LS112	70	74LS393	1.80	AY-3-2513	14.50	NE566	2.90	C2647	2.50	BF458	1.00	TIP32A	1.00
ICM7260	7.90		7.90	74C195	2.00	74LS113	70	74LS396	2.50	MSM5832	16.50	NE567	2.00	C2647	2.50	BF459	1.00	TIP32B	1.00
ICM7555	2.75	74S470	9.90	74C200	14.00	74LS114	80	74LS399	3.00	MM58174	19.50	NE570	5.90	AC125	1.20	BF469	1.20	TIP32C	1.20
ICM7556	2.95	74S471	9.90	74C221	2.75	74LS122	1.30	74LS396	2.50	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
		74S472	P.O.A.	74C240	2.75	74LS123	1.30	74LS398	3.00	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
		74S473	P.O.A.	74C244	2.95	74LS125	1.20	74LS399	3.00	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
		74S474	P.O.A.	74C373	5.75	74LS126	1.20	74LS400	5.50	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
		74S475	P.O.A.			74LS132	1.50	74LS440	5.50	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
		74S482	11.90	74C374	5.45	74LS133	4.90	74LS441	5.50	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
		74S489	7.90	74C901	3.00	74LS136	1.50	74LS442	5.50	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C902	2.50	74LS138	1.50	74LS443	5.50	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C903	2.50	74LS139	1.50	74LS445	5.50	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C904	2.50	74LS145	2.10	74LS446	5.50	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C905	15.00	74LS147	2.50	74LS447	5.50	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C906	2.90	74LS148	1.90	74LS448	5.50	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C907	2.90	74LS151	1.20	74LS449	5.50	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C908	2.75	74LS152	1.95	74LS450	5.50	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C909	14.00	74LS153	1.00	74LS454	5.50	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C911	12.50	74LS154	2.95	74LS541	7.95	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C912	12.50	74LS155	1.50	74LS561	2.75	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C914	4.50	74LS156	1.50	74LS562	2.75	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C915	4.00	74LS157	1.90	74LS563	2.75	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C917	15.50	74LS158	1.00	74LS569	5.95	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C918	2.90	74LS160	1.00	74LS640	3.95	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C920	12.50	74LS161	1.00	74LS641	2.75	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C921	12.50	74LS162	1.50	74LS642	2.75	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C922	7.50	74LS163	1.10	74LS643	2.75	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C923	7.90	74LS164	1.40	74LS644	2.75	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C925	8.90	74LS165	1.00	74LS645	2.75	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C926	8.90	74LS166	2.55	74LS668	1.75	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C927	9.90	74LS170	2.45	74LS669	1.75	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C928	9.00	74LS173	1.20	74LS670	2.75	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C929	9.50	74LS174	1.20	74LS673	12.55	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C930	2.75	74LS175	2.80	74LS674	12.55	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C932	2.50	74LS181	4.00	74LS690	3.95	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C941	2.50	74LS190	1.50	74LS691	3.95	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
				74C989	8.90	74LS191	1.20	74LS692	3.95	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
						74LS192	1.20	74LS693	3.95	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
						74LS193	1.20	74LS696	3.95	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
						74LS194	1.20	74LS699	3.95	MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
						74LS195	1.75			MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
						74LS196	1.75			MM58174	19.50	NE571	5.90	AC126	1.20	BF495	90	TIP41A	1.90
						74LS197	1.75			MM58174	19.5								

AND SCARCE STOCK UP


NOW!

Integrated Circuits & Transistors



2N3819	1.20	2SD288	3.95	7482	1.80	74367	1.50	8228	5.50	74F521	4.22	78L12	.75	4024	1.20	4514	2.90	R28110
2N3866	2.95	2SD325	2.95	7483	1.10	74368	1.50	8231	199.00	74F532	4.84	78L15	.75	4025	.80	4515	2.90	330 OHM
2N3904	1.00	2SD525	3.95	7485	1.20	74373	2.25	8232	199.00	74F534	4.84	78L18	.75	4026	2.40	4516	1.45	R28115
2N3906	1.00	2SK45	3.95	7486	1.20	74374	2.25	8237	39.00			78L24	.75	4027	1.20	4517	8.75	470 OHM
2N4030	1.50	2SJ49	7.50	7489	3.90	74375	1.75	8238	9.50	MEMORY		79L05	1.20	4028	1.20	4518	2.50	R28120
2N4032	2.20	2SJ56	12.50	7490	1.00	74377	2.45	8243	8.50	2101	6.90	79L12	1.20	4029	1.50	4519	1.90	560 OHM
2N4033	2.20	2SK45	3.95	7491	1.00	74390	1.95	8251	4.90	2102	2.50	79L15	1.20	4030	1.50	4520	2.55	R28125
2N4036	2.50	2SK134	7.50	7492	1.00	74393	1.95	8253	7.50	2112	7.90	79L18	1.20	4031	2.95	4521	3.90	820 OHM
2N4121	1.50	2SK176	12.50	7493	1.00	74425	2.55	8255	5.50	2114	2.95	79L24	1.20	4032	2.75	4522	1.90	R28130
2N4123	1.50	1N4001	.10	7494	1.50	74226	2.55	8257	16.50	3147	6.90			4033	2.75	4526	1.85	1K OHM
2N4236	1.90	1N4002	.15	7495	1.00	74490	2.65	8259	6.50	2708	5.90	LM309K		4034	3.50	4527	2.65	IR28135
2N4237	1.90	1N4007	.20	7496	1.50	9300	1.50	8271	89.00	2716	5.90	(7805KC)	1.90	4035	1.95	4528	1.15	1K2 OHM
2N4248	.40	1N5400	.40	7497	2.30	9301	2.50	8272	33.00	2732	7.00	LM317T	2.50	4038	3.25	4529	1.80	R28140
2N4249	.40	1N5404	.40	74100	1.65	9302	2.90	8273	65.00	2764	12.00	LM317K	4.50	4040	1.90	4530	1.60	1K5 OHM
2N4250	.40	1N5408	.60	74107	1.20	9304	4.00	8274	42.50	27128	49.00	LM317HV	9.50	4041	1.50	4531	1.65	R28145
2N4258	.50	0A47	.80	74109	.90	9305	2.40	8275	38.50	4116	3.95	LM323K	6.50	4042	1.00	4532	2.65	1K8 OHM
2N4355	.50	0A90	.50	74110	1.50	9307	3.80	8276	28.50	4164	10.00	LM337T	2.90	4043	1.60	4534	8.90	R28150
2N4356	.50	0A91	.50	74111	1.50	9308	2.60	8379	8.50	6116	10.00	LM337K	6.50	4044	1.20	4536	6.50	2K2 OHM
2N4360	1.00	0A95	.50	74112	1.50	9309	2.40	8282	6.90	6164	99.00	LM338K	9.50	4045	4.90	4538	3.50	R28155
2N4401	.30	5082-2800	2.95	74113	1.50	9310	1.50	8283	6.50	58725 (6116)	9.00	LM350T	6.50	4046	2.50	4539	1.65	2K7 OHM
2N4402	.30	5082-2811	4.95	74114	1.50	9311	2.50	8284	8.50			LM350K	7.50	4047	1.90	4541	1.60	R28160
2N4403	.30	HLM6620	5.95	74120	1.95	9312	2.50	8286	6.50	2101 (5101)	7.90	LM395K	22.50	4048	1.20	4543	2.50	3K3 OHM
2N4416	1.90			74121	.90	9313	6.00	8287	6.50	(8101)	7.90	LM396K	19.50	4049	1.00	4544	10.50	R28165
2N4427	2.90	BRIDGES		74122	.90	9314	2.40	8288	25.00	5101	7.90			4050	1.00	4549	7.25	4K7 OHM
2N4919	2.90	1.5AMP		74123	1.50	9316	1.90	8289	73.00	8101	7.90	78H 05KC	9.00	4051	1.50	4551	1.80	R28170
2N5088	1.00	W005	.50	74125	1.00	9317	4.20	8291	43.00	2532	12.50	78H 12KC	9.00	4052	1.50	4553	5.50	5K6 OHM
2N5089	1.00	W02	.60	74126	1.00	9318	4.60	8292	34.50			78HGKC	9.50	4053	1.50	4554	2.35	R28175
2N5139	1.20	W04	.60	74128	1.80	9319	2.00	8293-10	26.50			78P 05KC	14.50	4054	3.90	4555	1.10	6K8 OHM
2N5179	1.20	6AMP		74132	1.00	9320	6.90	8741	57.50	OPTO				4055	3.90	4556	1.25	R28180
2N5190	2.50	BPC602	2.90	74136	1.00	9321	2.40	8748	35.00	4N25	1.20	ITEM		4056	4.20	4557	7.85	8K2 OHM
2N5191	3.30	KBPC604	4.50	74138	1.80	9322	1.90	8749	58.50	4N26	1.20	RETAIL COST		4057	2.50	4558	2.25	R28185
2N5192	3.10	KBPC608	4.50	74139	1.50	9324	1.40	8755	33.50	4N27	1.20	79HGKC	16.50	4058	2.00	4559	7.25	10K OHM
2N5193	2.50	10AMP		74141	1.10	9328	4.90	2911	26.50	4N28	1.20	78S 40	3.50	4063	2.50	4560	3.75	10 PIN SIPS
2N5194	2.95	KBPC10005	3.90	74142	1.45	9334	6.00	2912	27.50	4N29	1.50	MC1496L	14.50	4066	9.90	4561	1.80	
2N5195	3.30	KBPC1002	4.20	74143	1.45	9338	5.90	2920	239.00	4N30	1.60			4067	1.00	4562	8.45	
2N5210	1.50	KBPC1004	4.90	74144	3.90	9340	9.90	3205-8205	9.90	4N32	2.50	SPECIAL FUNCTION		4069	1.00	4566	3.00	
2N5245	1.50	35AMP		74145	1.45	9342	5.90	3242	17.50	4N33	2.50	LM 4250	2.45	4070	9.00	4568	4.25	R29105
2N5303	8.50	KBPC3502	5.90	74147	1.95	9368	2.20	3245	10.90	4N37	2.00	NE5534 N	2.50	4071	80	4569	2.50	220 OHM
2N5401	1.50	KBPC35014/MD	6.90	74148	2.00	9374	3.30	3628	18.50	MCT6	2.50	NE5534 AN	2.95	4072	90	4572	.75	R29110
2N5457	1.00	A3504	6.90	74150	1.50	9386	2.40	8008-1	62.50	MCT66	6.90	MC3340	1.90	4073	90	4580	8.95	330 OHM
2N5458	.90	KBPC3510/MDA	9.90	74151	1.20	75107	2.50	8031-3	29.50	MCT2	1.50	MC3341	2.90	4075	90	4581	3.10	R29115
2N5459	.90			74154	1.75	75110	2.50	8035	6.90	1LD 74	5.90	76477	8.95	4076	1.50	4582	1.65	470 OHM
2N5461	.90			74155	1.20	75150	2.50	8039	7.90	1LQ 74	6.50	76488	8.95	4077	.80	4583	2.25	R29120
2N5462	.90	74		74156	1.70	75154	2.50	FD1771	19.00	FND357	1.80	76489	9.95	4078	.80	4584	.85	560 OHM
2N5463	.90			74157	1.00	75450	1.50	FD1791 (8876)	39.00	FND500	1.80	b038	6.50	4081	.80	4585	2.10	R29125
2N5486	.90	7400	.60	74158	1.00	75451	.90			FND507	1.80			4082	.80	4597	3.45	820 OHM
2N5489	14.50	7402	.60	74160	1.00	75452	.90	FD1793 (8877)	39.00	FND800	3.50	OM335 22.50		4085	2.20	4599	7.25	R29130
2N5490	16.50	7403	.60	74161	1.20	75453	.90			TIL31A	2.95	OM350 10.50		4086	2.30	45104	7.85	1K OHM
2N5491	18.50	7404	.60	74162	1.20	75461	1.50	FD1795	39.00	TIL81A	2.95	IM65X08CPE 5.00		4089	3.50	45106	7.85	R29135
2N5492	18.50	7405	1.00	74163	1.40	75462	1.50	FD1797	39.00	TIL306	1.45			4093	.75	45107	7.25	1K2 OHM
2N5493	19.50	7406	1.00	74164	1.20	75471	3.00	WD1691	29.50	MAN7- (DL702)	3.50	XR2206	7.95	4094	3.35	45109	7.25	R29140
2N5494	2.50	7407	1.00	74165	1.20	75472	3.00	WD2143	14.50	MAN7- (DL704)	3.50	XR2207	7.95	4095	2.40	45112	7.85	1K5 OHM
2N5495	2.50	7408	1.00	74166	1.70	75491	2.00	WD1931	22.50			XR2208	6.90	4096	2.40			R29145
2N5496	2.50	7409	1.00	74167	2.20	75492	2.00	WD1933	34.00			XR2209	6.90	4097	6.50			1K8 OHM
2N5497	3.00	7410	1.00	74168	1.45	75493	3.00	WD1983	14.75	BPW50	2.50	XR2211	7.45	4098	2.90			R29150
2N5498	3.00	7411	1.00	74169	1.20	75494	3.00	WD1993	59.00	HP5082-2811	2.50	XR2216	5.90	4099	3.90			2K2 OHM
2N5499	3.00	7412	1.00	74170	1.40	75495	3.00	WD2123	26.50			XR2240	6.95	4104	6.90			R29155
2N5500	3.00	7413	1.00	74171	1.40	8123	4.00	WD2520	16.50	HLMP 6620	3.95	XR2243	7.95	4160	1.25			2K7 OHM
2N5501	3.00	7414	1.00	74172	1.10	8130	7.95	TR1602 (S1883)	8.50	COY89	1.50	XR8038	7.50	4161	1.25			R29160
2N5502	3.00	7415	1.00	74173	1.10	8131	7.95			MOC3011	2.95			4162	1.25			3K3 OHM
2N5503	3.00	7416	1.00	74174	1.20	8135	6.95	TR1863	8.90	MOC3020	2.50	ICC7660	12.50	4163	1.25			R29165
2N5504	3.00	7417	1.00	74175	1.20	8136	6.95	COM8116	24.00	MOC3021	2.95	95H90	8.50	4174	1.25			4K7 OHM
2N5505	3.00	7418	1.00	74176	1.20	8136	6.95	BR1941	23.00	LEDS		11C90	16.50	4175	1.60			R29170
2N5506	3.00	7419	1.00	74177	1.20	8136	6.95	CR78002A	59.90	3mm RED	25	LM7555	1.90	4194	1.95			5K6 OHM
2N5507	3.00	7420	1.00	74178	1.45	82S23	5.95			3mm YELLOW	30	LM7556	3.50	4402	1.00			R29175
2N5508	3.00	7421	1.00	74179	1.10	8311	5.95			3mm GREEN	15	MC10116L	1.50	4404	1.15			6K8 OHM
2N5509	3.00	7422	1.00	74180	1.20	8311	5.95			5mm RED	15	LM13600	3.95	4408	6.90			R29180
2N5510	3.00	7423	1.00	74181	1.20	8311	5.95			5mm YELLOW	30	LF13741	80	4409	13.50			8K2 OHM
2N5511	3.00	7424	1.00	74182	1.20	8311	5.95			5mm GREEN	30	LF13741-H	1.50	4410	11.50			R29185
2N5512	3.00	7425	1.00	74183	1.20	8311												

JUST GIVE US THE NUMBERS



Digital handheld multimeters are now quite common and relatively inexpensive. You can pay between \$40 and \$300+, depending on features and performance. Pay what you can afford — you'll likely have it for a long time. These two are typical of the variety available. The Univolt DT-845A (from Benelec, Sydney) features a rotary function selection switch and autoranging. The Parameters 7040 on the right features thumb-press (left hand) range and function select switches and comes with a carry case. Both cost under \$100.

to gigantic two-handed monstrosities used for cutting fencing wire, sidecutters are used for cutting component leads to length, cutting off excess leads after soldering, cutting hookup wire, etc. They're also good on toenails! Pay good money and get quality. This applies to all your tools. They last longer and work better.

Your sidecutters should have a precise cutting edge around 8-10 mm or so long, flush on one side so that you can get right up against a tag, terminal or printed circuit board. They should fit comfortably in your hand and have a spring return that is not too stiff. The handles should be covered in plastic insulation, mainly for comfort.

When using sidecutters on component 'pigtailed' (the stiff wire leads), the part cut off can fly away with some speed and force. Watch it! That's dangerous to eyes. Use the sidecutters so that the dross flies toward the bench or floor. Some brands of sidecutters feature an attachment that prevents the cut bits flying off.

You'll need two types of pliers. One

snub-nosed set with 'toothed' jaws. They should have jaws around 15-20 mm long. They're for gripping things, particularly component leads and nuts. As for the sidecutters, get a pair with insulated handles that fit comfortably in your hand and have a spring return that isn't too stiff.

You'll need a pair of flat long-nosed pliers, too. They're very useful for holding things in awkward places — and when you can't find the other pair! They should have jaws from, say, 40 mm to 80 mm long; with insulated handles, of course. Spring return is not necessary.

In screwdrivers, you'll need two types: flat-blade and Philips-head. In each, you'll need a 'medium' (5-6 mm shaft) and a 'small' (3-4 mm shaft). If you want to go "the whole hog", a set of 'precision' screwdrivers can be handy.

Many people consider "nut drivers" or "spintates" to be superfluous, but we consider them to be almost *indispensable*. Just two will carry you through most jobs: a 5 BA (6 mm across the flats) and an 8 BA

(4.25 mm across the flats).

Along with nut drivers, too many people, foolishly, consider a "wire-stripping" tool superfluous. Nothing could be further from the truth. Sure, you can *get by* without one, but you shouldn't on a regular basis. There are *lots* around. All we can advise is: *try before you buy*. Then buy something with which you feel comfortable.

The sort of *drilling* mostly required with electronic construction calls for a small diameter, high speed drill. Printed circuit boards, in particular, require small diameter holes and they need to be drilled at high speed — typically 5000-10 000 rpm. There are a number of small, hand-held drills on the market which will do the job admirably. Some are battery operated, some are run from a mains plugpack or power supply. Most component holes are drilled to either 0.8 or 1.0 mm diameter. However, a drill set ranging from 0.5 mm to 6.5 mm is very useful. Common sizes used for mounting mechanical components are 7 mm to 10 mm. For drills of this size, you'll need a conventional hand or electric drill.


For shaping, finishing or enlarging holes, a set of small files comes in handy. "Needle" files are generally useful for electronics work. What to get? Well, you should get one 'flat', one 'half-round', one 'rat-tail' and one 'triangular'.

Not essential, but useful, is a "jeweller's saw" or small jigsaw. With this you can cut small holes of varying shapes in thin metal or plastic (panels, for example) or printed circuit boards.

Some form of 'hobby' cutting knife (such as an "NT-cutter") is also useful. There's no need to suggest the myriad uses here, get one and it will find uses for itself!

That pretty well completes the mechanical aspects of the toolkit. You could, of course, fit out your 'workshop' with a drill press, lathe, vyse, grinder etc. But you're just starting out, remember?

THE ULTIMATE TEST INSTRUMENT?



An oscilloscope makes an extremely versatile test instrument. You can view waveforms, measure voltages, periods and frequency with one. Serious hobbyists eventually get one. This BWD oscilloscope is Australian made.

'Test' tools

With all the kit and kaboodle described before, you can put a project together, and it *might* work straight off. But the nature of human beings, and electronics, is such that it *might not*, too!

What you need at this stage, to 'trouble-shoot' or check the workings of a circuit, is a *multimeter*.

A multimeter is a tool that will measure all the basic electrical parameters of a circuit, component or whatever. In its basic form, a multimeter will measure *voltage*, *current* and *resistance*. Most multimeters, however, will have some added "feature" (intended to get you to buy that model, rather than the opposition's). Such features might include a transistor 'tester', capacitance measurement, etc.

With multimeters, in general, you 'gets what you pays for'. But that shouldn't stop you shopping around.

The first parameter to take into account when buying a multimeter, is *sensitivity*. This is expressed as 'so many ohms per volt'. Don't try to work that out just now. As a minimum, get a multimeter with a *basic* sensitivity of 20 000 ("20 k") ohms per volt. A sensitivity of 100 000 (100k) ohms per volt would be better.

There are two types of multimeter to choose from: *analogue* and *digital*. Analogue meters are generally the cheaper variety and have a 'needle' movement that moves over a scale. They're simple and the technology is as 'old as the hills'. You can pay anything from around \$8 to \$150 or so. The majority are designed for operating on a bench or in the hand. At the bottom end, they have 10 ranges or so. At the top end, they might have over 30 ranges.

In digital multimeters, there's a positively *huge* choice. For beginners, accuracy is not all that important. You can pay anything from about \$45 for a four-function, 3½-digit autoranging type to around \$300 for a top-line model. When deciding to buy, pick the features you feel are necessary to your interests, or pick something in the low-price bracket that offers value for money.

With multimeters, your first one won't be your last, by any measure, so plan on replacing it at some future date. Value for money is what you're looking for. We'll go into this in more depth later in the series.

There are plenty of other test instruments you can use, but the multimeter is probably the *basic* one you'll *always* have. As you progress, you can get *logic probes*, or an *oscilloscope* to show you waveforms, *signal* and *function generators* to produce test signals, etc, etc. The best way to go about it is: get them as you need them. Often, you can build your own test instruments for a fraction of the cost of ready-made commercial types. Sounds like a good basis for a simple project series!

Don't hang about — get started! ●

PROJECTS TO BUILD!



That's what the hobby is all about: Practical projects, fun projects. Build your own test instruments, hi-fi gear, battery chargers, metal detectors, 'toys', etc. Here's a sample of simple hobbyist projects we've published over the years. Once you get a bit of experience, you can tackle things as complex as a computer, complete stereo hi-fi amplifier, signal generator, etc.

Top quality Swiss made infra-red people sensor

The very latest: Swiss made quality detector actually senses human radiation — even from across a room! Virtually no false triggering, ultra reliable. Simple connection to our Security Centre (L-5100) and Bookshelf Control Module (L-5102). Cat L-5010


Two other models also available.

ONLY **\$119**



Microwave Sensor

Want to catch them in the act? Silent, invisible microwaves detect any movement in the target area and trigger the alarm device. 12V operated. Range up to 15 metres, attaches to any alarm system! Cat L-5000




Latest technology!

\$95

Ultrasonic Blaster!

The 'Claytons' alarm: the ideal alarm for those who don't want to put in alarms! This one is fully self contained, including siren speaker. Just place it on the shelf and its invisible ultrasonic rays detect movement. Fantastic for single room protection; can also be used as a sensor on a master alarm console. Includes sensitivity control, operates from external 12V battery, from mains via optional plug-pack with internal battery back-up. Has provision for external speaker, sensors, etc.



Cat L-5108


\$99

Infra-red Beam

Burglar Alarms ... Door Minders ... People Counters ... the applications are endless!

Both infra-red transmitter and receiver are in the same unit, with a reflector supplied to send the beam back. A sensitivity control allows 'fine tuning' to suit the location. Mains (240V) powered, with a 12V DC @ 1A output each time the beam is broken. The unit can be set for two modes: 'instant' (output while beam is broken) and 'intermittent' (outputs for five seconds after beam is broken).

Cat L-5050



ONLY **\$99**

Plus! Everything you need for no-fuss installation of your alarm system ... such as

Wire

Thin hook-up wire for easy concealment. Range of colours available. 10¢/metre or only \$8.00 per 100m roll.

Light-weight 'figure 8' twin conductor cable. One cable marked with tracer for instant recognition. Cat W-2010, 20¢/metre or only \$15.00 per 100 roll.

Why pay thousands for security?

It's so easy with these superb security system components from Dick Smith Electronics. Everything from the very latest in integrated circuit control units right through to the sensors you use to stop thieves before they get in!


Don't know what to do? No worries: our exclusive booklet 'How to install your own burglar alarm' will tell you how easy it is! Yes, YOU can put in your own fully professional quality alarm system at a tiny fraction of the cost of professional installation.

Professional Quality Security Centre

This is it! The most professional alarm system we've ever seen — and it's suitable for homes, offices, factories ... you name it! With six individual sectors all full controllable for instant or delayed alarm, each able to isolate and each triggerable by a huge range of sensors: the type of alarm used by banks, etc where security is paramount.

Imagine how it would protect your home!

The type of alarm system the professionals charge \$1000 or more to install!



Magnetic Switches

100% Hidden Magnetic (Reed) Door & Window Switches. What a great idea! Ideal for all alarm systems — usable in wood, aluminium & other doors/windows. They are covered by window/door when closed — no one knows they're there! Operates between 8 & 10mm.


Cat L-5212



ONLY **\$3.95**

Reed Switch/Magnet Set.

Mounted so the magnet holds the switch closed, if the door is opened, switch opens. Attaches to most alarm systems.



ONLY **\$2.75**

Cat L-5210

Tools

Standard Flat Blade or Philips Blade Screwdrivers at bargain prices: **Mini Size** — Flat Cat T-4010 @ 55¢. Philips Cat T-4020 @ 65¢. **Stubby Size** — Flat Cat T-4060 Philips Cat T-4065 Each \$1.75. **Popular Size** — Flat Cat T-4085 @ 85¢ Philips Cat T-4030 @ 75¢. **Heavy Size** — Flat only, Cat T-4100 @ \$1.95 each.

Soldering Irons:

240V 30W general purpose iron Cat T-1330 \$9.95. 12V 25W general purpose iron T-1920 \$9.95.

Solder to suit 1.25mm hobby pack Cat N-1638 \$1.20.

Do it yourself and save a fortune!

★★★★★ EXCLUSIVE ★★★★★

Our step-by-step guide makes it so easy to install your own alarm system to fully professional standards! Everything you need to know - and it's only \$1.95 or FREE with any alarm system from Dick Smith Electronics.



Features:


- Heavy duty steel case with security key lock and tamper protection.
- Internal mains power supply plus charger for (optional) back-up battery: room inside the case for battery.
- Latest 'wire-out-proof' sensor circuitry - suits both n/o and n/c sensors!
- Use with any type of intruder detection sensors.
- Isolate any sector(s) you wish: you can have alarm on in rest of house while you're asleep at night.
- Comprehensive installation manual supplied!

Cat L-5100

\$239

One step — and they're gone . . .

Hide a pressure mat under the carpet, a rug — even the lightweight Bill Sykes can't get past this one! Put one in front of your safe! Normally open contacts.



Cat L-5270

ONLY \$19⁵⁰


Stainless Steel Pliers/Nippers
Transistor Nipper Cat T-3205
Mini Flat Nose Cat T-3325
Mini Needle Nose Cat T-3570
Mini Long Nose Cat T-3565
And they're only \$8.50 a pair!

Big screamers!

Know what a crook hates most? Noise! Scare the pants off them with this high efficiency horn speaker. Connects to alarm speaker output. Really loud. Cat C-2705

Larger (127 x 200mm) horn with huge 15 watts rating. For the installations where a loud alarm is a must. Cat C-2718

Also ideal for PA use ONLY



ONLY \$10²⁵



\$27⁵⁰

Give em the gong!


Ultra Loud Bell. A great new addition to our range. Huge 8 inch fire bell with massive gonger, 12 volts operate at 300mA. Suitable for most alarm systems. Cat L-5280

Piezo Piercer!

What an amazing sound from such a little gizmo! Piezo alarm unit features inbuilt driving circuit so it operates direct from 12 volt supply. Unbelievable 120dB @ 1m output

Cat L-7025

\$34⁹⁵




\$14⁹⁵

Battery Back-up

12V 2.6AH Rechargeable Gell Cell. At last! A high current rechargeable battery ideal for alarm use. Fits perfectly into our new Security Centre, also great for other alarms. Easy to keep trickle charged.

Cat S-3320




\$24⁹⁵

Protect against fire!

Most alarms have provision for a fire sensor. Take advantage of it and protect your home and property! Use any number of sensors in likely 'hot spots'.

Cat L-5254

\$7⁹⁵



A799

DICK SMITH ELECTRONICS

PTY. LTD.

ETI August 1984 — 51

See our insert for address details



Hi-TECH LIGHT AND SOUND

HIRE * SALES * SERVICE

63 Hardgrave Road, West End 4101
Postal Address: P.O. Box 377, West End


Phone: (07) 44 4971

GENEROUS TRADE TERMS
AVAILABLE TO INSTALLERS

DON'T FORGET WE DO

Pinspots, Revolving Things for Ceilings,
Lightguns, Mirror Balls, UV, Smoke
Machines

**Zero
88
-FX4**



Combined Lighting + Strobe Controller -

featuring "button" control for
switching over - ALL LIGHTS OFF -
STROBE CHASE ON!
Will operate 4 channels of Inductive
Load Lighting + Remote Control on up to
4 Strobes.
Many other combinations, patterns and
displays controllable through the "all
button" keyboard.
A "Hi-Tech" controller at a "Low-Tech"
price.

**Special Offer
\$520.00**

PINSPOTS — HELICOPTERS — SCANNERS

Pinspot Par 36 inc. Lamp	\$38.00
Par 38 inc. Lamp	\$32.50
Pinspot Par 46 inc. Lamp	\$56.00
Optikinetics Sound Scanner P36 master	\$310.00
Optikinetics Sound Scanner P36 Slave	\$252.00
4 Head Helicopter	\$295.00

STROBES & CONTROLLERS

Ice Strobe Starflash	\$340.00
Optikinetics White Lightning	\$690.00
Optikinetics Strobe Control 4 Channel	\$295.00
Optikinetics Strobe Control 1 Channel	\$90.00
Egg Strobe (fits BC holder)	\$24.00

PROJECTORS

Optikinetics Solar 250 Projector	\$307.20
-------------------------------------	----------

CONSOLES

Matra Mono inc. T/tables	\$1595.00
Matra Stereo inc. T/tables	\$1995.00
Citronics Stereo inc. T/tables	\$1995.00

SPEAKER SYSTEMS

Matra 150W Disco Bin — RCF	\$895.00 pr
Matra Towers 15" JBL	\$1250.00 pr

TOUCH CONTROL PANELS

Ice 12 Way Key Flash Panel	\$760.00
Ice 12 Way Slave Pack	\$450.00
Ice 10 Way Electronic Switch Panel	\$533.00

MIXERS

Citronic SM330 6 Channel	\$695.00
Citronic SM440 6 Channel	\$1055.00
Citronic CS220 Microphone Mixer	\$829.00
Citronic CS460 6 Channel	\$1769.00
Citronic CSV 30 Video Control	\$1340.00
Suplex MX 3000	\$395.00

MIRROR EFFECTS

Mirrorball 8" less motor	\$29.50
Mirrorball 12" less motor	\$59.50
Mirrorball 18" less motor	\$92.50
Mirrorball 20" less motor	\$130.00
Mirrorball 12" Half Ceiling Mounting inc. motor	\$69.80
Mirrorball Motors	\$30.00
Battery Motors	\$8.90


CONTROLLERS

Citronics LU 4000	\$645.00
Matra 4CH	\$225.00
Mode Unit Five Master	\$1185.00
Mode Unit Five Zone Matrix	\$792.00
Mode Unit Five Slave	\$830.00
Zero 88 FX4	\$520.00
Zero 88 Micro 4	\$1260.00

STROBES

COLOUR STROBE

- probably the
best selling multi-purpose
Strobe in QLD.
Solidly built. Highly
polished reflector.
Sound activated with
sensitivity control at
rear. VERY POWERFUL.
Red Blue Yellow Green



\$46.90

AMPLIFIERS

Matra 100 + 100W	\$690.00
ZPE 500W Mosfet	\$1080.00
ZPE 600W Mosfet	\$1650.00
ZPE 1000W Mosfet	\$1950.00

FOG & SMOKE MACHINES

Le-Maitre Mini Mist Smoke Machine	\$968.00
Le-Maitre Mini Mist Canisters	\$10.91
DS Smoke Machine	\$845.00

ROPE LIGHTS

7M 4 Channel 6 Colours	\$99.00
4Ch Controllers	\$90.00

Mail Orders + Installations + Other Info

CREDIT CARDS

Bankcard, M/Card, AGC Credit Line

CLUB INSTALLATIONS

Excellent service through Australia.

INSTALLERS

Write to us for attractive Trade
Terms.

MAIL ORDERS (AUST)

Add packing & post (P&P) as follows
(Aust. only) MINIMUM MAIL ORDER \$25
Goods \$25-\$49 P&P\$3.50
Goods \$50-\$99 P&P\$5.00
Goods \$100-\$149 P&P\$7.50
Goods \$150-\$199 P&P\$10.00

Goods \$200 + Add 5% to Order value
or otherwise by individual quotation.

Send to: **HI-TECH LIGHT & SOUND**
63 Hardgrave Rd.
West End Q. 4101.

WE CAN SUPPLY YOUR DISCO NEEDS

WRITE OR CALL FOR FURTHER INFORMATION ON OUR
EXTENSIVE RANGE OF SOUND & LIGHTING EQUIPMENT

New technology for TVs

The first digital TV, recently released on the market in Japan, was manufactured by National Panasonic's parent company, Matsushita Electric Industrial Co. It is claimed that the digital video circuitry will provide crisper images, expanded capabilities and cost less to make.

Current analogue TV sets generate pictures by processing analogue signals which are sent out by TV stations. Matsushita's digital TV converts these analogue video signals into digital signals, giving a claimed cleaner image due to reduction of spots, screen flickering and colour saturation.

The digital circuitry was developed by a division of ITT in West Germany, combined with Matsushita-originated peripherals and memories to provide 'window' monitoring displays inset on the normal picture.

The monitor mode provides two pictures, one at full-screen size and the other a 150 mm inset. The smaller picture is produced with analogue signals from a VCR, video disc player or

video camera.

The signals are analysed in units of 96 x 128 picture elements, and each pixel is converted to a digital code. By this process, each picture frame is stored in the 64K semiconductor memory and a memory-control LSI synthesises the picture frames with the full-screen display. The smaller 'window' image can be erased and moved around on the screen.

This multifunction digital TV can easily incorporate a tuner and adaptor for videotext and Teletext and will hookup directly with home computers, stereos, VCRs and other forms of component TV. It has one 21-pin and one eight-pin RGB input terminals and three video input terminals, and switching for

combining TV or prerecorded video from video cassette or video disc players. The picture tube has a 0.55 mm mask pitch for high-resolution display of text.

It has one-touch white balance and full remote control which can be used to adjust all functions and changes in picture contrast and brightness, tint and colour. The remote control unit currently controls 61 functions, including various functions of any VCR, video disc player, personal computer or video camera.

Although the set performs many complex image-manipulation and enhancement functions, it has about one-fifth the number of components in its video circuitry as an ordinary analogue TV set. It measures 481 x 503 x 518 mm and weighs 27.5 kg. Sound output through the multiplex audio system is 5 W per channel, through two 120 mm diameter speakers.

Hitachi is also planning to re-

lease a new TV soon. The 480 mm TV includes ghost-chasing circuitry that reduces the presence of secondary images that result in interference and overlapping signals.

Hitachi conducted a survey in Japan which showed that about 78% of home TV reception is haunted by ghosts that appear as shadow images 5-150 mm to the right of the regular image. Compensating circuitry reduces the video signal-to-noise ratio by 14-20 dB, which reduces the ghost image to between one-fifth and one-tenth of its original intensity, depending on the strength of the interfering signal.

Hitachi has filed 56 patent applications for the two-stage, CCD (charge coupled device), transverse filter method that it uses to wipe out the ghosts with digital conversion of misaligned signals. The circuit kicks in within 10 seconds after the channel is changed with the electronic tuner.

JVC stereo video

The Japanese manufacturer, JVC, has just announced the release of its latest video recorder the HR D225.


The stereo facility, with its Dolby B noise reduction circuitry, can record FM radio/TV simulcasts or give full stereo sound to your favourite video tapes.

A high-speed visual search system, Shuttle Search, plays the tape at nine times normal speed in either direction, making it quick and easy to locate

any desired programme segment. Still frame and frame advance facilities are also built in.

There is a special picture sharpness control, which can vary the video image to the degree of sharpness most pleasing to your eye. The HR D225 has presetting facilities for 16 broadcast channels, and a new up/down facility for channel scanning.

The unit has an instant recording facility which double as a sleep timer for automatic shut-off of recordings, and a 14 day/8 event program timer which offers almost limitless viewing flexibility.



AM stereo — still a debacle

Radio i, in Auckland New Zealand, claims to be the first station outside North America to broadcast in AM stereo, having introduced transmissions earlier this year.

The Harris system is used for the broadcasts of 1X1 Auckland on 1332 kHz. Radio i commenced operation in 1969 as a private commercial station. It features an 'easy listening' format, often giving it top ratings in Auckland in competition with

Radio New Zealand 1ZB.

The station's Managing Director, Mr Graeme Edwin, said that five special listening posts had been established in stores around Auckland to give the public the chance to hear the station in stereo. Radio i has imported Sony receivers for this purpose.

Although receivers are not widely available in NZ yet, Radio i has taken this pioneering step because the station has

no doubt that AM stereo will be the sound of the future.

In Australia, 12 stations have been carrying out tests in AM stereo. Unfortunately four incompatible systems are being tested by different stations. 2CH Sydney is testing with the Kahn system, while other stations are using either Motorola, Magnavox or Harris. One receiver being marketed is capable of tuning to any of the four stereo systems.


The Australian Department of Communications has approved experimental transmissions for all four systems. The New Zealand Post Office has approved the Harris system in New Zealand.

Present radio receivers cannot be economically modified to accept AM stereo, but the introduction of any new system will not affect the old receivers.

— Arthur Cushen

YAMAHA CD-X1

**Topline
performance
Holden
price!**



If you've been waiting for the price of CD players to drop, or waiting for superior CD players to arrive, you don't have to wait any longer. The CD-X1 has the performance, and at the right price.

WHEN YAMAHA released the CD-X1 compact disc player with a recommended retail price of almost one-third of their original CD-1 model, they really set their competition a merry chase. Although the CD-1 was over-priced, the CD-X1 is most probably under-priced in the eyes of Yamaha's competition.

The Yamaha CD-1 compact disc player was unquestionably an excellent, but complex piece of equipment. It incorporated double digital circuitry and an array of complex electronic refinements that overwhelmed many intending purchasers. The sales were slow. So the design team started developing a unit which would offer as good a performance as the CD-1, with a price that could not be resisted.

The secret of the CD-X1 is basically a metamorphosis of the bulk of the original electronic circuitry in the CD-1 compact

disc player into just two large scale integrated circuits which are electronic 'works of art'. One LSI circuit has 64 pins and the other has 40 pins. The metamorphosis also extended into the mechanical design as the case has become a complex but beautiful example of plastic moulding and cost effective engineering design.

The engineers have completely redesigned the laser pick-up system into a new three-beam configuration which is less than half the size of the original unit. It has markedly superior tracking capabilities to almost any other CD player on the market.

The basis of the digital system has been modified so that the digital-to-analogue conversion rate is doubled. The digital filter operates at 88.2 kHz instead of 44.1 kHz so that a simpler filter with smoother and more gentle skirt can be

used. This results in an improved phase response and achieves superior results at a lower cost when compared to the original unit.

Features

The frontal appearance of the CD-X1 bears a fleeting resemblance to the CD-1, as well as to some of the competitors' compact disc players. Yamaha also believe that 'black is beautiful' and the CD-X1 makes a feature of black buttons and white lettering to achieve an extremely neat and functional appearance.

The disc drawer is located on the left-hand side of the main panel and below it is the power 'on/off' switch. When the unit is first switched on without a disc in the drawer, a flashing green light softly illuminates the area below the bottom of the disc drawer. When a disc is loaded the light stops flashing.

In the middle of the panel is an 'open/close' button which must be pressed to open the drawer but is not essential to close the drawer. Unlike some of the competitors' units, you can push on the front of the drawer and it will close without trauma; or you can press the 'play' button and the drawer will automatically close and the disc start to play. Below the

YAMAHA CD-X1 COMPACT DISC PLAYER


Dimensions: 340 mm wide x 92 mm high x 290 mm deep.

Weight: 3.6 kg

Price: Rrp \$599.

Manufacturer: Yamaha Nippon Gakki Cox Ltd, Hamamatsu, Japan.

Distributor: Rose Music, 28 Kent St, Belmore NSW 2142.
(02)750-8999.



Simple design. The front panel features clean lines and simple layout of the controls and displays.

'open/close' button is a 'play mode' switch which selects three functions: 'auto', 'normal' and 'single'.

In the 'auto' mode playing will commence as soon as the power is switched on (if a disc is already in the drawer) or it will play at the pre-programming time, if an automatic timer is connected. In the 'normal' mode the playback begins when the 'play' button is pressed, while in the 'single' mode the unit will stop playing after each individual track and then has to be restarted with the 'play' button.

On the right-hand side of the front is a large 'play/pause' button which sensibly provides both functions. On the extreme right-hand side of the panel is the 'stop' button whose function is self-explanatory. In the middle of the panel is a small, clear, plastic escutcheon. Behind it the music number is indicated on the left-hand side; the elapsed time of the selection being played, or the remaining time of the disc is on the right-hand side.

The music number display, unlike some

of controls. The designers claim that these buttons are so simple that they virtually explain themselves.

My staff and I do not support that view as two of my staff tried to use the controls without reference to the handbook and found that they ended up with somewhat different results to what they had expected. I believe that the days of picking up a piece of equipment and being able to use it correctly without reference to the handbook are long gone.

The first of these controls is the 'on/off' repeat button which allows you to either replay the whole disc, or just those sections that have been programmed into the memory using the three memory control buttons. The second 'repeat' switch is labelled 'A-B' and is pressed once at the start of the section whose cyclical playback is required (during the normal replay cycle) and pressed again at the end of that sequence. The programme section between the two specified points automatically replays 'over and over again'; as long




Figure 1.

Engineering masterpiece — in plastic! The disc drawer and transport are constructed of ingeniously designed plastic components, as is most of the cabinet. The single printed circuit board containing all the electronics is at right. Note the LSI chips at the front.


of the other units on the market, works all the way up to '99', which is fortunate as many of my latest CD test discs contain 99 tracks. The escutcheon also contains four illuminated displays which indicate which choice of a possible series of functions has been selected. These are 'repeat', 'A-B repeat', 'memory' and 'play' modes.

On the bottom of the front panel are nine buttons which provide a wide range


as you so desire, until you've had enough.

This particular feature has unquestioned benefits for the technical reviewer who can select a portion of a test disc and replay it through his analysis equipment, without the problems that are common with a record player. Its uses for other purposes is far less obvious, although it will no doubt prove to be an excellent conversation piece. ►

HANDLING COMPACT DISCS



- Always place the compact disc in the disc tray with the label facing upward (Compact discs can be played only on one side.)
- To remove a disc from its storage case, press down on the centre of the case and lift the disc out, holding it carefully by the edges.



- Fingermarks and dust should be carefully wiped off the disc's recorded surface with a soft cloth. Unlike conventional records, the compact disc has no grooves to collect dust and microscopic debris so gently wiping with a soft cloth should remove most particles. Wipe in a straight motion from the inside to the outside of the disc. Small dust particles and light stains will have absolutely no effect on reproduction quality.




- Never use such chemicals as record sprays, antistatic sprays or fluid, benzene or thinner to clean compact discs. Such chemicals would irreparably damage the disc's plastic surface.
- Discs should be returned to their cases after use to avoid serious scratches that could cause the laser pickup to "skip".
- Don't expose discs to direct sunlight or high humidity and temperature for extended periods. Long exposure to high temperatures can warp the disc.
- Don't stick paper or don't write anything with ballpoint pen on the surface of the label side.

(Material courtesy Yamaha)



Louis A. Challis
& Associates Pty LtdFREQUENCY
RESPONSE OFYAMAHA CD-XI
COMPACT DISC
PLAYER

1 dB/Division



 Recording No. Sign. Date 21-6-84 Potentiometer 50 dB Zero Level -50 D A B C Lin.
 5 10 20 50 100 200 500 1000 2000 5000 10000 20000 50000 100000
 1st Range 50 dB Rectifier RMS Lower Lim. Freq. 2 Hz Writing Speed 50 mm/sec Paper Speed 3 mm/sec
Louis A. Challis
& Associates Pty LtdFREQUENCY
RESPONSE OFYAMAHA CD-XI
COMPACT DISC
PLAYER

EXPANDED SCALE

0.2 dB/Division


 Recording No. Sign. Date 21-6-84 Potentiometer 10 dB Zero Level -20 dB D A B C Lin.
 5 10 20 50 100 200 500 1000 2000 5000 10000 20000 50000 100000 2
 1st Range 10 dB Rectifier RMS Lower Lim. Freq. 2 Hz Writing Speed 50 mm/sec Paper Speed 3 mm/sec


100 Hz



1 kHz

The three memory buttons are labelled 'store', 'cancel' and 'check/RT'. When playing the disc through in the 'music search' mode, looking for a specific selection for which a subsequent memory cycle is desired, one presses the memory 'store' button. On moving further forwards or backwards through the disc one repeats this function in order to store the required sequence in the memory.

By using these two switches, together with the forward and backward music search switches, one does have a more tedious and less direct control facility than that provided by CD players with a numeric key pad. What you are getting, however, is the same function without the complexity, the size or the cost of the competing units.

The third memory switched labelled 'check/RT' can be used in two different ways. If you press the 'stop' button and press 'check/RT' sequentially, it will display each of the tracks selected, together with the appropriate total recording time of that track and the remaining programmed track times. If the 'check/RT' switch is held down during playback it will at first display the same information and, after three seconds, the elapsed time on the track actually being played.


The four music search buttons are labelled '—', '<<<', '>>>' and '+'. They allow you to index forwards or backwards,

by individual track numbers, using the \pm buttons and fast-forward and fast-reverse buttons. The fast-forward and fast-reverse buttons operate slowly for the first three seconds, and then engage in a high speed mode which simultaneously reduces the unit's playback volume to protect your amplifier and speakers. During 'pause' these controls increment forward or reverse in one minute intervals of the track content; this is particularly convenient if you know where a section of music begins or ends.

The rear of the player is particularly sparse with a pair of coaxial sockets and a double insulated mains lead which has been sensibly designed for only 220/240 volts operation. The front, sides and rear of the cabinet is fabricated from moulded plastic but use screwed-on metallic top and bottom panels to provide rigidity, strength and access convenience.

The inside of the cabinet using a wide range of different plastics, some metal and many ingeniously designed plastic inserts. The tray mechanism is worthy of special comment as many of its elements look like metal but are, in fact, ingeniously designed pieces of plastic.

The circuitry uses only two printed circuit boards which are particularly small. These use a phenolic material but are, nonetheless, executed to a high standard. The underside of the boards is fully pro-



By comparison. The linearity of the CD-X1 is "... extremely good all the way down to -60 dB where it is better than the CD-1 (reviewed Sept. '83), but is slightly inferior over the -80 dB to -90 dB range".

tected by masking over the laminate. Even though they are simply constructed, their operation is complex.

The electronic circuitry on the main pc board (see Figure 1) consists of integrated (LSI) circuits which have replaced literally dozens of other integrated circuits, transistors, diodes and components. This has resulted in a printed circuit board that looks only slightly more complex than a transistor radio.

MEASURED PERFORMANCE OF YAMAHA CD-X1 SERIAL NO. 26867

DISTORTION

AT MAXIMUM OUTPUT LEVEL = 0 dB

	100 Hz	1 kHz	10 kHz	
2ND	-106.2	-114.3	-85.6	dB
3RD	-88.5	-105.7	--	dB
4TH	-107.3	-107.9	--	dB
5TH	-105.2	-106.2	--	dB
T.H.D.	-88.3	-101.5	--	dB
	0.0038	0.00084	0.0052	%

AT INDICATED LEVELS FREQUENCY = 1 kHz

LEVEL	-10dB	-20dB	-40dB	-60dB	-80dB	
2ND	-84.5	-101.1	-84.2	-57.9	-27.5	dB
3RD	-90.4	-88.4	-72.4	-43.3	-21.9	dB
4TH	-97.4	-104.9	-82.1	-57.5	-28.5	dB
5TH	-110.7	-92.0	-72.3	-42.4	-40.6	dB
T.H.D.	-83.3	-86.6	-68.9	-39.7	-20.1	dB
	0.007	0.0047	0.036	1.04	9.9	%

EMPHASIS

FREQUENCY	RECORDED LEVEL	OUTPUT LEVEL	OUTPUT LEVEL
		(LEFT)	(RIGHT)
1 kHz	-0.37 dB	-0.2 dB	-0.2 dB
5 kHz	-4.53 dB	-4.4 dB	-4.3 dB
16 kHz	-9.04 dB	-9.9 dB	-9.5 dB

COMPACT DISC PLAYER DATA SHEET

MEASURED PERFORMANCE OF YAMAHA CD-X1 SERIAL NO. 26867

FREQUENCY RESPONSE

FREQUENCY	OUTPUT LEVEL dB V
1.0 kHz	+6.5
20 Hz	+6.6
40 Hz	+6.6
100 Hz	+6.6
200 Hz	+6.6
500 Hz	+6.5
1.0 kHz	+6.5
5.0 kHz	+6.4
7.0 kHz	+6.3
10.0 kHz	+6.3
16.0 kHz	+6.0
18.0 kHz	+6.3
20.0 kHz	+5.9

LINEARITY

RECORDED LEVEL dB	OUTPUT LEVEL dB
0.0	0.0
-1.0	-1.0
-3.0	-3.0
-6.0	-6.0
-10.0	-10.0
-20.0	-20.0
-30.0	-30.0
-40.0	-40.0
-50.0	-49.9
-60.0	-59.8
-70.0	-69.3
-80.0	-78.0
-90.0	-84.7

SIGNAL TO NOISE RATIO

WITHOUT EMPHASIS	93.4 dB (Lin) 99.1 dB(A)
WITH EMPHASIS	94.0 dB (Lin) 101.5 dB(A)

CHANNEL SEPARATION

FREQUENCY	RIGHT INTO LEFT dB	LEFT INTO RIGHT dB
100 Hz	-95.1	-94.9
1 kHz	-84.4	-84.0
10 kHz	-64.2	-65.0
20 kHz	-57.0	-58.9

Objective testing

The objective testing of this unit proved to be even more simple than when we reviewed the CD-1 (almost one year ago). The frequency response is extremely flat, as both the normal level recording and the expanded scale level recordings show. The unit exhibits a miniscule 0.6 dB rise between 18 kHz and 20 kHz, but is virtually ruler-flat everywhere else.

The digital-to-analogue output conversion linearity is extremely good all the way down to -60 dB where it is better than the CD-1, but is slightly inferior over the -80 dB to -90 dB range.

The signal-to-noise ratio without emphasis is almost identical to the CD-1, but is inferior with emphasis at 94 dB unweighted and 101.5 dB A-weighted. The channel separations of the CD-X1 is 5.5-6 dB lower than claimed by the manufacturer at 1 kHz and not nearly as good as that provided by the CD-1. Before you get disturbed, however, it should be pointed out that these levels of separation are still so much better than required that it does not really constitute a loss of effective performance.

The distortion figures of the CD-X1 at 0 VU are much better than claimed by the manufacturer, and also much better than achieved by the CD-1. I have compared the individual harmonic distortion figures against those of the CD-X1 and these reveal that the CD-X1 is superior at each of

the test levels, with the exception of -10 dB, all the way down to -80 dB. Even the differences at -10 dB are inconsequential, so I am satisfied that the large scale integrated circuitry has achieved the two most important functions that the designers set out to provide.

It has one other attribute that most other CD players can't match. It can track all of our eccentric test discs at first go, including the nasty one with ± 1 mm eccentricity. All of the other objective testing confirms that the basic performance parameters of the CD-X1 are on a par with any other CD player on the market, irrespective of its price.

Subjective testing

The subjective testing of this unit revealed that the functional controls, although deliberately simple, achieve a degree of functional simplicity which I am sure you would appreciate as much as I did. This unit has not been designed for a computer fadist, for whom numeric key pads are stock-in-trade. It has been designed for someone who just wants to play music.

Although I have now tested more than 15 CD players, I found that I did not miss the more advanced control functions that are on many of the other players. I could achieve almost as much without any noticeably greater effort (except with discs containing 99 tracks).

When I received this player I was given two Denon PCM digitally recorded discs from Japan. These typify the best in the new generation of digitally recorded compact discs; the quality has not been compromised by either using old analogue recordings (some companies are doing this), or sloppy recording techniques or inadequate studios, which can be clearly discerned in many of the latest discs.

The subjective testing was done using a disc of Jean Jacques Kantorow performing J. S. Bach's Violin Concerto in D Minor (38c37-7096). It is a brilliant rendition of violin music at its absolute best and it left a spellbinding impression.

This was eclipsed by Jacques Rouvier's piano rendition of Debussy's "Preludes", a masterful rendition of an absolutely lyrical piece of music.

The CD-X1 produced music which was superb, highlighting the excellence of its design. It convinced me that the CD-X1 is a true second generation CD player in the fullest sense of the words. It also convinced me that it is essential to select your CD discs from what I would describe as second generation software, in order to obtain the full benefits of the medium.

If you have been waiting for the price of CD players to drop or for superior CD players to arrive, I suggest your wait is over. The CD-X1 provides the performance and offers it at the right price. ●



CACOPHONY SALE!! MASSIVE SCOOP PURCHASE HUNDREDS OF APPLICATIONS FROM ONLY 75¢!!!!

Jaycar has bought the entire surplus stock of a coaxially mounted electric bell - as used in the Telecom 'Gondola' telephone! This unique bell is actually TWO bells - one mounted coaxially inside the other. The striker is mounted between the rims of the bells and is electromechanically driven. The unit runs on AC from about 17-48V.

The exciting part, however, is the price!! We purchased the bells FAR BELOW MANUFACTURERS COST - so YOU REAP THE BENEFIT!!
Cat. LA-5270
START YOUR OWN CACOPHONY!!
1-9 \$1.50 ea: 10-24 \$1.25 ea:
25-99 \$1.00 ea: 100+ 75¢ ea

SMOKE DETECTORS BACK!!

BARGAIN OF THE CENTURY


Once again we have made a scoop purchase of ionisation chamber type smoke detectors. When we had this product before we sold many thousands at our ridiculously low prices. We sold out of course but NOW THEY'RE BACK!!

The smoke detector is completely self-contained, is round and measures a compact 115mm diameter and 40mm deep. Fixing screws and masonry plugs are provided along with 9V battery and very comprehensive instruction manual.

The "Smoke Sentry" once sold for \$49 and frankly was a flop at that price. Despite the fact that every home should have at least one, people considered that their children and their own lives were not worth that amount. But now you have NO EXCUSE! Once again Jaycar has made a MASSIVE SCOOP PURCHASE of SMOKE DETECTORS below importers COST! We pass the savings on to you!

If you missed out before HURRY this time. Don't be disappointed!!
Cat. LA-5090

\$19.95 10+
1-9 Pcs **\$17.95**



MICROBEE DUST COVER

This great new, clear cover will keep dust and grime and all the nasties off your MicroBee. Contacts on the keys will last much longer. Can be removed in a moment. Antistatic treated to repel dust.
Cat. XA-5575 **\$9.50**

VOLTAGE REGULATORS

We have had a large demand to expand our range of Voltage Regulators. So here's two new ones in TO-220 flat plastic packs.

7809 Positive 9 volt 1A

Cat. ZV-1509 **\$1.05 ea - 10 up 95¢ ea**

7824 Positive 24 volt 1A

Cat. ZV-1524 **\$1.05 ea - 10 up 95¢ ea**

LM 1458N IC

Dual Operational Amp


(Specs supplied upon request only)

Cat. ZL-3753

NORMALLY \$1.50

AUGUST ONLY 50¢

10 or more 45¢ each




JEWELLER'S SCREWDRIVER SET BARGAIN!

A vinyl case containing 6 pieces of high quality plated Jewellers screwdrivers. AN ABSOLUTE MUST in every workshop.

GRAB ONE IN MAY AT A BARGAIN PRICE!
NORMALLY \$3.95 - THIS MONTH \$2.95
SAVE 25% - Cat. TH-2005

25% OFF



240V CASSETTE HEAD
DEMAGNETISER

MASSIVE
SAVING

\$5.95 -

SAVE \$2.55

We have made a massive scoop purchase of this popular item. Normally \$8.50 each



MASSIVE PRICE BREAKTHROUGH!

Jaycar has made a sensational purchase of Belt Drive Turntables - BELOW Manufacturers Cost!! Because of our buy we can pass them on to you at a MASSIVE SAVING.

The Turntables are made in England by B.S.R. They are unmounted and suitable for Disco Consoles, 3-in-1's etc. They are also ideal as replacements for existing 3-in-1 sets. (See specifications).

But there is an aspect that is really amazing! You can work the Turntable from 9-12V DC. This means that you can run the unit from a car or truck!! (The AA0292 model can of course run on 240V mains).


The Turntable features quality Belt Drive operation, lightweight Transcription type arm, Cueing facility and Stereo Ceramic cartridge with Diamond Stylus. The platter has calibration markings to check speed. A simple neon on 240V will "strobe" to the markings. Whilst the 33 & 45 rpm speed has been accurately set in the factory, you have the facility to make pitch adjustments underneath the turntable.

The DC Motor Drive (as used in the best turntables) is electronically controlled!!

Each unit comes with complete instructions. Quantity limited! You will have to hurry to avoid disappointment.

SPECIFICATIONS:

- ★ Dimensions 330(W) x 285(D) x 60(H)mm overall
- ★ Platter diameter 280mm
- ★ 2 speed - 33 & 45 rpm (internally adjustable)
- ★ Pick-up arm counterbalanced type with cueing facility
- ★ Pick-up ceramic (stereo) with diamond stylus
- ★ Turntable operation - auto stop, will return to rest automatically. Turntable chassis is sprung on all corners with transit screws & clips ★ Weight 1.5kg
- ★ Output stereo RCA sockets underneath unit



ELECTRONIC BELT DRIVE TURNTABLE BSR QUALITY



Check the price! Cat. AA-0290
(Requires 9-12V DC @ 500mA)

ONLY \$29.95

240V version - (includes 12V 500mA adaptor)

ONLY \$39.95

Cat. AA-0292
(Due to the weight of the unit post and packing is \$5 NOT \$4.50).

"JET PHONE" ADAPTOR - NEW - IDEAL FOR AIR TRAVELLERS!!

How many times do you travel by air? If you are a regular traveller in economy, you will be undoubtedly familiar with the plastic 'pneumatic' type of stereo headphones. Well, we think that they are hopeless!!

They are uncomfortable (in our opinion) and unless you get a good fit, the sound quality is poor. Wouldn't it be nice to be able to use your OWN high quality headphones in flight?

NOW YOU CAN!!

The Jaycar AA-2040 JET PHONE ADAPTOR plugs into the two air sockets on the armrest. You then plug your headphones into the adaptor for comfortable Hi Fi sound!!

BRILLIANT AND INEXPENSIVE!!

**Jaycar
ELECTRONICS**

Incorporating
ELECTRONIC AGENCIES
NUMBER 1 FOR KITS

SHOWROOMS

SYDNEY

117 YORK STREET

Tel: (02) 264 6688 & (02) 267 1614

Telex: 72293

CARLINGFORD

Cnr. CARLINGFORD & PENNANT
HILLS ROAD

Tel: (02) 872 4444

CONCORD

115-117 PARRAMATTA ROAD

Tel: (02) 745 3077

HURSTVILLE

121 FOREST ROAD

Tel: (02) 570 7000

**MAIL ORDERS
& CORRESPONDENCE**

P.O. BOX 185


CONCORD, 2137

Tel: (02) 745 3077

JAYCAR - No1 FOR SPEAKERS

SENSATIONAL DEALS ON 3-WAY SPEAKER SYSTEMS!!

A massive scoop purchase of factory distress stock has enabled us to pass on unbelievable prices on quality speaker systems. The component speakers in these systems are normally incorporated into cabinets for many well known national brand HI FI companies. Each speaker is factory guaranteed for 90 days, however we doubt whether you will ever need to worry about it.



8" 3 WAY SYSTEM

Superb 8" woofer with foam surround suspension and heavy magnet assembly with sealed back midrange and tweeter. System impedance 8 ohms. Power handling 40 watts rms. Crossover capacitors and connecting diagram and recommended 8" cabinet detail drawing supplied.
Cat. CS-2453 (2 required for stereo)

\$29.95/set



10" 3 WAY SYSTEM

Once again, a high quality 10" woofer with higher power, sealed back midrange and tweeter. System impedance 8 ohms. In addition a quality Pioneer 3-way crossover is provided at no extra charge. Connection instructions are also provided as well as recommended 10" cabinet plans.

Cat. CS-2454 (2 required for stereo)
INCLUDES PIONEER 3-WAY CROSSOVER!!

\$39.95/set

JAYCAR -

WELCOMES YOU TO A WONDERLAND OF ELECTRONICS

6" WIDERANGE

4 ohm impedance. Suitable for cars, or two in a box for extension speaker system. Very high quality curvilinear cone. Normally sells for **\$6.95** each. Less than 1/2 normal cost!
Cat. AS-3011

\$2.99 ea

10 up

\$2.50 ea


PHILIPS 12" WOOFER

We have made a MASSIVE SCOOP purchase of genuine quality PHILIPS European made 12" HI FI woofers. These are used in the fabulous ETI4000 series kits. 100 watts rms power handling.

CATALOGUE PRICE \$99.50

THIS MONTH ONLY \$59.50

SAVE A WHOPPING \$40.00!!



POST & PACKING CHARGES

\$5 - \$9.99	\$1.50
\$10 - \$24.99	\$3.20
\$25 - \$49.99	\$4.50
\$50 - \$99.99	\$6.50
\$100 - \$198	\$8.00
Over \$199	\$10.00

COMET ROAD FREIGHT ANYWHERE IN AUSTRALIA ONLY \$12.00

SHOP HOURS

CARLINGFORD, CONCORD & HURSTVILLE

Mon - Fri: 9 am - 5.30 pm
Sat: 9 am - 12 pm

Thurs Night: 8.30 pm (Not Concord)

SHOP HOURS SYDNEY

Mon - Fri: 8.30 am - 5.30 pm

Sat: 8.30 am - 12 pm

Thurs Night: 8.30 pm

MAIL ORDER BY

bankcard

VIA YOUR PHONE



MasterCard

VISA

TAKES STANDARD 8" SPEAKERS

FROM 99¢

8" CEILING GRILLES

Will they ever be this cheap again?

Once again - a massive scoop purchase with a difference. We have purchased a very large quantity of 'reject' grilles. They are rejects because they have small flaws in the mouldings. Most people however cannot pick the flaws if allowed to examine the grille. Imagine what the flaws look like *if* just up on the ceiling! Naturally we are offering a massive saving over normal units which we also sell. Exactly the same units (sans flaws) have been sold throughout Australia in the 10's of 000's. The perfect ones sell for around \$2.95 - at least one company sells them for well over \$3.00.
Cat. AX-3560

PA. INSTALLERS - GO FOR IT!

PRICES INCLUDE TAX

SCOOP! WHAT PRICE US?

1-4 UNITS \$1.50
5-19 UNITS \$1.25
20-49 UNITS \$1.15
50 + UNITS 99¢

10" ELECTRIC GUITAR SPEAKER



Quality Pioneer brand - check the specs! Check the price!!
HURRY

Impedance	8 ohms
Voice Coil dia.	1 1/2"
Power Rating	60W (RMS)
Resonant Frequency	80Hz
Sensitivity	98(dB/W)
Response	80Hz - 7,000Hz
Total Flux	61,100 Maxwell
Flux Density	8,300 Gauss
Net Weight	1,540 grams

CATALOGUE PRICE \$39.95

ONLY \$29.95

ASK FOR A NEW CATALOGUE!!

Mail Order customers, if you have not seen our new catalogue, boy are you missing out! If, (or when) you next buy from us by mail order just ask for a catalogue. It will be sent FREE with your order! If you have one and want one for a friend, that's fine too! Just ask!


8" TWIN-CONE HI FI

20 watts rms with whizzer cone. Air suspension type. Low free air resonance. Normally this speaker sells for around **\$19.95**. The Jaycar massive scoop purchase enables you to buy them this month at only **\$9.95**.

AN INCREDIBLE 50% SAVING!!

The stock WON'T LAST AT THIS PRICE - HURRY!!
Cat. CE-2330

**NORMALLY \$19.95
THIS MONTH \$9.95**



DENON CD TEST DISC

Louis Challis

This test disc is one of the best bargains of 1984. If you're not planning to buy it then you're obviously not seriously involved with high fidelity as it contains so much invaluable testing information. It gives you the equivalent of more than \$10 000 of test equipment for less than \$20.

TEST RESULTS

To test a disc like the Denon Audio Technical CD test disc is 'a little hairy'. Our approach was to inter-compare measurements of what are nominally the same signals from four different test discs on two CD players, the Yamaha CD-X1 and the Sony CDP-101. The results of these tests provided measurable and significant differences in performance. Thus, by way of example, the harmonic distortion with the 1 kHz signal on the Sony Type 3 disc provided the following results:

Measured Distortion Performance of Denon Test Disc c.f. Sony Test Disc

AT MAXIMUM OUTPUT LEVEL = 0 dB

	Sony	Denon	Sony	Denon	
	1000kHz	1001 Hz	100 Hz	100 Hz	
2ND	- 111.4	- 111.5	- 106.2	- 103.0	dB
3RD	- 115.1	- 115.2	- 88.5	- 88.7	dB
4TH	- 107.4	- 107.0	- 107.3	- 106.7	dB
5TH	- 105.9	- 119.0	- 105.2	- 115.6	dB

Louis A. Challis

DENON AUDIO TECHNICAL CD TEST DISC

Disc No: 38C39-7145 (Produced May, 1984).

Price: Rrp \$19.95.

Manufacturer: Nippon Columbia and Waseda

University for Denon in Japan.

Distributor: TEAC,
115 Whiteman St,
Sth Melbourne Vic.
(03)699-6000.

TWO YEARS AGO when the first production of Sony CDP-101 players arrived in Australia, I faced a dilemma. Without software you can't test the equipment. Sony produced some magnificent demonstration discs for the initial release of their players, but at that time there was not a single test disc in this country.

We reviewed a CDP-101 a few months later with just two demonstration discs, but we still managed to produce some rather exciting test results in the absence of a definitive test disc.

At that time, Sony in Japan and Philips in Eindhoven made some fairly momentous decisions concerning standards for CD players and for test disc material. Sony produced one disc and Philips a set of three.

The Sony Test Disc Type 3 retails for more than \$70 and the Philips disc No. 3 retails for about \$100. These discs, like the seven or eight other commercial test discs now available, contain information whose accuracy and precision is far greater than that provided by the average laboratory with test equipment costing tens of thousands of dollars.

If you own a good CD player then, by purchasing the appropriate CD test discs, you will be able to convert that CD player into a precision piece of laboratory test equipment. You can test not only your CD player but most of your hi-fi equipment, including your tape recorder, amplifier, loudspeakers and even the room in which you do your listening.


This could be, and I venture should be, one of the most exciting pieces of information that you have heard in years. If you are at all serious about your home hi-fi system, then the chances are that you have already spent copious sums of money on ancillary items of test equipment, probably including test tapes and records. These do not begin to compare with the Denon Audio Technical CD test disc.

I have watched with interest or excitement (depending on the quality of the record) as each new conventional micro-groove test record has been released. However, I have been far more interested and concerned with both the availability and content of each new CD test disc, for this medium is not only more demanding, but the availability of appropriate test software is far more important. The reason for this is that no single test disc has contained all the software that I require. Consequently, I have been forced to use six or more laboratory test discs to provide the aggregate information required by a single review (see Yamaha's CD-X1 review).

While my requirements are possibly more demanding than yours, it is equally clear that the average (or above average) hi-fi enthusiast has special requirements in assessing amplifiers, tape recorder, cassette player, speakers and listening room.

In order to perform such testing, it is





clear the test software should be suitable for use by people both with and without supplementary test equipment. The Denon Audio Technical CD test disc provides precisely those facilities *and a whole lot more.*

Features

This particular disc contains almost all the test material that you are likely to require and provides you with the equivalent of more than \$10 000 of test equipment for less than \$20. Need I say more!!

The Denon test disc contains 99 tracks with a wide range of carefully collected software. Track 1 provides a commentary in English on how to use tracks 1 and 2. This immediately tells you whether your loudspeakers are correctly phased. Just that information alone would be worth the \$20 or more that some of my acquaintances have paid servicemen for correctly phasing their speakers, removing 'muddy' sound from their new stereo systems. Tracks 1 and 2 contain in-phase, out-of-phase and channel balancing information, which is particularly well presented.

Tracks 3 to 9 contain a series of orchestral, concerto, chamber music, piano, organ, jazz and rock demonstration material. Tracks 10 and 11 contain announcements in English and Japanese; I was intrigued that this took 108 seconds in English and only 43 seconds in Japanese. Could it be that the Japanese language is twice as efficient as the English language or that we use too many redundant (or long) words? I listened carefully to the Japanese again and discovered that they actually left out some of the text — Shame!!

Tracks 12 to 35 contain test tones at precise frequencies and levels ranging between 0 and -60 dB, as well as 'zero' signals with which the basic background noise of your equipment, or your hearing

acuity, may be evaluated. The zero signal level, which the disc describes as 'infinity zero', is an extremely important test which your amplifier and loudspeakers may not necessarily duplicate. It is also interesting to note that the 1 kHz frequency on the test disc is not actually 1 kHz, but 1001 Hz.

The reason for this unusual choice of frequency, like many of the other test frequencies selected on the disc, is that 1001 Hz is a precise sub-multiple of the 44.1 kHz sampling frequency used by CD players. Consequently, it can be digitally derived without the need for separate analogue test equipment. The digital purity of this signal is then absolute, and unwanted inaccuracies are avoided.

Tracks 36 to 39 each contain a 1 kHz reference signal followed by a logarithmically-swept band of test signals covering the range 20 Hz to 20 kHz. Tracks 40 to 45 provide a wide range of intermodulation tests complying with both the International Electro-Technical Commission (IEC) and the SMPTE standards.

Tracks 46 to 64 contain a variety of sine wave test signals at 0, -20, -40 and -60 VU including test tones of 40, 100, 315, 1001, 3149, 6301, 9999, 15 999, 17 999 and 19 999 Hz. These are particularly suitable for testing your cassette recorder, tape recorder or loudspeakers, particularly if you can use your VU meters on playback.

Track 65 provides a further logarithmic swept signal covering the range 5 Hz to 22.5 kHz. Tracks 66 to 68 provide three test tones at 100 Hz, 1001 Hz and 9999 Hz which glide from -60 dB to 0 dB per second, to evaluate linearity distortion in your CD player, amplifier, loudspeakers, tape recorder or whatever you may choose to connect to the output of your CD player.

At this point I should stress again a word of warning which the literature gen-

tly presents and which I will re-inforce. The test signals that this CD test disc produce cover such a wide dynamic range that the chance of blowing up your amplifier or loudspeakers are particularly good (or bad). It doesn't take much power to destroy a small loudspeaker, particularly when it does not incorporate any internal protection system. Amplifiers are generally a little more difficult to destroy, but they too fail fairly rapidly, particularly if the loudspeaker has already failed. They have to dissipate not only their own power losses, but also the energy that should have been dissipated in the loud speakers.

BE WARNED — CD test discs, as well as being very useful or convenient, are also very much like a loaded gun. If mishandled, or employed in the wrong hands, they can be very dangerous.

Tracks 69 and 70 provide a 401 Hz test signal with the signal phase being rotated through 360° at 12° per second. Tracks 71 to 75 provide excellent square waves and tone bursts at three different frequencies to evaluate your loudspeakers, amplifiers, tape recorder and cassette recorder. These have precise zero crossings to avoid the disturbing effects that many early pieces of test equipment could not properly provide.

Tracks 76 to 78 contain impulse test signals which are extremely useful for testing both the CD player, your loudspeakers and a wide range of high fidelity and professional equipment — but be careful, these signals can wipe out your tweeters if you aren't careful with the volume control settings!

Track 79 is a band of 120 seconds of 'white' noise with a genuine 20 kHz bandwidth, derived digitally with what is described as an 'M'-sequence dither. This signal is absolutely perfect for conducting A-B tests between pairs of loudspeakers, *and just by itself would justify the purchase of this disc.*

— Write for **FREE** Catalogue —

IMPORTERS
MANUFACTURERS
DISTRIBUTORS

Exciting Lighting

729 6337

(SHOWROOM BY
APPOINTMENT)

SPECIALISING IN
DISPLAY, ADVERTISING, ENTERTAINMENT AND SPECIAL EFFECT LIGHTING * ROPE/SNAKE LIGHT - 12V AND 240V * POLYCARBONATE TUBE LIGHT * STAR LIGHT PANELS * INFINITY PANELS * BUBBLE MACHINES * PINSPOTS * SCANNERS * HELICOPTER LIGHTS * MIRROR BALLS AND MOTORS * BUBBLE LAMPS * SPECIAL KEYLIGHTS * VARIOUS TYPES OF LONG LIFE ENERGY SAVING LAMPS AND GLOBES * FLASHING DISPLAY BOXES * ELECTRONIC LIGHTING CONTROLLERS - CHASERS, MUSICOLOUR, MATRIX, STARBURST * BUDLIGHT RIBBON * NEOLIGHT

AGENTS FOR THE NEW "LINE LITE" PLUS MANY OTHER EXCITING LIGHTING PRODUCTS
P.O. Box 634, Dandenong, Vic., 3175

ALSO AGENTS FOR THE POPULAR
RANGE OF **CITRONICS** PRODUCTS

**WE'RE ON THE
MOVE**

**TRUSCOTT'S
ELECTRONICS WORLD
IS MOVING**

As of early July we're
expanding, we will be
offering bigger and better
service at our big new
premises located at:

**30 LACEY STREET CROYDON
VIC.
Phone (03) 723 3860**


Matsunaga

Automatic Voltage Regulators and Slide Regulators

Stabilised AC power supply

Precision manufactured, accurate and efficient. Matsunaga automatic voltage regulators offer rapid voltage correction with zero waveform distortion. The units are of robust but compact and lightweight construction and are ideal for applications where constant voltage is important.

Where specific Line Interference problems occur, Electromark will supplement the voltage regulator with filters selected for the particular problem.



Models — SVC, 350 N,
1000 N

Input Voltage: 180V to 260V
AC.

Output Voltage: 110V to 240V
±3% (simultaneous output) Single
Phase 50-60 Hz.

Prices: 350VA \$141.00, 1000VA
\$252.00 (plus Sales Tax if
applicable).

Quantity discounts available.

**ELECTROMARK PTY. LTD.,
43 Anderson Road,
(P.O. Box 184)
Mortdale. NSW 2223**

SOUND REVIEW

Tracks 80 to 89 are most probably the 'pièce de résistance' of the disc. They contain a series of 1/3-octave bands of signal between 25 Hz and 16 kHz on the left channel and matching octave bands of signal centred on 31.5 Hz through to 16 kHz on the right channel (see Figure 1).

These signals are arranged so that while the left channel steps through three contiguous 1/3-octave bands, the right channel provides the corresponding octave band signal. You are thus able to generate at will the 1/3-octave band or single octave bands for listening to your loudspeakers, for testing your tape recorder, for assessing your room characteristics, and if your loudspeakers are good enough, for assessing your own hearing acuity or that of your relatives and friends.

This facility is undoubtedly worth many times the cost of the disc. I will be using it in future loudspeaker subjective assessments as it will save me the trouble of bringing home the 50 kg or so of test equipment that I have had to carry in the past!

Track 90 contains a band of 'pink' noise which is also invaluable for loudspeaker testing. Track 91 provides a superb 3150 Hz test sine wave for 'wow and flutter' measurements (but this requires access to a wow and flutter meter).

Track 92 contains a test signal which is FFFF/0000 at 22.05 kHz for testing CD player out-of-band ('anti-aliasing') filters and consequently is inaudible to mere mortals.

Tracks 93 to 96 contain a series of orchestral and piano music at normal stereo level, -20 VU, -40 VU and -60 VU. This is extremely useful for evaluating both your CD player and the loudness contours and noise generation characteristics of your amplifier/speaker system. If nothing else, it will tell you how good or bad the background listening levels are in your room. If you live in a noisy location you may be tempted to move as a result!

Tracks 97 to 99 contain three classical samples of music, each repeated four times for A-B testing of amplifiers and loudspeakers, which once again prove to be an excellent set of test material.

Conclusions

If by now you are not 'chaffing at the bit' to buy this disc, then it's clear that you are not seriously involved with hi-fi. I classify this particular CD test disc as one of the best bargains of 1984. I believe that almost every recording studio, radio station, television station and serious hi-fi enthusiast will want to buy this particular disc because it provides so much invaluable testing information.

The information has been produced with a degree of precision which has never before been matched by any other means for so little cost. Having checked the main parameters, I can now attest to its precision, accuracy and usefulness. (I kept the disc.)●

A special opportunity for readers of

Electronics Today

By special arrangement with Teac Australia Pty Ltd, the local representatives for Denon, we are able to offer readers the outstanding new Denon Technical CD Test Disc for only

\$19.95
Plus \$2.50 postage and handling

This important new tool for evaluating CD players and testing audio systems comes from Denon, the Japanese company that has played a leading role in the development of digital audio recording. Here's what Louis Challis, Australia's foremost audio and electronic equipment reviewer, said after testing this exciting new disc in his NATA-registered laboratory:




"I classify this particular CD disc as one of the best bargains of 1984. I believe that almost every recording studio, radio station, television station and serious high fidelity enthusiast will want to buy this particular disc, because it provides just SO MUCH INVALUABLE (testing) INFORMATION."

(Electronics Today, August 1984)

This is an excellent offer for such a professional, state of the art disc! Look at what you get for just \$19.95:

- Source material for listening tests: excerpts from various types of music, specially chosen to allow accurate evaluation by ear.
- Low and high frequency sweep signals at different levels.
- Square wave, impulse, noise and burst signals.
- Linearity test signals.



- Test signals for basic performance checks.
- CD player test signals: reference 0 dB and -60 dB levels, a sweep signal from 20 Hz to 20 kHz, two-tone signal for intermodulation tests, etc.
- Spot frequency test signals for overall system testing.

FEDERAL MARKETING MAIL ORDER FORM

Allow four weeks for delivery Send completed coupon to: Federal Marketing, PO Box 227 Waterloo NSW 2017.

I don't want to miss the opportunity to obtain a copy of this important audio testing tool. Please rush me Denon Technical CD Test Discs at the price of \$19.95 each.

plus \$2.50 for handling and airmail postage anywhere in Australia

Total price of discs \$
Plus \$2.50 postage & handling per disc \$

TOTAL \$

Name

Address

Postcode

Signature

Tick box to indicate payment:

American Express ☐ Bankcard ☐ Cheque* ☐

* Please make cheques payable to the Federal Publishing Company Pty Ltd

Credit Card No:

.....

Card Expiry Date:

Unsigned orders cannot be accepted



SERIES 5000

PRICES SLASHED

As designed by ETI

INDIVIDUAL COMPONENTS TO MAKE UP A SUPERB HI-FI SYSTEM. BY DIRECTLY IMPORTING AND A MORE TECHNICALLY ORIENTED ORGANISATION BRING THESE PRODUCTS TO YOU AT LOWER PRICES THAN OUR COMPETITORS.

EXTRA FEATURES OF OUR TIPS POWER AMPLIFIER

KIT PRICE \$319 P&P \$12.00

- 1% Metal Film Resistors are used where possible • Prewound Coils are supplied
- Aluminium case as per the original article • All components are top quality • Over 400 Kits now sold • We have built this unit and so know what needs to go into every kit • SUPER FINISH Front panel supplied with every kit at no extra cost to you.
- We are so confident of this kit that we can now offer it assembled and tested so that people who do not have the time can appreciate the sound that this amplifier puts out. This is done on a per order basis delivery approx. four weeks after placement.

PREAMPLIFIER

KIT PRICE \$289 P&P \$12.00

- 1% Metal Film Resistors are supplied • 14 metres of Low Capacitance Shielded are supplied (a bit extra in case of mistakes) • English "Lorlin" Switches are supplied no substitutes as others supply • We have built and tested this unit and so

Only \$449

Only \$449

know what needs to go into every kit • Specially imported black anodised aluminium knobs • Again as with the power amp we are offering this kit A & T at a price which we do not believe there is a commercial unit available that sounds as good. Same delivery as the PA.

PREAMPLIFIER SPECIFICATIONS

Kit Price \$289, P&P \$12.00

Frequency response: High-level input: 15Hz-130 kHz, +0, -1 dB Low-level input — conforms to RIAA equalisation, ± 0.2 dB
1kHz < 0.003% on all inputs (limit of resolution on measuring equipment due to noise limitation).
Distortion: High-level input, master full, with respect to 300 mV input signal at full output (1.2V): >92 dB flat >100 dB A-weighted.
S/N noise: MM input, master full, with respect to full output (1.2V) at 5 mV input, 50 ohm source resistance connected: >86 dB flat >92 dB A-weighted.
MC input, master full, with respect to full output (1.2V) and 200 μ V input signal: >71 dB flat >75 dB A-weighted.

On Special at \$259
Normally \$289

*All parts available separately for both kits.

POWER AMPLIFIER Kit Price \$319, P&P \$12.00

SPECIFICATIONS


150W RMS into 40hms
Power output: 100W RMS into 8 ohms (± 55 V supply).
Frequency response: 8 Hz to 20 kHz, +0 -0.4 dB 2.8-Hz to 65 kHz, +0 -3 dB. NOTE: These figures are determined solely by passive filters.
Input sensitivity: 1V RMS for 100W output.
Hum: 100dB below full output (flat).
Noise: -116 dB below full output (flat, 20 kHz bandwidth).
2nd harmonic distortion: -0.001% at 1 kHz (0.0007% on prototypes) at 100 W output using a ± 56 V supply rated at 4 A continuous. -0.003% at 10 kHz and 100 W.
3rd harmonic distortion: -0.0003% for all frequencies less than 10 kHz and all powers below clipping.
Total harmonic distortion: Determined by 2nd harmonic distortion (see above).
Intermodulation distortion: -0.003% at 100 W. (50 Hz and 7 kHz mixed 4:1).
Stability: Unconditional

Please note that the "Superb Quality" Heatsink for the power amp was designed and developed by Rod Irving Electronics and is being supplied to other kit suppliers. This product cost \$1,200 to develop so that your amplifier kit would have a professional finish as well as sound.



On Special at \$299
Normally \$319

MX-1200 MICROPHONE/AUDIO MIXER



MX 1200 \$625 this month only

This unit features: 12 microphone line inputs with pan, bass, treble, effect and fold back controls for each channel • LED peak indicators for each channel • 2 turntable inputs with cross-fade and individual output controls • master equaliser for bass, midrange and treble • variable headphone output etc. etc. • complete with carrying case


SPECIFICATIONS:

INPUTS
Level/Impedance Mic 46 db-1K
Line 22 db-15k x 12
Phono 52 db/50K STEREO x 2 (2mv) at 1KHz
Effect Return (Aux) 20 db/50K x 1
OUTPUTS
Level/Impedance L & R 0 db-2K
Effect Send 0 db/2K F.B. Out 0 db-2K
Head phone Stereo +10 db 600 (100 1K)
EQUALISATION
Channel
Bass +15db
Treble +15db
Master
Bass +12db
Treble +10db
Middle +12db

FADER & CONTROLLERS

12 channel fader: Slide, 60mm, LOG 25%
2 Master fader: Slide, 60mm, LOG 15%
12 F.B. Volume: 300 LIN
1 F.B. Master level: 300 LIN
12 Effect Send: 300 LIN
1 Effect Return: 300 LOG 15%
2 Phono: 300 LOG 15%
1 Head Phone: 300 LOG 15%
S/N: 58DB
FREQUENCY RESPONSE 20-20 kHz
TOTAL HARMONIC DISTORTION Less than 0.1%
METER 2 illuminated VU Meters 0db = 0.775V
PEAK INDICATOR 12 LED Peak Indicators
VOLTAGE 240 VAC 50Hz
POWER CONSUMPTION 7.2 watts
DIMENSIONS 620 (W) x 386 (D) x 108 (H) mm (supplied complete with carrying case)

THIRD OCTAVE GRAPHIC EQUALIZER



SPECIFICATIONS E.T.I. Dec. 1982

Bands: 28 Bands from 31.5 Hz to 16 kHz
Noise: <0.008 mV, sliders at 0, gain at 0 (-102 dB).
20 kHz bandwidth
Distortion: 0.007% at 300 mV signal, sliders at 0, gain at 0 max. 0.01%, sliders at minimum.
Frequency Response: 12 Hz-105 kHz, +0, -1 dB, all controls flat.
Boost & Cut: 14 dB

\$19500 1 Unit
\$37900 2 Units

SERIES 4000 SPEAKERS.

- 8 Speakers only \$155
- 8 speakers with crossovers \$499
- Speaker boxes (assembled with grill and speaker cutout) ... \$299
- Crossover kits \$199
- Complete kit of parts (speakers, crossovers, screws, inner-band boxes) \$799
- Assembled, tested, ready to be hooked up to your system ... \$849



WE BELIEVE THAT WE ARE NOW THE ONLY ONES TO SUPPLY COMPLETE SPEAKER KITS ASSEMBLED AND TESTED FOR THOSE WHO HAVEN'T GOT TIME \$849 EX STOCK.

PLEASE WRITE FOR CONSTRUCTION NOTES, THESE COMPLIMENT THE SERIES 5000 AMP RANGE AND ADD THE FINAL TOUCH.

Errors and Omissions Excepted

ROD IRVING ELECTRONICS

425 High St., Northcote 3070 (03) 489 8866 (03) 489 8131
48-50 A Beckett St., Melbourne (03) 347 9251

Mail Order and Correspondence
P.O. Box 235 Northcote 3070

To Order By Phone

Mail Order Hotline (03) 481 1436



POSTAGE RATES

\$1-\$9.99	\$2.00	\$10-24.99	\$3.50
\$25-49.99	\$4.50	\$50-99.99	\$6.00
\$100-199	\$8.00	\$200-499	\$10.00
\$500+	\$12.00		

(All above charges are for surface mail and some heavy items will vary from these rates.)

Cert. post for orders over \$100 included "free".
Reg. post for orders over \$200 included "free".
Account orders from schools, govt. depts., public co's., gratefully accepted. Min order amount \$20.00 (or a min. \$5.00 accounting charge will apply.) Comet Road Freight, Airmail etc. are extra.



Low cost handheld DMM

Rod Irving Electronics has just released details of a new addition to their extensive range of multimeters.

It's the YFE YF1100, a 3½-digit machine priced to undersell the opposition at \$59.95. It comes with facilities for transistor and diode testing. The YF1100 has a large, easy-to-read liquid crystal display and clearly laid out front panel.

Function and range control is via a set of side buttons. There are six ranges of current and resistance, and five of volts. It will accept currents from two microamps through to 10 Amps.

There are separate jacks for the ranges up to two amps and the 10 amp range. Both are fuse protected to save the meter in the event of misuse. It is designed to be able to tolerate 500 V across the current jacks.

The YF1100 will measure up to 1000 Vdc and 750 Vac and up to 20M of resistance.


It will also measure the Hfe of a transistor. Separate jacks are provided for pnp and npn transistors. To increase the flexibility

of the jacks there are two emitter terminals on each jack commoned together, so that any transistor can be fitted, irrespective of its orientation.

The YF1100 also has diode testing facilities and the ability to test resistance both with and without turning on semi-conductor junctions.

For more information contact **Rod Irving Electronics, 425 High St, Northcote Vic 3070. (03) 489-8866.**

The YF1100, a 3½-digit multimeter from Rod Irving.



Quick tip cleaning

Delicate soldering requires accurately cleaned soldering-iron tips and this new cleaner Clean-o-Point solves and eliminates many of the problems that crop up using old fashioned, home made devices.


'Clean-o-Point' has been designed for on-bench use and contains a motorised pair of sponge rollers. The soldering-

iron tip is placed between the rollers and tin alloy, liquid and residue are wiped off and fall within a receptacle designed exclusively to retain used solder.

Solder spray which normally occurs when wiping the tip is eliminated and since the heating element does not come into contact with the damp sponge rollers it retains an even temperature. The cleaning action is thorough, quick and avoids any necessity for visually checking the tip.

'Clean-o-Point' helps to achieve an increase in soldering quality and enables recycling of solder normally lost in the cleaning process.

For further information contact **C & K Electronics, 15 Cowper Street, Parramatta NSW 2150. (02)636-0799.**



Smart data logger

Data Electronics has just announced the release of a new data logger. The Dataporte is a high performance data acquisition, data logging and controlling unit, suitable for a wide variety of applications.

Standard features of the Dataporte include analogue, digital, event and counter inputs, data averaging, data storage, analogue and digital outputs, set-point control and alarm outputs,

real time clock, RS232C/RS422 ASCII communications, and simple programming.

The Dataporte is programmed from a computer or terminal, and may be continually supervised, or operated in a stand-alone mode. The 24 analogue inputs accept voltage, current, resistive and frequency signals, and are self-calibrating, and autoranging over three decades.

The eight digital/counter inputs are debounced, and allow state and even monitoring, and counting. Scan rates are programmed as a function of time or events detected on digital or counter channels.

The eight digital outputs may be manged directly by the user, or programmed as a function of selected analog inputs to provide direct control and alarm functions, or analog front-ending to PLC's.

Dataporte is designed and manufactured in Australia by Data Electronics (Aust.) Pty Ltd. More information is available by contacting the manufacturer at **4 Pilgrim Court, Ringwood Vic 3134. (03)874-7066.**

Functionally, the CRL 2.35A features a new, clear, 34 dB mirror scaled meter which displays current sound level and maximum held value. This meets the Australian Standard at all three response speeds permitting the use of 'Max Hold' to full specification.

The price of a typical system, with plug-in units for multiple functions, is usually well under \$2000. For further information contact **M. B. & K. J. Davidson Pty Ltd, 66 Atherton Road, Oakleigh Vic. 3166. (03)568-1933.**

New sound lever meter

Cirrus Research has announced the CRL 2.35A Measuring System. At the input socket, the whole range of L3M microphone pre-amplifiers or input units is available together with eight different microphone capsules. These give a total measurement range from 10 to 160 dB at all grades of the International Standard IEC 651 up to and including Precision Grade 1, totally covering Australian Standard 1259 parts two and three.

Nine plug-in units are cur-

rently available for the DP15 function interface. These have all the parameters expected of a current technology sound level meter, including not only octave filter (to AS Z41), L_{eq} and D_{ose} , but also vibration, speed measurement, digital readout, ac power drive and many others.

The main body of the CRL 2.35 A has an input sensitivity of 0.5 μ C to 7 V over a bandwidth of 8 Hz to 32 kHz, while the main amplifier covers the whole range from infrasound to ultrasound.


Power to the people!

Thousands of Australian homes are in such remote areas that they will never be connected to regional electricity networks. But thanks to a Sydney company, even the most isolated families can now obtain an endless supply of 'free' electricity . . . from the sun.

"If your home is not connected to mains electricity, you either generate your own, or do without," said Amtex Electronics' manager, Jim Kuswadi.

"You can convert the Sun's energy to electricity instantly, with no noise, pollution or fuel costs, and minimum maintenance."

Amtex offers a choice of five systems: • The solar lighting kit provides four hours of light each night from three 13 W fluorescent lamps. In sunless periods, a fully-charged battery will keep the system operating for five days or more. • The home



power system (dc); On a typical day, this system could provide power for four 20 W fluorescent lights for three hours, a 50 W portable colour TV for three hours, a transistor radio for six

hours, and a small water pump for half an hour. • 240 V ac systems are available in small, medium and large sizes, to meet customers' varying requirements. These units supply power

for most 240 V domestic appliances.

For further information, contact: **Jim Kuswadi, Amtex Electronics, 36 Lisbon St, Fairfield NSW 2165. (02)728-212 1.**

MASTER HEAT GUNS



MASTER HEAT GUN HB10

Is the Heat Gun designed for the electronics industry. It is our lightest tool weighing less than 1kg and also our smallest. Ideally suited to bench and field use it is supplied with a heat shrink nozzle, bench stand and 340C element. Optional elements are available from stock.

HB10	Heat gun	\$90.80
HB12	260C Element	\$18.38
HB14	426C Element	\$18.38
HB17	Carrying Case	\$27.58

Tool & accessory prices are plus 7.5% Sales Tax and \$6.00 freight within Australia.



MASTER HEAT GUN 2000

The 2000 series gun is the top of the range of general purpose heat guns. It offers a cool touch Heat Shield and plug in elements for versatility. This gun offers thermostatic protection at air flows of 2700fpm delivering 27cfm.

HB56	Heat gun	\$179.00
HB63	960W Element	\$ 18.50
HB64	480W Element	\$ 18.50

Shrink attachments and solder point tips are available, please contact us for full details.

Prices valid during month of publication and are subject to change after that time without notice. E & OE.

STEWART ELECTRONIC Components P/L

44 Stafford Street, Huntingdale

P.O. Box 281 Oakleigh 3166

Phone (03) 543 3733 Telex AA36908

DISTRIBUTORS WANTED!


We are looking for capable, aggressive distributors to promote our **KYOCERA** Solar Panels. These panels are manufactured in Japan to the same high quality standards you have come to expect of Japanese electronic products.

To help distributors to promote this product, we are offering a special price until August 31, 1984 for orders of 12 panels or more

KYOCERA SOLAR PANEL PSA 100H-361

Power output ... 40w ($\pm 5\%$)
Optimum voltage ... 16.2V
Open circuit voltage ... 19.6V
Optimum current ... 2.47A
Short circuit current ... 2.7A

DIMENSION OF PSA100H-361



\$359.⁰⁰ Each
minimum 12 pcs
(Freight additional)
Valid to 31 Aug 84

ORDER NOW!

AMTEX
ELECTRONICS

A DIVISION OF
TELCON AUSTRALIA PTY. LIMITED
(Incorporated in New South Wales)

36 LISBON STREET
FAIRFIELD, NSW 2165
AUSTRALIA
TELEPHONE (02) 728 2121
727 5444
TELEX AA27922

To: **AMTEX ELECTRONICS**
36 Lisbon St., Fairfield. NSW 2165

Please send me **KYOCERA** Panels @ \$359

I enclose cheque/money order for \$

Name:

Address:

..... Postcode.....

Please send by Rail.....

Road transport (mark one)

Nearest rail station.....


Mail Order... Promark Distributors... Mail Order

Your First Choice for High Technology Electronic Components
(Founded 1976)

"D" Range Connectors

Gold plated solder GERMAN MADE

plug



socket

9 way ADS 9L	\$1.95	9 way ADF 9L	\$2.40
25 way ADS 25L	\$4.30	25 way ADF25L	\$4.80

PIN HEADER

A8D	\$1.20
A14P	\$1.50
A16P	\$1.70





GOLD PLATED WITH CAP

A24P	\$3.10
A40P	\$5.05

NEW! \wedge NEW! \wedge NEW!

Siemens/TEC — Floppy Disk Drives

These are professional grade 5 1/4" half-height units featuring brushless steelbelt drive 3/6 mSec access time and industry standard formats, with maintenance and guarantee backed by SIEMENS, ask for data.



no discount on drives


Part No.	Sides	Density	Tracks	Cap.	Price
FB.501	Single	Single	48tpi	250K	\$219.50
FB.503	Double	Single	48tpi	500K	\$305.00
FB.504	Double	Double	96tpi	1M	\$335.50

!! CHECK THESE PRICES !!

SIEMENS MINIATURE PCB RELAYS 1 AND 2 CHANGE OVER

Contacts 1 Amp, max voltage 120AC, plugs in IC socket.

1 c/o 6V type 6V103	\$2.50
1 c/o 12V type 12V103	\$2.50
1 c/o 24V type 24V103	\$2.50
2 c/o 6V type 6V104	\$3.75
2 c/o 12V type 12V104	\$3.75
2 c/o 24V type 24V104	\$3.75



FINEST QUALITY GERMAN IC SOCKETS GOLD PLATED

MACHINED CONTACT

PCB



WIRE WRAP

AR6	\$0.68	AR6W	\$0.90
AR14	\$1.10	AR14W	\$1.85
AR16	\$1.20	AR16W	\$2.25
AR18	\$1.30	AR18W	\$2.38
AR20	\$1.62	AR20W	\$2.55
AR22	\$1.82	AR22W	\$2.75
AR24	\$2.05	AR24W	\$3.05
AR28	\$2.05	AR28W	\$3.25
AR28	\$2.12	AR40W	\$4.05
AR40	\$3.12		



BARGAIN PRICED BRIDGES

35 Amp 400 PIV

Type 3504

1 Amp 400 PIV


Type WO 4



\$4.75 ea.

\$0.60 ea.

SUBMIN R. F. CHOKES



ALL
VALUES
50c

2.2 Microhenry	100 Microhenry
3.3 Microhenry	220 Microhenry
4.7 Microhenry	330 Microhenry
10 Microhenry	470 Microhenry
22 Microhenry	1 Millihenry
33 Microhenry	3.3 Millihenry
47 Microhenry	4.7 Millihenry

! SPECIAL !
Voltage Converter

TSC7660
for modems, etc.
\$3.80

MAKE YOUR OWN VOLTMETER

TELEDYNE I.C.'S.

3 1/2 digit LCD DVM IC TSC7106	\$16.50	Superlow power 3 1/2 digit LCD DVM TSC7126	\$19.50
3 1/2 digit LED DVM IC TSC7107	\$16.50	Dual power MOSFET driver TSC450	\$ 4.95
12 bit CMOS A/D for uP TSC7109	\$19.50	15 bit CMOS A/D TSC800	\$35.50
4 1/2 digit CMOS DVM IC TSC7135	\$22.50	Ultra linear VCO TSC9400	\$ 6.45
4 digit LCD driver TSC7211	\$10.50	Stable VRef 1.22V TSC9491	\$ 2.45
4 digit LED driver TSC700	\$ 8.65	Super stable VRef 5V TSC9495	\$ 7.70

ALL COMPONENTS OFFERED ARE BRAND NEW, PREMIUM GRADE DEVICES. **SALES TAX IS INCLUDED**
FREIGHT CHARGE IS \$3.50 PER ORDER. IF YOU REQUIRE DATA AND APPLICATIONS ON ANY ITEM SEND
A STAMPED SELF-ADDRESSED ENVELOPE.

D.I.S.C.O.U.N.T.S. . . . TOTAL ORDER VALUE . . . up to \$50 NETT; \$50 to \$100, less 10%; \$100 and over, less 15%.

P.O. BOX 381 CROWS NEST N.S.W. 2065. PHONE (02) 439 6571


BANKCARD WELCOME

* **PRICES VALID TO 1-11-84** *

(No discount on B/Card Sales)

S100 PRODUCTS

32K S-100 EPROM CARD PRICE CUT!



\$109.00

USES 2716's

Blank PC Board — \$69

ASSEMBLED & TESTED
ADD \$49.00


KIT FEATURES

- 1 Uses +5V only 2716 (2Kx8) EPROM's
- 2 Allows up to 32K of software on line
- 3 IEEE S-100 Compatible
- 4 Addressable as two independent 16K blocks
- 5 Cromemco extended or Northstar bank select
- 6 On board wait state circuitry if needed
- 7 Any or all EPROM locations can be disabled
- 8 Double sided PC board, solder masked, silk-screened
- 9 Gold plated contact fingers
- 10 Unselected EPROM's automatically powered down for low power
- 11 Fully buffered and buffered
- 12 Easy and quick to assemble

256K S-100 SOLID STATE DISK SIMULATOR! WE CALL THIS BOARD THE "LIGHT-SPEED-100" BECAUSE IT OFFERS AN ASTOUNDING INCREASE IN YOUR COMPUTER'S PERFORMANCE WHEN COMPARED TO A MECHANICAL FLOPPY DISK DRIVE.

FEATURES:

- 256K on board, using + 5V 64K DRAMS.
- Uses new Intel 8203-1 LSI Memory Controller.
- Requires only 4 Dip Switch Selectable I/O Ports.
- Runs on 8080 or Z80 S100 machines.
- Up to 8 LS-100 boards can be run together for 2 Meg. of On Line Solid State Disk Storage.
- Provisions for Battery back-up.
- Software to mate the LS-100 to your CP/M* 2.2 DOS is supplied.
- The LS-100 provides an increase in speed of up to 7 to 10 times on Disk Intensive Software.
- Compare our price! You could pay up to 3 times as much for similar boards.



BLANK PCB
(WITH CP/M* 2.2
PATCHES ON DISK)
\$99.95

\$699.00

#LS-100 (FULL 256K KIT)


ALLOW 4-6 WEEKS DELIVERY

THE NEW ZRT-80 CRT TERMINAL BOARD!

A LOW COST Z-80 BASED SINGLE BOARD THAT ONLY NEEDS AN ASCII KEYBOARD, POWER SUPPLY, AND VIDEO MONITOR TO MAKE A COMPLETE CRT TERMINAL. USE AS A COMPUTER CONSOLE, OR WITH A MODEM FOR USE WITH ANY OF THE PHONE-LINE COMPUTER SERVICES.

FEATURES:

- Uses a Z80A and 6845 CRT Controller for powerful video capabilities.
- RS232 at 16 BAUD Rates from 75 to 19,200.
- 24 x 80 standard format (60 Hz).
- Optional formats from 24 x 80 (50 Hz) to 64 lines x 96 characters (60 Hz).
- Higher density formats require up to 3 additional 2K x 8 6116 RAMS.
- Uses N.S. INS 8250 BAUD Rate Gen. and USART combo IC.
- 3 Terminal Emulation Modes which are Dip Switch selectable. These include the LSI-ADM3A, the Heath H-19, and the Beehive.
- Composite or Split Video.
- Any polarity of video or sync.
- Inverse Video Capability.
- Small Size: 6.5 x 9 inches.



BLANK PCB WITH 2716
CHAR. ROM, 2732 MON. ROM
\$99.00

SOURCE DISKETTE - ADD \$20

SET OF 2 CRYSTALS - ADD \$12

ZRT-80

WITH 8 IN.
SOURCE DISK!

\$219.00

(COMPLETE KIT,
2K VIDEO RAM)

ROD IRVING ELECTRONICS

425 High St., Northcote 3070 (03) 489 8866 (03) 489 8131
48-50 A Beckett St., Melbourne (03) 347 9251

Mail Order and Correspondence
P.O. Box 235 Northcote 3070

To Order By Phone

Mail Order Hotline (03) 481 1436



64K S100 STATIC RAM

\$499.00
KIT
NEW!

LOW POWER!

RAM OR EPROM!


BLANK PC BOARD
WITH DOCUMENTATION
\$119.00

SUPPORT ICs + CAPS
\$29.00

FULL SOCKET SET
\$19.00

FULLY SUPPORTS THE
NEW IEEE 696 S100
STANDARD
(AS PROPOSED)
FOR 56K KIT \$419

ASSEMBLED AND
TESTED ADD \$50



FEATURES:

- Uses new 2K x 8 (TMM 2016 or HM 6116) RAMs.
- Fully supports IEEE 696 24 BIT Extended Addressing.
- 64K draws only approximately 500 MA.
- 200 NS RAMs are standard. (TOSHIBA makes TMM 2016s as fast as 100 NS. FOR YOUR HIGH SPEED APPLICATIONS.)
- SUPPORTS PHANTOM (BOTH LOWER 32K AND ENTIRE BOARD).
- 2716 EPROMs may be installed in any of top 48K.
- Any of the top 8K (E000 H AND ABOVE) may be disabled to provide windows to eliminate any possible conflicts with your system monitor, disk controller, etc.
- Perfect for small systems since BOTH RAM and EPROM may co-exist on the same board.
- BOARD may be partially populated as 56K.

64K SS-50 STATIC RAM

\$359.00
(48K KIT)

NEW!

LOW POWER!

RAM OR EPROM!

BLANK PC BOARD
WITH
DOCUMENTATION
\$119.00


SUPPORT ICs + CAPS

FULL SOCKET SET

56K Kit \$419

64K Kit \$499

ASSEMBLED AND
TESTED ADD \$50



FEATURES:

- Uses new 2K x 8 MK58725P RAMS
- Fully supports Extended Addressing.
- 64K draws only approximately 500 MA.
- 200 NS RAMs are standard. (TOSHIBA makes TMM 2016s as fast as 100 NS. FOR YOUR HIGH SPEED APPLICATIONS.)
- Board is configured as 3-16K blocks and 8-2K blocks (within any 64K block) for maximum flexibility.
- 2716 EPROMs may be installed anywhere on Board.
- Top 16K may be disabled in 2K blocks to avoid any I/O conflicts.
- One Board supports both RAM and EPROM.
- RAM supports 2MHZ operation at no extra charge!
- Board may be partially populated in 16K increments.


32K S100 EPROM/STATIC RAM

NEW!

FOUR FUNCTION BOARD!

NEW!

EPROM II
FULL
EPROM KIT
\$129
A&T EPROM
ADD: \$35



BLANK
PC BOARD
WITH DATA
\$69.00

SUPPORT
ICs
PLUS CAPS
\$29.00

FULL
SOCKET SET
\$25.00

We took our very popular 32K S100 EPROM Card and added additional logic to create a more versatile EPROM/RAM Board.

FEATURES:

- This one board can be used in any one of four ways:
A. As a 32K 2716 EPROM Board
B. As a 32K 2732 EPROM Board (Using Every Other Socket)
C. As a mixed 32K 2716 EPROM/2K x 8 RAM Board
D. As a 32K Static RAM Board
- Uses New 2K x 8 (TMM2016 or HM6116) RAM's
- Fully Supports IEEE 696 Buss Standard (As Proposed)
- Supports 24 Bit Extended Addressing
- 200 NS (FAST!) RAM's are standard on the RAM Kit
- Supports both Cromemco and North Star Bank Select
- Supports Phantom
- On Board wait State Generator
- Every 2K Block may be disabled
- Addressed as two separate 16K Blocks on any 64K Boundary
- Perfect for MP/M* Systems
- RAM Kit is very low power (300 MA typical)

32K STATIC RAM KIT — \$199.00

For RAM Kit A&T - Add \$40

POSTAGE RATES


\$1-\$9.99	\$2.00	\$10-24.99	\$3.50
\$25-49.99	\$4.50	\$50-99.99	\$6.00
\$100-199	\$8.00	\$200-499	\$10.00
\$500+	\$12.00		

(All above charges are for surface mail and some heavy items will vary from these rates.)

Cert. post for orders over \$100 included "free".
Reg. post for orders over \$200 included "free".
Account orders from schools, govt. depts., public co's., gratefully accepted. Min order amount \$20.00 (or a min. \$5.00 accounting charge will apply). Comet Road Freight, Airmail etc. are extra.



We have the Relay to fit your Printed Circuit Board



• Reed Relays • Flat Form Relays • Sealed Relays • Solid State Relays
FOR YOUR COMPREHENSIVE CATALOGUE CONTACT:

EMAIL
Relays

BELLCO
Controls

Melbourne 15 Hume Street, Huntingdale, Victoria. 3166. Tel: (03) 544 8244. Telex: AA30895.
Sydney Valetta Building, Campbell Street, Artarmon, N.S.W. 2064. Tel: (02) 439 3311. Telex: AA21117.
Adelaide 34 South Terrace, Adelaide, S.A. 5000. Tel: (08) 211 7855. Telex: AA89186.
Brisbane 105 Colchester Street, South Brisbane, Qld. 4101. Tel: (07) 44 2962. Telex: AA41330.
Perth 46 Collingwood Street, Osborne Park, W.A. 6017. Tel: (09) 446 9888. Telex: AA92085.
Melbourne 9 Harker Street, Burwood, Victoria. 3125. Tel: (03) 288 8044. Telex: AA31261.
Sydney 275 Stanmore Road, Petersham, N.S.W. 2049. Tel: (02) 560 7077. Telex: AA72575.
Adelaide 34 South Terrace, Adelaide, S.A. 5000. Tel: (08) 211 7855. Telex: AA89186.
Brisbane 105 Colchester Street, South Brisbane, Qld. 4101. Tel: (07) 44 7261. Telex: AA41330.

WANTED
in good condition:
ELECTRONIC PARTS
and
COMPUTERS
also
TEST EQUIPMENT
CASH REWARD!
Phone 569-9770

SEMICONDUCTOR PRICES SLASHED

TRANSISTORS
BC107, 108, 109 — 0.30
BC547, 548, 549 — 0.15
BC177, 178, 179 — 0.30
BC557, 558, 559 — 0.15
BC182, 183, 186 — 0.35
BC637, 638, 639 — 0.33
BD139, BD140 — 0.50
BD681, BD682 — 0.75
2N3055 metal can — 0.80
Plus lots more!

LARGE RANGE OF AMERICAN 2N series, also PHILIPS

LARGE RANGE OF Top RCA DEVICES, incl SCR's and TRIACS, ex stock.

LARGE RANGE OF JAPANESE TRANSISTORS and AUDIO IC's ex stock.

Where else can you buy Semis on Saturday arvo?

DIODES, RECTIFIERS
0A90, 0A91, 0A95 — 0.20
1N914, 1N4148 — 0.05
1N4001 - 1N4004 — 0.10
1N5401 - 1N5404 — 0.30
4001V 6Amp — 0.75
Large range up to 50Amps

SAVE up to 50%

BRIDGE RECTIFIERS
1.5A 400 PIV — 0.40
2A 400 PIV — 0.70
6A 400 PIV — 1.50
10A 400 PIV — 2.00
25A 400 PIV — 3.95
25A 1000 PIV — 5.50
35A 400 PIV — 4.50
Special types also avail.

INTEGRATED CIRCUITS
7400 Series, from 0.40
74LS from — 0.40
4000 Series, from 0.50
Large range of LINEAR Large range of MICRO & SPECIAL PURPOSE avail.

VOLTAGE REGULATORS
Large range from 40mA up to 5 Amps all volt

ZENER DIODES
400mW Series — 0.15
1 Watt Series — 0.25
5 Watt Series — 0.60
LED's
RED 3mm and 5mm — 0.10
GRN, YELL and AMBER, 3mm and 5mm — 0.20
Flashing RED — 0.35

FREE SAMPLES
ONE BAG PER CUSTOMER!
ADVERTISING PROMOTION OFFER!
We want to show-off the quality of our LED's, IC's, Diodes, Transistors, etc, so we'll send you a selection of 10 various types, worth upto \$3.
This FREE OFFER is for mail-order buyers only and ends on September 1st.

FILL OUT THIS FORM
Please send me one free Sample Bag. I am enclosing a 30¢ stamp to cover postage.
NAME _____
ADDRESS _____
POSTCODE _____

Computer Case
• FOR EXISTING SYSTEMS AREN'T YOU TIRED OF LOOKING AT THE "GUTS" OF YOUR HOME-MADE CPU?
• FOR NEW SYSTEMS DO YOU WANT TO BUILD YOUR COMPUTER, BUT CAN'T HACK-UP THE ALUMINUM?
• FOR OEM'S, GOVT DEPTS, ETC CAN'T WAIT FOR CUSTOM-BUILT ONE-OFF PROTOTYPES? NEED EX-STOCK DELIVERY?
• THEN YOU NEED TO BUY OUR HIGH QUALITY COMPUTER CASE
SIZE 430x180x510MM DEEP. Various options are available for most combinations of 5" and 8" floppy drives and 5" hard-disks. Call and let us know what you want. We'll fix you up.
EACH \$199
New DISK DRIVE CASES from \$75
PACK/POST \$2 PLUS 5% OF ORDER

2Kgm handy SURPRISE KIT
WORTH UP TO \$60
Transformers, Electros, Poly & ceramic caps, Resistors, Switches, Semiconductors, Pots, INTER-STATE POST- ADD \$3.00

ECONOMY FM MIC 88-108Mhz
TRANSMITS TO 50W RANGE, CONDENSOR MIKE, Operates on two 1.5V pencil batt
\$10

VHS AND BETA VIDEO HEAD-CLEANERS
EACH \$6
'Wet' type with Cleaning Fluid.

ROCKER SWITCHES
250V 3A MAINS OR 3 POLE CHANGEOVER
ONLY 9c EACH

NEW DOT-MATRIX PRINTER SPECIALS
80CPS CP-80, parallel input..... \$349.00
80CPS FAX-80, parallel input..... \$359.00
100CPS Copal, parallel and serial.. \$475.00
20CPS DAISY-WHEEL letter quality.. \$595.00

FANS Ex-computer
5 inch
MUFFIN, 115v \$8
ROTRON, ETC. 220v \$10
DISCOUNTS SHOWN ARE OFF OUR REGULAR PRICES. SPECIALS AVAIL. AUGUST ONLY!

PRE-PAK electronics p/l

1a WEST ST, LEWISHAM, NSW

569-9797
24 HR PHONE ORDER SERVICE

Phone or mail order
BANKCARD accepted

Throw out your fuses


Philips has introduced a range of thermistors especially designed to replace fusible links.

The extended range of positive temperature coefficient thermistors are rated at 56 V and 256 V. They are automatically resettable, fast, reliable and have clearly specified, guaranteed current switching levels to simplify selection.


Philips claim the devices can often replace bimetal switches and fuses, and are ideal for protecting any electrical/electronic circuit in consumer products or industrial equipment. Applications include the protection of battery operated toys, hair-dryers, kitchen appliances, loud-speaker output circuits, semiconductor circuits, small motors and transformers.

The thermistors act as current sensors for connection in series with the load. At I_t (trip current) the resistance jumps from low to very high, limiting the circuit current and protecting the load. Below I_t , the voltage drop across the thermistor is less than 6% of the operating voltage due to the thermistor's low resistance at ambient temperature.

The current switching levels range from a few mA to over 1 A and are guaranteed stable throughout the life of the thermistor. Operating tempera-



Protected! A Philips thermistor *in situ*, acting as overload protection for a transformer.



ture range at minimum voltage is 0 to +55°C.


For further information contact **Philips, 67 Mars Road, Lane Cove, NSW.**

Accurate NTC thermistor

For electronic thermometers with a resolution of one tenth of a degree, Siemens has introduced the NTC thermistor M 841. The sensor operates over the entire body temperature range of 30°C to 50°C with a resolution of less than 0.1°C, which corresponds to a resistance tolerance of $\pm 0.4\%$.

The new NTC thermistor with its 20 mm long, silver-plated leads can be operated in the range between -40°C and +100°C. Rated resistance values are 3k or 5k; versions up to 100k are in the course of preparation. Other applications are in automotive electronics, heating and air conditioning and warning devices.

For more information contact **Siemens, 544 Church St, Richmond Vic 3121. (03)429-7111.**



Super accurate! The latest generation of NTC thermistors.

Dual power MOSFET driver

The TSC426/427/428 are dual CMOS high speed drivers, available from Promark Electronics. A TTL/CMOS input voltage level is translated into an output voltage level swing equalling the supply. The CMOS output will be within 25 mV of ground or positive supply. Bipolar designs are capable of swinging only one volt of the supply.

The low impedance high cur-

rent driver outputs will swing a 1000 pF load 18 V in 30 ns. The unique current and voltage drive qualities make the TSC426/427/428 ideal power MOSFET drivers, line drivers and dc-to-dc converter building blocks.

For more information contact **Promark Electronics, PO Box 115, Nunawading Vic 3131. (03)878-1255.**


Line filters

At this year's Hanover Fair Siemens showed a virtually complete range of power line filters, now comprising nearly 50 variants (all of them two-wire filters). Under the collective name 'Sifi', four series (B 84111/2/3/4) are now available with graduated attenuation values (normal/medium/very high/extra high).

Symmetrical insertion loss is up to 80 dB; the permissible current ratings are divided into six classes, from 1 to 20 A. There are different types of mounting and filters with equipment plugs for facilitating installation in the


EDP system power line. The most popular styles are now stocked in Australia.

Usually, for equipment with a linear power section, RFI can be effectively suppressed using filters with only normal attenuation (B84111, immunity: 1 MHz). Power sections with secondary pulsing, however, require filters with medium-range attenuation values (B84112, immunity: 0.1-100 MHz), and power sections and transistor/thyristor switches with primary pulsing require filters with very high attenuation values (B84113/4, immunity: 0.01-




100 MHz). 'Sifi' filters are also suitable for microprocessor systems, office equipment and domestic appliances.

For more information contact **Siemens, 544 Church St, Richmond Vic 3121. (03)429-7111.**



THE GREAT AUSSIE SOFTWARE COMPETITION



your computer and **Laptam Computers** have got together to run one of the most exciting competitions ever offered in a computer publication. The prize is a Laptam 3006 computer system — designed and built in Australia to top specifications — plus a Mannesmann Tally MT160 printer.

Total value \$14,000

All you have to do is write an original, innovative program for any application of your choosing. It doesn't have to be a super complex program, or even business orientated; the aim of the competition is to reward original Australian initiative in producing a well written, well structured program.

Groups of programmers as well as individuals are encouraged to enter the competition, which will run in *Your Computer* in four issues, from June to September 1984.

All programs remain the property of the authors.

Full details are in the current issue of *Your Computer*
Australia's largest selling microcomputer magazine
\$2.50 at all leading newsagents and computer stores

Construction Projects

AERIAL PROJECTS

D0064B \$6.75
Practical aerial designs including active, loop and ferrite which are relatively simple and inexpensive to build. Theory and mathematics are avoided.

CB PROJECTS

D0055B \$6.75
A number of useful designs include a speech processor, interference filters and a simple CB radio receiver. Stripboard layouts, wiring diagrams and notes on construction are provided.

POPULAR ELECTRONIC CIRCUITS — BOOK 2

D0061B \$7.75
A wide range of designs for electronics enthusiasts who are capable of producing working projects from just a circuit diagram without the aid of detailed information.

ELECTRONIC PROJECTS USING SOLAR CELLS

D0049B \$6.75
Includes a number of projects that benefit from solar power and obviate the problems encountered with batteries, such as weight and bulk, frequency of replacement, and failure when exhausted.

DIGITAL IC PROJECTS

D0050B \$6.75
The projects included in this book range from simple to more advanced projects — some board layouts and wiring diagrams included.

BUILD YOUR OWN HI-FI AND AUDIO ACCESSORIES

D0052B \$4.95
Essential for keen hi-fi and audio enthusiasts. Projects include stereo decoder, three-channel mixer, FET preamp for ceramic pick-ups, mic preamp with adj. bass, stereo dynamic noise limiter, loudspeaker protector, etc.

28 TESTED TRANSISTOR PROJECTS

D0053B \$4.50
Some circuits are new, others are familiar designs. Projects can be split and/or combined.

ELECTRONIC TIMER PROJECTS

D0066B \$6.75
These may have a high degree of accuracy with quartz control or they may be quite simple designs, using only a few components. A number of specialist timer projects are car windscreen-wiper delay unit, darkroom timer, metronome, etc.

ELECTRONIC PROJECTS FOR CARS AND BOATS

D0067B \$6.75
Fifteen fairly simple projects designed for use with 12V electrical systems but in some cases can also be employed with 6V and/or positive earth systems.

BUILDING AND INSTALLING ELECTRONIC INTRUSION ALARMS


D0356P \$16.95
Electromechanical intrusion alarms, audio and vibration alarms, photoelectric alarms, proximity alarms and car alarms are all covered in this book. Hints on selection, construction, installation and maintenance are also included.

BUILD YOUR OWN ELECTRONIC EXPERIMENTER'S LABORATORY USING ICs

D0384B \$2.75
Projects include a simple audio frequency oscillator, a TTL pulse detector, a simple square wave generator and a high impedance voltmeter.

ELECTRONIC SCIENCE PROJECTS

D0412B \$5.95
Twelve electronic projects with a scientific flavour — each project includes details on how it works, construction and use. Includes a simple infra-red laser, a low-cost solid-state oscilloscope, a pH meter, and electronic stethoscope and an electronic seismograph.



POWER-SUPPLY PROJECTS

D0047B \$5.95
Gives a number of power-supply designs, including simple unregulated types, fixed-voltage regulated type and variable voltage stabilised designs. The designs are all low-voltage types for semiconductor-circuits.

PROJECTS IN OPTO-ELECTRONICS

D0057B \$6.75
Included are simple circuits using ordinary LEDs as well as more sophisticated designs such as infra-red transmitters and detectors, modulated light transmission and also photographic projects, etc.

Electronics Today Book Sales

Simply fill out the reply-paid card insert and send to:


**ETI Book Sales,
140 Joynton Ave.,
Waterloo, NSW 2017**

SCRs AND RELATED THYRISTOR DEVICES

E0095P \$21.25
Written for experimenters, technicians and engineers, this book is a practical and comprehensive guide to the theory, operation, specifications and applications of silicon-controlled rectifiers (SCRs) and related thyristor devices.

REGULATED POWER SUPPLIES

E0096P \$29.75
Comprehensive discussion of the internal architecture and operation of the latest solid-state regulators. Explains when regulated supplies are needed and how to incorporate them in your projects. Also discusses modern circuitry including linear and switching circuits and late ICs.



PRACTICAL SOLID-STATE CIRCUIT DESIGN

E0094P \$16.95
An introductory course in practical solid-state circuit design for the experimenter, designer or technician interested in constructing tailor-made circuits.

ACTIVE-FILTER COOKBOOK

E0084P \$24.25
Learn to construct filters of all kinds — highpass, lowpass, bandpass. The book is easy to understand — no advanced maths or obscure theory is used.

DESIGN OF PHASE-LOCKED LOOP CIRCUITS, WITH EXPERIMENTS

E0074P \$16.95
An excellent introduction to the theory, design and implementation of phase-locked loop circuits using various TTL and CMOS devices. Includes manufacturers' data sheets and describes the use of breadboarding aids in laboratory-type experiments.

PRACTICAL TRANSFORMER DESIGN HANDBOOK

E0075P \$38.95
An easy to understand, illustration-filled guide to designing and constructing transformers. Reviews the fundamentals of electricity, magnetism and algebra needed to understand transformer theory, and covers general design considerations, transformer types, power losses and transformer use in converters and inverters.

TTL COOKBOOK

E0083P \$20.50
A complete look at TTL logic circuits — what TTL is, how it works, and how to use it. Many kinds of practical TTL are included, such as digital counters, electronic stopwatches, digital voltmeters, etc.

IC CONVERTER COOKBOOK

E0139P \$22.75
Written for the practising engineer, technician, hobbyist or student, this book will be an invaluable working guide to the understanding and use of IC analogue/digital and digital/analyse converters.

CMOS COOKBOOK

E0086P \$21.00
This book explains CMOS technology and its application to 'real world' circuitry. A mini-catalogue is included, which lists more than 100 devices, giving pinouts and application notes.

IC TIMER COOKBOOK

E0087P \$26.95
Gives you a look at the hundreds of ways IC timers are used in electronics instrumentation.

IC OP-AMP COOKBOOK

E0088P \$25.75
Basic op-amp theory in detail, with 200 practical, illustrated circuit applications: JFET and MOSFET units are featured, plus manufacturers' data sheets and company addresses.

DESIGN OF OP-AMP CIRCUITS, WITH EXPERIMENTS

E0089P \$17.50
The design of the fundamental circuits that are the basic building blocks of more sophisticated systems. A series of 35 experiments illustrates the design and operation of linear amps, differentiators and integrators, and lots more.

555 TIMER APPLICATIONS SOURCE BOOK, WITH EXPERIMENTS


E0090P \$11.25
The construction of the 555 timer and numerous practical examples of its applications in all areas of electrical and computer engineering, including 17 simple experiments.

Circuit Techniques & Design

HOURS OF FUN!

Tug-O-War Game

Peter Ihnat



Try our electronic intergalactic Tug-O-War decision maker! Originally created for the Galactic Hyperspace Planning Council, you can build and use it right in your own home.

IT'S BEEN SOME TIME now since we published a simple row-of-LEDs type game. This project is quite simple to build and play but has a special challenge all its own. The Tug-O-War consists of a row of 15 LEDs, one of which is lit at any time. To start a game, press the reset button and the middle LED will come on. You and your opponents are each armed with a pushbutton. By rapidly and repeatedly pressing your button, you try to 'pull' the LED which is on towards your end of the unit, as does your opponent. Each pushbutton press causes the LED on your side of the LED currently on to light. So with no opponent, the LED closest to you will light after seven presses. The same goes for your opponent. The aim of the game then is to win by 'pulling' the lit LED down to your end of the unit by pressing your pushbutton as fast as possible.

Easy, I hear you say. Don't be fooled by the apparent simplicity! After many battles fought in the ETI lab, we noticed that intense concentration is required to win — a laugh, cough or any distraction can lose you some LED positions which are hard to regain (a jab in the opponent's ribs usually distracts them long enough for you to catch up). Another observation was that anyone who plays arcade video games regularly has a noticeably higher button-pushing speed and can maintain it over

relatively long periods of time (i.e.: Geoff Nicholls wins most times!).

Extra features

Three minor additions to the basic game are incorporated in this project. Firstly, I have included a 'game select' switch for those who would rather *push* the lit LED away from their side instead of *pulling* it towards them. In one position, the game played is *Tug-O-War* (pull towards you); in the other position it is *Indian Wrestling* (push away from you). But note that the direction of LED movement is the only difference between the two games.

Secondly, I've connected each of the end LEDs back into the circuit so that when either is reached, the circuit latches and further presses of the pushbuttons are ignored. If flashing LEDs are used in the end positions, then a very effective 'win indication' will result!

The final addition is a sound option. Using a low cost buzzer, the game 'beeps' with increasing speed as the lit LED approaches either end of the unit. This type of aural stimulation is quite effective in such a game since it induces the player to press his pushbutton faster as he draws closer to winning.


Any of the three additions just discussed can be left off the current project. Including them, however, doesn't increase the

HOW IT WORKS ETI-807

The heart of the game revolves around IC3 and IC4. IC3 is a binary up/down counter which has two clock inputs — count up and count down. Its four outputs feed IC4 which is a 4-to-16 line decoder. Its 'truth' table, showing its complete operation, is given in Table A.

Only one of its outputs will be low (0) at any time — which output depends on the value applied to its four inputs. For example, 0000 on the inputs causes output 0 to go low; 0111 on the inputs causes output 7 to go low. Here, 15 LEDs are connected to these outputs and their common side goes to +5 volts through the current limiting resistor R9. The state of the counter determines which one of the LEDs will be on.

In basic terms, a player feeds pulses into either the *up* or *down* count input of the counter. This causes the next LED either left or right of the lit LED to light, depending on which player pressed his button.



The diagram illustrates the internal circuitry of a 16-bit digital game. Key components and their connections include:

- Power Supply:** A +5V supply is connected to various points throughout the circuit, including the ICs, resistors, and LEDs.
- IC1 (74LS74):** A dual in-line package (DIP) with pins 1, 2, 3, 4, 7, 11, and 14 connected to the +5V supply. Pins 10 and 13 are connected to ground (0V).
- IC2 (74LS123):** A DIP with pins 1, 2, 3, 4, 7, 11, and 14 connected to the +5V supply. Pins 10 and 13 are connected to ground (0V).
- IC3 (74LS193):** A DIP with pins 1, 2, 3, 4, 7, 11, and 14 connected to the +5V supply. Pins 10 and 13 are connected to ground (0V).
- IC4 (74LS154):** A DIP with pins 1, 2, 3, 4, 7, 11, and 14 connected to the +5V supply. Pins 10 and 13 are connected to ground (0V).
- IC5 (74LS86):** A DIP with pins 1, 2, 3, 4, 7, 11, and 14 connected to the +5V supply. Pins 10 and 13 are connected to ground (0V).
- IC6 (555):** A DIP with pins 1, 2, 3, 4, 7, 11, and 14 connected to the +5V supply. Pins 10 and 13 are connected to ground (0V).
- Resistors:** Various resistors (R1, R2, R3, R4, R5, R6, R7, R8, R9, R10, R11, R12, R13, R14) are used to limit current and provide timing. Values range from 15k to 270k.
- Capacitors:** C1 (1μF) and C2 (220μF) are used for timing and decoupling.
- LEDs:** 16 LEDs (LED1 to LED15, with LED8 being green and the others red) are connected to the output of the ICs. LED1 and LED15 are flashing LEDs.
- Buzzer:** A buzzer is connected to the output of the ICs.
- Switches and Buttons:** SW1 (TUG-O-WAR), PB1, PB2, and PB3 (RESET) are used for user input.

**LED1 AND LED15 ARE FLASHING LEDS
LED8 IS A GREEN LED
THE REST ARE RED LEDS**

For a guide to buying components and kits see **SHOP AROUND** this issue.

The middle LED is fed from output 0 and is the one that lights when RESET is pressed. Seven LEDs are placed either side of the middle giving 15 in total. Output 8 is not used.

IC1 and IC2 are used to 'condition' the inputs to prevent the quality of the pushbuttons from affecting the outcome of the match. Otherwise, a switch with bad contact bounce will give that player too much of an advantage.

IC1 is a dual D flip-flop but is not used as such. Each of its flip-flops has a **CLEAR** and **SET** input and these are used to 'de-bounce' the pushbuttons. The output from the flip-flop is normally high, going to low when the button is pressed and returning high when released.

IC2 is a dual monostable which produces a very short, active-low pulse on the falling edge of its input (see the timing diagram). These short pulses are used to clock IC3. The GAME SELECT switch simply interchanges the counter's clock inputs.

To stop the game when a LED reaches one end, diodes D1 and D2, and resistor R7, form a simple NOR gate which controls the CLEAR input of the monostables. During the game, R7 pulls the CLEAR high so that the monostables can function properly. When either end of the row of LEDs is reached, the CLEAR is pulled low, preventing the game from continuing.

The sound option basically consists of a low cost buzzer and a 555 timer running as a low frequency astable oscillator. Each time the 555 output goes high, the buzzer sounds. To control the speed of beeping, R10, R11 and R12 change the voltage at the

TABLE 1: Truth table for 75154


[illegible]

X = "Don't Care" Condition

control input of the 555. This voltage is very roughly proportional to the binary output of the counter. Normally, these resistors would connect directly to the counter's outputs and the beeping speed would increase as the counter went from 0000 to 1111. However, in this project, the slowest beeping speed should occur when the counter outputs 0000 and it should increase as it counts from 0001 to 0111 or from 1111 down to 1001 (because 0000 was chosen to

correspond with the middle LED position).

IC5 is used to invert the three lower bits of the counter, feeding R10 to R12 only when the most significant bit is high. This almost works correctly except that the speed of beeping corresponding with counter outputs 0000 and 1111 are the same. This is not all that noticeable when playing the game and besides, isn't worth the expense of extra circuitry to solve the problem.



cost of the unit too much but makes the game just that much more exciting.

Construction

I constructed the project on a printed circuit board. While it's not essential, it does markedly reduce the amount of wiring required and the possibility of wiring errors, especially if you're new to this hobby. I recommend you either purchase a ready-made pc board (or a made-up kit, saving all the bother of chasing parts), or you can make your own. The board artwork is reproduced elsewhere if you want to copy that, or artwork is available through out artwork service (see the 'Shoparound' page this issue).

The front panel I 'dressed up' with a plastic Scotchcal label. Like pc boards, these are quite easy to make (see ETI September 1977, Photostats of this article are available through ETI Reader Services, see page 3 this issue). If you purchase a made-up kit though, a Scotchcal label will likely be included. The box I used is a common plastic 'zippy' box.

Begin construction by first checking the pc board, whether you bought it ready-made or etched it yourself. Make sure that there are no broken tracks, small links between close tracks or incorrectly drilled holes. If all is well, then mount and solder the seven wire links as shown on the component overlay diagram. Note that the five short links can be bare wire, whereas the longer two should be insulated hookup wire as a precaution against shorts.

Next, insert and solder the resistors, capacitors, diodes, and finally the ICs.




Figure 1. Showing how the LEDs are all mounted.




Figure 2. Assembly details for the players' hand controls.

Check the orientation of the two capacitors, the diodes and ICs. IC sockets are not required unless you are dubious about soldering the ICs directly.

The tricky part of construction is mounting the LEDs. Each LED needs to be oriented correctly and its leads bent over 90 degrees about 5 mm from the base. These can then be positioned and soldered to sit approximately 8 mm off the pc board (see Figure 1 and the photos). If you're adding the options, now's the time to do it. Watch component orientation (check with the component overlay).

Drill the holes required in the front panel and sides of the zippy box. Mark out the positions carefully and centre-punch them before drilling. Clean off any burrs afterwards.

To stick the Scotchcal label onto the front panel, use the following technique. Firstly, spray paint the panel with white paint to prevent any imperfections in the aluminium from showing through the thin plastic Scotchcal material. Put it aside to dry. Next, peel the paper backing off the Scotchcal label and soak the label in water. Scotchcal, and most contact-stick plastics, become less tacky when wet and this allows them to be handled much more

PARTS LIST — ETI-807


Resistors	all 1/4 W, 5% unless noted
R1-R7, R11*	15k
R8	470R
R9	220R
R10*	27k
R12*	5k6
R13*	270k
R14*	120k
R15	(see text), 1 W
Capacitors	
C1*	1µ/16 V pc-mount electro
C2	220µ/25 V
Semiconductors	
IC1	74LS74
IC2	74LS123
IC3	74LS193
IC4	74LS154 or 74154
IC5*	74LS86
IC6*	555 timer
D1, D2	1N914, 1N4148
LED1, LED15	5 mm flashing LED (optional; otherwise as for LED2 etc.)
LED2-LED7, LED9-LED14	5 mm red LED
LED8	5 mm green LED
ZD1	5V1, 1 W zener (see text)
Miscellaneous	
PB1, PB2	SPDT momentary-action pushbutton switch (or DPDT type, e.g. Dick Smith cat. no. S-1220).
PB3	SPST momentary-action pushbutton (e.g. Dick Smith S-1102).
SW1	DPDT ultra-miniature toggle switch (e.g. Dick Smith S-1245), if required.

ETI-807 pc board; 60x113x196 mm zippy box; Scotchcal label; buzzer* (e.g. Dick Smith L-7009); two stereo 3.5 mm jack plugs and sockets (optional); 4xAA battery holder; dc power socket if mains eliminator is used (see text) fifteen LED bezels; hookup wire; two metres of twin-shielded cable; nuts, bolts, film containers, etc.

Price estimate: \$30-\$40



(depending on options)

* Parts marked with * only required if sound option is fitted.



easily. Also soak the painted panel (after it has dried!) and apply the label to it.

You'll notice that, as long as both surfaces are wet, it's possible to slide the label around until it is correctly positioned (applying dry Scotchcal gives you only one chance to get it right — usually you



miss!!). Then wipe the label with a piece of cloth to squeeze out excess water and wait until the whole assembly is dry. Hey Presto! One correctly attached label.

Now insert the LED bezels and push all the LEDs through. The two front panel switches should be mounted next and

wired to the pc board. Use washers beneath the nuts to save tearing the Scotch-label.

The players' hand controls can now be made. Any type of container can be used; for example a small zippy box. For the prototype, I used two plastic film contain-

Inside-out. Showing the general assembly. The box I used features 'slots' down the sides and the pc board slips into these. The battery holder visible here was held in place with double-sided sticky pad.

ers. I cut a hole in the bottom of each container and mounted the pushbutton switch, as shown in Figure 2, after soldering the connecting cable to the contacts. A small hole in what used to be the film container's lid enables the shielded cable to exit. The other end of the cable can be terminated with a 3.5 mm stereo plug which plugs into a 3.5 mm socket on either side of the main unit or, to cut costs, simply connect it directly to the pc board, passing the cable through a hole drilled in the side of the box.

If a dc plugpack is to be used to power the unit (see later), then the corresponding socket can be mounted in the side of the box and wired up.

The buzzer, if used, can be mounted in any convenient position, either inside or outside the box.

Powering up

Once constructed, the unit will run from a variety of power sources. The ICs used in the game are TTL types and this immediately specifies +5 volts as the required supply. If you have a simple 5 V dc power supply available then the problem is solved. In this case, resistor R15 and zener ZD1 are not required and simply wire your supply to where the zener would have been. **IMPORTANT** — ensure that the supply is connected the right way round, otherwise *all* the ICs will be destroyed.

Project 807

Another possible power supply for the game would be batteries. Four cells will produce six volts which TTL will happily accept. Once again, R15 and ZD1 are not required. Small battery holders which take four cells are readily available. You can use either AA, C or D type batteries. Actually, four AA batteries will fit comfortably inside the unit but you'll have to fit an on/off switch somewhere on the side of the box.

If you end up having the batteries outside the unit then there is a possibility that someday, somehow, someone might accidentally reverse the polarity. To prevent any damage to the unit, place a diode,

such as a 1N4002, in series with the positive battery connection with the anode going to the battery positive cathode to the circuit's positive supply line. The diode could be mounted where R15 would normally have gone.

For those of you who have a dc mains eliminator (plugpack) for low voltage gadgets then fit ZD1 and choose R15 from Table 1. The current consumption with a five volts supply is just over 100 mA, so make sure that your plugpack can supply at least that much. Also, fit the correct socket on the side of the unit to match the output plug from your plugpack.


Good tugging!

TABLE 1



Selection of R15

dc plugpack voltage	R15 1W
7.5 V	22R
9 V	33R
12 V	56R



eti
807



eti 807 TUG-O-WAR



PLAYER 1



PLAYER 2



FERGUSON TRANSFORMERS

PRINTED CIRCUIT BOARD MOUNTING TRANSFORMERS

PL9 5VA	\$7.95	PL24 5VA	\$7.95	PL18/12VA 10.50
PL12 5VA	\$7.95	PL30 5VA	\$7.95	PL24/12VA 10.50
PL15 5VA	\$7.95	PL40 5VA	\$7.95	PL30/12VA 10.50
PL18 5VA	\$7.95	PL161 5VA	\$10.50	

LOW PROFILE CHASSIS MOUNTING TRANSFORMERS

PL12 20VA \$14.75	PL12 60VA \$19.50	PL24 40VA \$16.50
PL15 20VA \$14.75	PL15 60VA \$19.50	PL30 40VA \$16.50
PL18 20VA \$14.75	PL18 60VA \$21.50	PL40 40VA \$16.50
PL24 20VA \$14.75	PL24 60VA \$21.50	PL30-9/40VA \$23.50
PL30 20VA \$14.75	PL12 40VA \$16.50	
PL40 20VA \$14.75	PL15 40VA \$16.50	PL30/60VA \$21.50
PL15-18 20VA \$23.50	PL18 40VA \$16.50	PL30-9/60VA \$25.50

CONVENTIONAL CHASSIS MOUNTING TRANSFORMERS

PF3577 \$33.90	PF3993 \$23.90	PF4362 \$57.90
PF3783 \$79.50	PF4244 \$46.50	PF4363 \$57.90
PF3787 \$21.50	PF4354 \$49.50	PF4405 \$44.50
PF3788 \$43.50	PF4361/1 \$49.50	

BELL TRANSFORMERS

PPB4 1000 \$15.50	PPB8 1000 \$15.50	PPB12/500 \$15.50
-------------------	-------------------	-------------------

AUDIO TRANSFORMERS

MT552 \$28.50	OP590 \$46.50	OP592 \$36.90
---------------	---------------	---------------

D.C. POWER SUPPLIES

PPA3DC \$12.90	PPA6DC \$12.90	PPA9DC \$12.90
PPA4.5DC \$12.90	PPA7.5DC \$12.90	

BUILD YOUR OWN SPEAKERS WITH PHILIPS

Part No.	Price
ADO 1610 T8	\$16.95
ADO 2160 SQ8	\$49.50
AD70601 W8/620	\$28.50
AD 12250 W8	\$83.00

P.C. EDGE CONNECTORS



S100 gold plated wire wrap	\$8.50
S100 solder tail	\$7.90
D2 Motorola bus	
43 B6 solder tail	\$8.50
43 B6 gold plated wire wrap	\$11.50

10 TURN POTENTIOMETERS

Stock resistance values

50R 100R 200R	
500R 1K 2K 5K	
10K 20K 50K	
100K	

Spectrol model 534 - 1 shaft	
Price 1 - 9	\$9.50
10 + values may be mixed	\$8.50

DIP PLUGS

Ideal for use with flat ribbon cable or to mount components on

24 pin \$1.50	24 pin \$2.90
40 pin \$1.90	40 pins \$5



POWER TRANSFORMERS

SPECIALLY DESIGNED FOR MICROCOMPUTERS

- Good regulation electrostatic shield
- RI 810 8V @ 10A x 15V @ 1A \$39.50
- RI 820 8V @ 20A 15V @ 1A \$54.50

20 TURN

CERMET TRIM POT



SPECTROL 43P ACTUAL SIZE

STOCK RESISTANCE VALUES
10R 20R 50R 100R 200R 500R 1K 2K 5K 10K 20K 50K 100K 200K 500K 1M 2M

1-9	10-99	100+
\$1.40	\$1.30	\$1.00

Values may be mixed

Hexadecimal Keypad

\$42.50



19 key pad in cludes 1 10 keys ABLDEF and 2 optional keys and a shift key

Ideal for dream project

MULTIDIALS




Dials to suit 10 T Pots

Model 21 18 dia	\$24.50
Model 16 9 dia	\$19.50
Model 18 1 x 175 dia	\$27.50

RS232 & "D" TYPE CONNECTORS

PART NO	DESCRIPTION	1-9	10-25
DE 9P	9 PIN MALE	\$1.75	\$1.60
DE 9S	9 PIN FEMALE	2.25	2.10
DE 9C	9 PIN COVER	2.55	2.45
DA 15P	13 PIN MALE	1.10	1.05
DA 15S	15 PIN FEMALE	2.25	2.10
DA 15C	15 PIN COVER	1.15	1.05
DB 25P	25 PIN MALE	2.95	2.80
DB 25S	25 PIN FEMALE	3.45	3.30
DB 25C	1 pc Grey Hood	1.20	1.10
DB 25C2B	2 pc Black Hood	1.40	1.35
DB 25C2G	2 pc Grey Hood	1.35	1.25
DC 37P	37 PIN MALE	3.95	3.75
DC 37S	37 PIN FEMALE	5.45	4.95
DC 37C	37 PIN COVER	2.45	2.25
DH S	Hardware Set (2 Pairs)	1.05	0.95

RITRON DIGITAL MULTIMETERS




Q16010 specifications

1-4	5+
\$57.50	\$55.00

Q17040 specifications

1-4	5+
\$87.50	\$83.50

- 28 Ranges
- Push Button Operation
- Auto Polarity
- Low Battery Indicator
- Full Overload Protection
- Finger Guards on Probes and Shrouded Plugs for Safety
- Accuracy: 1 year 18°C to 28°C (+ % of reading + No. of Digits) 200 hour battery life



16 Pin Zip Dip II \$11.50
24 Pin Zip Dip II \$12.50
40 Pin Zip Dip II \$17.50
28 Pin Zip Dip II \$16.50

DIP SWITCHES SPST

PN	No. of Switches	Price
SD4	4	\$1.70
SD6	6	\$2.30
SD7	7	\$2.40
SD8	8	\$2.50
SD10	10	\$3.00

DIP SWITCHES SPST



cermet single TURN TRIM POT

Spectrol model 63P ACTUAL SIZE

STOCK VALUES
10R 20R 50R 100R 200R 500R 1K 2K 5K 10K 20K 50K 100K 200K 500K 1M 2M

1 9	\$1.20
10 99	\$1.00
100	\$0.90

Values may be mixed

HEATSINKS

High Thermal Capacity Black Anodised

	1-4	5-9	10-49	50-99	100-499	500 plus
	\$	\$	\$	\$	\$	\$
HS1 — 38mm	1.85	1.75	1.50	1.35	1.00	0.90
HS2 — 75mm	3.00	2.90	2.50	2.00	2.00	1.50
HS3 — 150mm	5.80	5.40	4.90	3.80	2.90	2.70
HS4 — 225mm	8.10	7.60	7.10	5.90	4.50	4.30
HS5 — 300mm	8.90	8.40	7.90	6.50	4.90	4.60

Unanodised

HS11 — 38mm						
140	120	100	090	080	070	
HS12 — 75mm						
250	220	190	160	125	120	
HS13 — 150mm						
490	450	400	320	245	240	

BLANK CASSETTES T.D.K.

TDK ADC60	1 for \$3.99	10 for \$28.60
TDK DC60	1 for \$2.30	10 for \$19.99
TDK ODC60	1 for \$3.85	10 for \$34.10
TDK SAC60	1 for \$3.85	10 for \$34.10
TDK SAXC60	1 for \$6.30	10 for \$50.60
TDK DC90	1 for \$2.60	10 for \$22.10
TDK ADC90	1 for \$3.85	10 for \$33.00
TDK SAC90	1 for \$4.65	10 for \$42.90
TDK ODC90	1 for \$5.20	10 for \$59.50
TDK SAXC90	1 for \$5.99	10 for \$59.99
TDK DC120	1 for \$4.99	10 for \$40.70
TDK ADC120	1 for \$5.99	10 for \$53.00

TDK VIDEO TAPES

E180 \$13.50ea L750 \$14.50ea

Errors and Omissions Excepted

POSTAGE RATES

\$1-\$9.99	\$2.00	\$10-24.99	\$3.50
\$25-49.99	\$4.50	\$50-99.99	\$6.00
\$100-199	\$8.00	\$200-499	\$10.00
\$500+	\$12.00		

(All above charges are for surface mail and some heavy items will vary from these rates.)

Cert. post for orders over \$100 included "free".
Reg. post for orders over \$200 included "free".
Account orders from schools, govt. depts., public co's., gratefully accepted. Min order amount \$20.00 (or a min. \$5.00 accounting charge will apply.) Comet Road Freight, Airmail etc. are extra.

Please debit my Bankcard.
Bankcard No.
Expiry Date
Name
Signature

ROD IRVING ELECTRONICS

425 High St., Northcote 3070 (03) 489 8866 (03) 489 8131
48-50 A Beckett St., Melbourne (03) 347 9251

Mail Order and Correspondence
P.O. Box 235 Northcote 3070

To Order By Phone

Mail Order Hotline (03) 481 1436



ELECTRONIC MOUSETRAP

With Auto Despatch and Reset

Ian Thomas

Furry freeloaders are generally not welcome in the home unless they're of the 'house-trained' variety. Commercial poisons (saturated in grain) act as an anti-coagulant and the beasts die by bleeding to death (slow and aesthetically unpopular). Other methods maim or kill slowly. This electronic mousetrap despatches them in milliseconds and automatically resets!

RECENTLY, relatives of mine reported that they had acquired some tiny furry freeloaders and couldn't find a mousetrap anywhere. This seemed a bit strange so I went to try and get some myself. Lo and behold, they were right — the mouse plague reportedly invading our three eastern states seemed to have taken all available supplies. I must have tried at least ten shops in both my local shopping centre and in the big smoke but there wasn't one mousetrap to be bought. OK then, perhaps it would be an idea to build my own. At least if the design turned out to be better, then I'd get a new path to my front door on the insurance!*

Given that the mousetrap was to be electronic (what else for an electronics engineer?), the first question was exactly how to despatch the miniscule marauders without a risk of doing the same to me. Suggestions from Roger for robot arms with hammers in their claws seemed a little too 'high tech' for me and perhaps not quite practical (I never suggested that ... Ed). The easiest way seemed to be a simple ZAP at just the right time and place.

The simplest way to do this would be to take the mains lead, connect the neutral to a metal plate and the active to an insulated bolt in the centre of the plate with some cheese on the bolt. It would probably work just fine but would also probably clean up all the pets and small children in the area too! Things should be simple, but not *too* simple — to paraphrase Einstein.



The best idea seemed to use a high voltage pulse triggered by the mouse itself to despatch the little pest and try to arrange the triggering so it would be very hard for a person to get a potentially lethal belt through any part of their anatomy.

If the object of the exercise is to electrocute the rodents then it seemed a good idea, working on the "more is better" principle, to poke as much power as possible into the mouse. Clearly then, if we want to achieve optimum power transfer into the mouse then it is necessary to arrange for the output impedance of the high voltage generator to be the complex conjugate (opposite) of the mouse input impedance or:

$$Z_{out} = Z_{mouse}$$

where

$$Z_{mouse} = R_{mouse} + jX_{mouse}$$

and therefore

$$Z_{out} = R_{mouse} - jX_{mouse}$$


About this stage I started to get the feeling that technical niceties were starting to get the better of things (besides which, have you ever considered how to measure the complex input impedance of a mouse? Awkward to say the least!). Since it's a well

known tenet that "... it's the volts that jolts but the mills that kills," I decided on generating one massive pulse of high voltage with a reasonably low output impedance to do the deed.

Generating this sort of high voltage pulse has been done for years now (perhaps in a rather extreme form). Capacitor discharge ignition systems in cars are a case in point. They are well understood, so I decided to use a similar method in my mouse-macerator.

The method requires that a capacitor be charged to a high dc voltage and then dumped into a coil which acts both as an inductance and a step-up transformer. The output voltage of the whole assemblage is equal to the capacitor dc voltage times the coil step-up turns ratio. Normal CDI systems deliver about 30 to 40 kV, *far* too much for this application. These voltages are hard to contain and tend to flash over everywhere. Also, the high step-up turns ratio in an automotive coil (usually about 100:1) means an equal step-down in current, all else being equal, which we don't want.

* On the theory that "build a better mousetrap and the world will beat a path to your door".



Design details

If we assume that the mousetrap will be mains powered then a simple diode and resistor combination will charge the storage capacitor to about 340 volts if left to itself and, with a 1M resistive bleed, it drops to about 280 V. This is still heaps (we want to terminate them — not blow them to pieces) and if the capacitor is followed by a 20:1 step-up coil the output voltage becomes about 6 kV — just nice!

The actual mechanism of the trap requires that the voltage not be continuously maintained but pulsed when the victim is nibbling on the bait. Even the most credulous mouse would probably be a bit wary of cheese that glows blue in the dark, buzzes and crackles a lot and stinks of ozone (although I have known limburgers with such characteristics!). This means that the sensing mechanism that detects the presence of the victim must also be able to tolerate 6 kV pulses. Another major problem to be aware of is that the trap is running off the mains and the output *must* be isolated to avoid any unfortunate mishaps.

The actual layout for the trap is a central disk, on which the cheese is placed, surrounded by a wide earth mat. The theory is that when our furry foe approaches the bait his back paws will be on the earth and its nose or front paws will touch the central electrode. When the trap triggers, all the goodness stored in the capacitor will flow through the whole body of the mouse causing instant discorporation and, hopefully, throwing it away from the trap ready for the next candidate for the big cheese factory in the sky. (See? — auto despatch and reset!).

The easiest way to isolate the trigger circuit from the output pulses is to use a large series resistor and in the actual design I used the largest I could get, namely 22M. Experimenting with a DVM I found that normal body resistance of a person (me) is of the order of 1M, most of which is skin resistance. The resistance of the interior of a body is very low as it's mostly salt water so I reasoned that a mouse would probably be about the same for the worst case and, if its mouth was actually on the cheese, probably

a bit less. Therefore, compared to the 22M resistor, the mouse could be regarded as a short circuit.

The secondary winding of the coil is connected directly to the central electrode. To prevent it shorting out the resistance of the mouse the other end of the secondary is connected to two diodes which are reverse-biased by the trigger power supply. This nicely leaves the whole secondary floating when it has no voltage across it, but when the trap triggers one of the diodes will turn on and clamp the end of the coil effectively to earth (or +12 Volts which, compared to 6 kV, is the same thing) giving the mouse the full benefit of the voltage excursion.

As the secondary is *very* well insulated from everything else (it has to be to prevent flashover or punch-through), this arrangement ensures that mains voltages are completely isolated from the business end of the trap.

To further ensure that no mains could ever get near the output I powered the trigger circuit from a small transformer, even though only a few milliamps are needed, and coupled the trigger circuit to the dump SCR through an optocoupler. This nicely leaves the mains, dump capacitor and coil primary as the only parts of the trap that are connected directly to the 240 V mains.

The trigger circuit is a simple two-transistor amplifier with positive feedback around it to turn it into a monostable pulse generator. The most current that can flow through the 22M resistor is about $\frac{1}{2}\mu\text{A}$ so two transistors are needed to give sufficient gain to trigger the optocoupler. The optocoupler itself is a Motorola MOC3021 which has a triac type output and is normally used in triac power control circuits but it works just fine triggering SCR's too.

The dump capacitor is charged through two 220K resistors and a diode directly connected across the 240 Vac. Two resistors are used because there is no way of being sure which mains input is active and which is neutral. Using a resistor from each input ensures that, no matter how it's connected, a hapless project builder won't hang himself directly across 240 V when testing things

out — he'll at least have 200k to ease the pain!

The coil primary has a diode across it so that after the SCR fires and dumps the capacitor's stored energy into the coil the diode turns on and prevents the coil-capacitor ringing and transferring the energy back into the capacitor again (see "How It Works"). The diode *must* be a rapid recovery type as things happen pretty fast when the SCR fires and 1N4006s are nowhere near quick enough. Leaving the diode out reduces the effectiveness of the ZAP dramatically and without it I doubt that the pulse would do more than seriously annoy the mouse (and we don't want to annoy the mice do we?).

The coil itself posed me a few problems as I detest sitting for hours winding fine wire on formers and trying not to either drop it and have to start again or, worse, breaking the wire. For reasons I've already talked about, the coil has to have a 20:1 turns ratio so every turn on the primary means 20 more turns on the secondary. Clearly we want the fewest turns possible on the primary. *However* the coil primary must meet other requirements as well.

When the trap is triggered, the energy stored in the capacitor is transferred to the coil primary. Hanging just a few numbers around this we get:

$$\frac{1}{2} CV^2 = \frac{1}{2} LI^2$$

where V is the capacitor voltage and I is the peak coil current.

Rearranging things we get:

$$I = V\sqrt{\frac{C}{L}}$$

All this says is that, if the primary inductance is too small the peak current becomes impractically large. As this peak current has to flow through the SCR, and after that the clamping diode, the peak rating of these devices determines the smallest value inductor we can tolerate. As most diodes can tolerate high currents for microseconds I took the rating of the SCR as the determining value. This was given as 100 amps (no kidding — that's the peak current that flows!). Which, going through the numbers, gives an inductor value of about 20 microhenries. I did a bit of experimenting with various core materials and found that about twenty turns around a ferrite core gave the right value (see *Construction*) which gave me 400 turns of secondary to wind.

In the final coil these very high currents cause the core material to saturate which makes these values a bit dubious but the final thing still seems to work just fine!

The picture is actually a bit more complicated than these simple calculations show as current also flows in the secondary/mouse circuit which helps avoid the saturation problem. In order to ensure that saturation of the core doesn't cause problems I made sure that the coil would still work as a transformer by winding both the primary and secondary as simple, one-layer solenoids ▶

\$100,000 STOCKTAKE SALE

We are absolutely up to the rafters with direct import electronic products, and with more and more shipments due this month we must clear excess stock levels right now. So here is your chance to save a fortune - but please note **1st come, 1st served** - these prices will definitely not be offered again. **Phone your order Toll Free today 008 999 007 (up to 6pm)** and remember with Altronics Famous JetService delivery we deliver next day to capital cities and suburbs (please allow 24 - 48 hours extra for country areas).

NICAD RECHARGEABLE AA and C size



Huge Savings
with Bulk Qty's
Massive 1.8 A/H
(C size)

Manufactured by Furukawa Japan. In our estimation one of the World's finest Nickel Cadmium Battery manufacturers.

	1-9	10-25	25 Up
S 5020 AA size	\$2.45	\$2.00	\$1.85
S 5022 C size	\$5.95	\$5.00	\$4.65

COMPONENT JOYSTICKS Standard type (non-centering)

- Resistance 100K ohm
- Lever movement 60°
- Metallic knob
- For TV games, RC units
- Life 300,000 cycles



NOW 1/2 PRICE
\$2.50
K 9680

Self Centering Type

Resistance 5K ohm suit ETI project for microbee
"Proportional Analogue Joystick" Dec 1983

K 9689 \$12.50 \$10.00


ZIF SOCKETS (Zero Insertion Force)



	Were	Now	10+
P 0650 24 Pin	12.95	11.50	9.90
P 0655 28 Pin	15.00	13.80	11.90

FAMOUS J & M BRAND D RANGE CONNECTORS SAVE 25% ON BULK QUANTITIES!

EXCLUSIVE TO
ALTRONICS AND DEALERS
IN AUSTRALIA



	WERE	NOW	10UP
P 0880 DB 9 Male 9 Pin	2.90	2.20	1.95
P 0881 DB 9 Female 9 Pin	2.95	2.70	2.50
P 0882 DB 9 Male PCB Mnt	3.25	3.10	2.98
P 0883 DB 9 Female PCB Mnt	3.95	3.75	3.60
P 0889 DB 9 Backshell Cvr	2.00	1.80	2.30
P 0890 DB15 Male 15 Pin	2.95	2.90	2.29
P 0891 DB15 Female 15 Pin	3.50	3.00	2.80
P 0892 DB15 Male PCB Mnt	3.25	3.10	2.98
P 0893 DB15 Female PCB Mnt	3.95	3.75	3.60
P 0895 DB15 Backshell Cvr	2.85	2.90	2.30
P 0900 DB25 Male 25 Pin	4.50	3.95	3.60
P 0901 DB25 Female 25 Pin	4.95	4.50	3.98
P 0902 DB25 Male PCB Mnt	4.50	4.10	3.85
P 0903 DB25 Female PCB Mnt	5.50	5.00	4.70
P 0905 DB25 Backshell Cvr	2.00	2.50	3.98

MASSIVE
SAVINGS
FOR OEM'S!

PHONE OUR WHOLESALE DEPT
(09) 381 7233
ASK FOR STEVE

VINYL BINDER



Holds 12 magazines, each on a spring out wire rod. Just the shot for each year's set of Electronics Australia, ETI or any of your favourite magazine.
Suits all A4 size publications (275 x 210). Very smart Royal Blue colour with beautiful gold embossing.
B 9999 Were \$5.95
Now \$4.00 each.

DIL SWITCHES

GOLD PLATE SELF WIPING CONTACTS



SAVE UP TO 30%

S 3050	4 way	1.35	1.00
S 3060	8 way	1.60	1.25

PROFESSIONAL QUALITY SOLDER SUCKERS

Not to be compared with inferior "Hobby" types. Saves countless hours in fault finding and repair of complex PCB's.
SINGLE HANDED OPERATION
SELF CLEANING PLUNGER
LONG LIFE TEFLOON TIP
DOUBLE DIAPHRAGM
DUAL O-RING SEAL
225mm x 20mm (id)
50mm STROKE
POWERFUL SUCTION



T1240... only \$11.95
T1241. Replac tip. \$1.95

NEW PRODUCTS COMPUTER LEADS

Our superb quality Computer leads are just the shot for interconnecting your computer to printers, modems, terminals etc. Each end is terminated with D25 Series connector. The 25 wire cable is fully shielded and double insulated. Easy access to connector termination is available for interposing connections when necessary. With present day labour costs these leads work out miles cheaper than making your own.

TWO TYPES AVAILABLE
each 1.8m long




Introductory Price
\$24.50 \$16.00
SAVE 33%

P 0862 Male to Male
P 0864 Female to Male

D25 to D25 ADAPTOR

When used in conjunction with either P 0862 or P 0864 any requirement for interconnection can be configured.



P 0860 \$16.50
INTRODUCTORY PRICE
\$12.50

MASSIVE PRICE BREAKTHROUGH! ELECTRONIC BELT DRIVE TURNTABLE BSR QUALITY

Altronics has made a sensational purchase of Belt Drive Turntables - BELOW Manufacturers Cost!! Because of our buy we can pass them on to you at a MASSIVE SAVING. The Turntables are made in England by B.S.R. They are unmounted and suitable for Disco Consoles, 3-in-1's etc. They are also ideal as replacements for existing 3-in-1 sets. (See Specifications). But there is an aspect that is really amazing! You can work the Turntable from 9-12V DC. This means that you can run the unit from a car or truck!! (The A 0612 model can of course run on 240V mains). The Turntable features quality Belt Drive operation, lightweight Transcription type arm, Cueing facility and Stereo Ceramic cartridge with Diamond Stylus. The platter has calibration markings to check speed. A simple neon on 240V will 'strobe' to the markings. Whilst the 33 & 45 rpm speed has been accurately set in the factory, you have the facility to make pitch adjustments underneath the turntable. The DC Motor Drive (as used in the best turntables) is electronically controlled!! Each unit comes with complete instructions. Quantity limited! You will have to hurry to avoid disappointment.

SPECIFICATION

- * Dimensions 330 (W) x 285 (D) x 60 (H) mm overall.
- * Platter Diameter 280 mm.
- * 2 speed 33 and 45 rpm.
- * Pick up Arm Counter balanced type with cueing facility.
- * Pick-up ceramic stereo with diamond stylus.
- * Turntable operation - auto stop, returns to rest automatically.
- * Turntable chassis is sprung on all corners.
- * Output stereo RCA sockets provided.
- * Weight 1.5KG.




AMAZING
LOW PRICE
CAT. A 0612 \$29.95

240V VERSION (includes 12V adaptor)
CAT A 0614 \$39.95

Freight Packing - due to the bulk and weight of this unit - freight is \$5.00 per unit.

Up to 25% off RAINBOW CABLE



Per Metre Price

	M 10M+	25M+
W 0510 10 core	1.00	.90 .80
W 0516 16 core	1.60	1.40 1.25
W 0524 24 core	2.40	2.00 1.80

HOOK UP WIRE SUPER BUY!

LIGHT DUTY TINNED

13/12mm
Hook-up wire 100m reels. Use for all general purpose wiring work, 8 colours.
All One Price \$5.00 per 100m

W 0250 Red	W 0254 Yellow
W 0251 Black	W 0255 Green
W 0252 Brown	W 0256 Blue
W 0253 Orange	W 0257 White

Order a reel of each
(8 reels) pay only \$30.00

MEDIUM DUTY TINNED

14/20mm
Supplied on 100m reels
\$8.00 per 100m

W 0260 Red	W 0265 Blue
W 0261 Black	W 0268 White

Order a reel of each
(4 reels) pay only \$25.00

TELEPHONE TYPE CABLE

Supplied on 200m rolls, enclosed in tough PVC bags in the traditional way. Enables tangle free extraction from centre of roll through hole in the side of PVC bag.



FOUR WIRE

RED/BLACK/BLUE/WHITE

W 0302 per metre	.50
per 200m roll	46.00 35.00

SIX WIRE (Three Pair)

RED/BLACK/BLUE/WHITE/GREEN/ORANGE

W 0303 per metre	.60
per 200m roll	56.00 42.00

20 WIRE (10 Pair)

Pairs 1-5 BLUE/ORANGE/GREEN/BROWN/SLATE with White mates
Pairs 6-10 BLUE/ORANGE/GREEN/BROWN/SLATE with Yellow mates

W 0310 per metre	1.50
per 200m roll	208.00 150.00

ENAMELLED WINDING WIRE

Handy hobby packs - for coil winding etc.



	Metric	B+S	Pack	WERE	NOW
W 0402	.2mm	32	25g	2.95	2.50
W 0403	.25	30	25g	2.95	2.50
W 0404	.4	26	25g	2.95	2.50
W 0405	.5	24	100g	2.95	2.50
W 0406	.63	22	100g	2.95	2.50
W 0407	.8	20	100g	2.95	2.50
W 0408	1	18	100g	2.95	2.50
W 0409	1.25	16	100g	2.95	2.50

TINNED WIRE PACK


.63mm/22g B&S 100g Pack

W 0420	\$2.95
10 up each	\$2.50

BANKCARD HOLDERS — PHONE ALTRONICS TOLL FREE 008-999-007 FOR NEXT DAY JETSERVICE DELIVERY

BANKCARD HOLDERS — PHONE ALTRONICS TOLL FREE 008-999-007 FOR NEXT DAY JETSERVICE DELIVERY

BARGAINS WITH FAMOUS MOTOROLA AND NATIONAL SEMI DATA BOOKS



CMOS DATA

A comprehensive reference covering 40XX, 45XX CMOS family's along with specialty devices such as LCD drivers, telephone and general communication functions and industrial control. 862 pages essential in all spheres of electronics.

B 1105 11.50 9.95

MECL DATA

Emitter Collector Logic (ECL) is today's fastest form of digital logic providing the most direct way of improving system performance. This previously hard to get manual provides data on the 10KH, 10K and 111 families. MECL memory and ALL CHIPS.

B 1100 9.95 7.50

MASTER SELECTION GUIDE

The most useful book ever printed. Covers MOS IC's listed by function. LINEAR IC's listed by function. LSI memory, TTL, ECL power products, SCR's, diodes, transistors listed by application and ratings. Essential data given for all devices. Terrific value.

B 1104 7.95 5.00

BONUS OFFER THE SET OF 9 ONLY \$65

POWER DATA

Motorola are the undisputed world leader in power transistors. Renowned for their low cost and reliability. Book includes a 9 page selection guide, application notes and data sheets for over 700 devices, 989 pages. Previously over \$20.00.

B 1101 12.95 10.00

R.F. DATA MANUAL

The 2nd Edition of the R.F. Data Manual has been updated to incorporate the latest changes since last printing. There are 251 devices and 10 application notes including Tuning Diodes, Hot Carrier Mixer Diodes, Pin Switching Diodes and R.F. Fets. Motorola R.F. family now includes 1.2 GHz pulsed power devices to 325 watt peak output, 2 GHz cw broadband transistors to 16 watt o/p and Power Amplifiers to 20 W o/p for FM 806 to 870 MHz mobile band. A truly list class R.F. Data Book.

B 1110 \$13.50

OPTO DATA

Handy reference provides data and application notes on opto couplers, infra red LEDs, photo transistors and a complete chapter on fibre optics, a communications system which is fast gaining usage world wide. Very Educational.

B 1118 8.95 7.00

LINEAR IC's

Popular data manual. At last readily available. Approx. 800 pages, full data design procedures and equivalent listings for 1000's of devices under headings OP AMPS, VOLTAGE REGULATORS, CONSUMER CIRCUITS (e.g. TV automotive power), HIGH FREQUENCY CIRCUITS and SPECIAL PURPOSE CCTS.

B 1114 9.95 7.50

MEMORY DATA

An absolute must for the enthusiast and engineer alike. This is the latest reprint of Motorola's famous memory data manual and includes the latest specifications and design application data on 1T1 RAM, 1T1 PROM, MECL MEMORY, DYNAMIC RAM, MOS STATIC RAM, MOS EPROM, MOS E2 PROM and MOS ROM. Worth many dollars more.

B 1113 8.95 7.00

SCHOTTKY TTL DATA

Essential reference for the enthusiast and engineer alike. Designing, building and servicing digital circuitry is an absorbing pastime. Data for the L.S. and F.F. families along with design considerations and circuit characteristics are logically presented in this manual, making it quick and easy to use.

B 1109 9.95 7.50

Please Allow \$6 Road Freight Per Set

BONUS OFFER THE SET FOR ONLY \$59

NATIONAL SEMI

THE INTERFACE DATABOOK

In National Semiconductor's interface Databook, 702 pages of specifications describe one of the industry's broadest lines of interface products. Over 300 data sheets have been compiled, covering transmission line drivers/receivers, bus transceivers, peripheral power drivers, level translators/buffers, display drivers, MOS and magnetic memory interface circuits, microprocessor support circuits, applicable TTL and CMOS logic circuits. An industry reference guide gives National Semiconductor's exact replacement for 7 other manufacturers. Product selection guides and a complete product applications section make it easy to find the correct part number for these specialised IC's.

(702 Pages)

B 1005 11.50 10.00

TRANSISTOR DATABOOK

National Semiconductor has added many new transistors and product families since publication of the last data book. Many have already been widely acclaimed by users. In addition to small-signal power bipolar and field effect transistors that have been the mainstay of our catalog, there is a section for multiple-effect transistors. More part numbers will be added as market needs expand. To keep current on all new National transistors, please contact your National sales representative or franchised distributor and ask to be placed on the customer mailing list.

(558 Pages)

B 1050 11.50 10.00

LOGIC DATABOOK

National's new Logic Databook covers all of their logic families: TTL (54/74), Schottky 54S/74S, low power Schottky (54LS/74LS), High speed (54H/74H), and low power (54L/74L). The Logic Databook—especially organised for quick and easy referencing—offers two complete functional indices and selection guides, one for SSI and one for MSI devices. In addition, it includes over 100 connection diagrams and test waveforms to help speed the design-in cycle. All in all, it's probably the most comprehensive collection of practical information ever assembled on such a broad line of practical components.

(624 Pages)

B 1015 9.95 8.95

CMOS DATA BOOK

This databook contains information on National Semiconductor's standard SSI/MSI CMOS products. This includes the popular 54C/74C series logic family, which is pin for pin, function for function equivalent to the 7400 family of TTL devices. All device outputs are LPTTL compatible, capable of sinking more than 360uA (= 1 LSTTL load). The AC parameters are specified with a 50pF capacitive load. In addition this book describes National Semiconductor's extensive line of CD40XXB and CD40XXS series devices. These parts meet the standard JEDEC B-Series specifications. Special Function LSI A/D Converters and Memory device specifications contained herein offer the designer unique high-density low-power system solutions. All devices are compatible with 54C 74C series and CD40XXB series products.

(842 Pages)

B 1030 11.50 9.50

VOLTAGE REGULATOR HANDBOOK

With the variety of fixed and variable-regulator technology currently available, the 336-page Voltage Regulator Handbook becomes a test for the selection of three-terminal and dual tracking components that meet the system requirement while utilizing the most cost effective approach. Beginning with product selection procedure and a data sheet summary, the text continues with easily accessible information about booster circuitry, power transformer and filter capacitor selection, test methods, manufacturers' cross reference and extended use applications for National's regulators.

(336 Pages)

B 1055 9.95 8.95

LINEAR DATABOOK

The new 1983 edition of the National Semiconductor Linear Databook is the most comprehensive available. It presents approximately 2000 pages of specifications for high-technology linear products within its two volumes. Applications, descriptions, features and diagrams in this databook include detailed sections for Voltage Regulators, Op Amps, Voltage Comparators, A to D, D to A Converters, Industrial Blocks and Audio, and TV Circuits. The Databook also features advanced telecommunication devices and speech synthesis DIGITALKer plus other non-state-of-the-art linear products offering performance economy quality and reliability.

B 1010 (Vol.1) 12.50 7.50

B 1011 (Vol.2) 12.50 7.50

HALF PRICE Z80 A

FAMOUS SGS BRAND FULL SPEC



Z9001 CPU WAS \$8.95 NOW \$4.50

Z9005 PIO WAS \$8.95 NOW \$4.50

DIODES SLASHED

			NOW	100 UP
Z 0101	1N914/1N4148 Diode	5c	3c	
Z 0105	1N4002 100V 1 Amp	6c	4c	
Z 0109	1N4004 400V 1 Amp	8c	5c	
Z 0112	1N4007 1000V 1 Amp	10c	7c	
Z 0115	1N5404 400V 3 Amp	18c	15c	
Z 0118	1N5408 1000V 3 Amp	20c	17c	
Z 0120	R250A 400V 6 Amp	50c	50c	



SUPER BRIGHT HIGH INTENSITY SEIMENS 5mm RED LEDS

WERE 50¢ SAVE A FORTUNE!
CAT 1-9 10-99 100 UP
Z0155 22c 19c 15c

LOGIC PROBE

Q1272 WAS \$29.50

ONLY \$19.50

• Directly powered from circuit under test (5V) • Tested to 12.6 MHz • DTL/TTL — CMOS Threshold selector • Circuit loading 30uA approx. • High-Low — pulse or memory led indication. Impulse mode pulse length is extended to enable visual observation. In memory mode any detected level is continuously displayed until reset.

SECURITY EQUIPMENT

ALARM CONTROL MODULE

EASY TO INSTALL • BUILT IN SIREN DRIVER — DIRECTLY DRIVES LOW COST 8 OHM HORN SPEAKERS, SIREN HORNS AND MECHANICAL BELLS • LOW POWER 12V DC OPERATION.



\$5042. Only \$39.50

MINI BUZZER 1.5-5V DC

SENSATIONAL LOW PRICE

Handy little solid-state audio "Buzzer" or signalling device. Just the shot for communicator panels, or for timer alarms or in the car. Polarity conscious.

\$5062 \$1.95 Now \$1.00 ea.

PIEZO ALARM

Similar to "Sonalert" type. Absolutely ear piercing sound. Recommended voltage 5-15V DC. Ideal for almost all audio signaling applications, i.e. fire, water and gas signalling, computer alarms, etc.

\$5066 \$4.95


NOW \$3.50

DUAL FUNCTION TYPE

Same physical dimension as S 5066. Gives either a pulsed output (siren) or a continuous tone. 3 wire connection enables selection of either output.

\$5070 \$5.95 Now \$4.00 ea.


HIGH SECURITY LOCK SWITCH



\$2510 \$8.95

Now \$5.00 ea.

KEY OPERATED SWITCH



\$2500 \$6.95

Now \$3.50 ea.


WEATHERPROOF SIREN HORN

12V DC operated - Deafening Siren Wail. Superhandy for audio, signalling, security systems etc. Current drain 500 MA approx. Completely weatherproof. Attractive off-white PVC finish.

\$5058 \$22.50 Now \$15.00 ea.

LOW COST WEATHERPROOF HORN SPEAKER

5 WATT 8 OHM



C2010

\$9.50

Now \$6.50

Fully weatherproof. New unique voice coil construction ensures high dependability on full drive.

Suitable for PA intercom and security systems etc.

Reed Switch and Magnet Sets

Fully Encapsulated Self adhesive or Screw Mount.

\$5055 N/C Reed and Magnet

Were \$2.50 Now \$1.50

\$5056 N/O Reed and Magnet


Were \$2.95 Now \$1.75

\$5053 SPDT changeover Econ Type


Were \$2.50 Now \$1.50

N/C denotes normally closed contacts when magnet in proximity of switch.

N/O denotes normally open contacts when magnet in proximity of switch.



Construction. The components are mounted on the copper side of the board, note. Two stiff wires soldered to the sensor/blaster pad hold the cheese. Four stick-on feet are attached beneath the board.



For a guide to buying components and kits see **SHOP AROUND** this issue.

PARTS LIST — ETI-1524

Resistors.....all ½W, 5% unless noted
R1.....22M, 10% ½W or 1W
Philips CR50 or similar

R2, R4.....1M
R3, 5, 7.....10k
R6.....220R
R8.....330R
R9.....470R
R10, R11.....220k

Semiconductors

D1-7.....1N914, 1N4148
D8.....1N4004
D9.....MR856 fast recovery diode
IC1.....MOC3021
Q1.....PN4250
Q2.....BC549, BC109
Q3.....S2600M (RCA) SCR, or
C122E, TIC126E

Capacitors

C1.....1n disc ceramic
C2.....100n metallised poly
C3.....150µ/16 V axial electro.
C4.....10n/400 V (250 Vac)
mains-rated metal foil
plastic cap.
C5.....2µ/7/400 V (250 Vac)
mains-rated metallised cap
(Siemens, type B32231 or
similar self-healing type)

Transformers

T1.....240 V/9 V — ct, Dick Smith
2840 or similar
T2.....see text

Miscellaneous

ETI-1524 pc board; 'UB-1' zippy box (157 x 95 x 50 mm); cable clamp; fuseholder; F1 — 0.25 amp 3AG fuse; mains cable and 3-pin plug, 3-way terminal block; Ferrite aerial rod 9 x 194 mm (approx.), e.g. DSE L-1401; 7-8 metres of 1 mm diameter enamelled copper wire; 30-odd metres of 0.16 mm enamelled copper wire; insulation tape; glue (see text); nuts, bolts, etc.


Price estimate: \$28-\$30

which would be close-coupled even without the core. The choice of ferrite as a core material was made purely because it is readily available; transformer iron would be much better and if you can get some, use it by all means.

To make the mousetrap easy and safe to build I chose to use a rather unusual construction method where the components are mounted on the same side as the copper. This enabled me to use only one board and at the same time keep all the nasty bitey voltages safely enclosed. It's a bit more tedious to assemble but means the final trap is cheaper to make. A plastic jiffy box covers all the works and gives the project a nice neat appearance.

Construction


The first and most tedious part of building the mousetrap is to wind the coil. First the core material must be prepared. I used a



ELLISTRONICS

PTY LTD


797 SPRINGVALE RD. MULGRAVE, MELBOURNE, VIC. 3170. PH:(03)561 5844 TELEX AA37758 LSTRON
SUITE 18. 47 FALCON ST. CROWS NEST, SYDNEY N.S.W. 2065 PH:(02)922 3220 TELEX AA37758 LSTRON




FAST

\$1-12

The 74F153 is a high-speed dual 4-input multiplexer with common select inputs and individual enable inputs for each section. It can select two lines of data from four sources. The two buffered outputs present the data in the true (non-inverted) form. In addition to multiplexer operation, the 74F153 can generate any two functions of three variables.




The 74F138 is a high speed 1-of-8 decoder/demultiplexer. This device is ideally suited for high-speed bipolar memory chip select address decoding. The multiple input enables allow parallel expansion to a 1-of-24 decoder using just three 74F138 devices or a 1-of-32 decoder by using four 74F138 devices and one inverter.




\$1-26

\$2-80

The 74F374 is a high speed, low power octal D-type flip-flop featuring separate D-type inputs for each flip-flop and 3-state outputs for bus-oriented applications. A buffered Clock and Output Enable are common to all flip-flops.



The 74F109 consists of two high-speed completely independent transition clocked JK flip-flops. The clocking operation is independent of rise and fall times of the clock wave form. The JK design allows operation as a D flip-flop by connecting the J and K inputs together.




.65¢

PLUS 20% TAX
IF APPLICABLE

RELATIVE TRANSISTOR SIZES IN VARIOUS TTL FAMILIES FAST ADVANTAGES

- Improved Circuit Speed/Power Performance.
- Improved Noise Immunity.
- Better Line Driving Characteristic Than Schottky.
- Reduce Input Loading and Increased Fan Out.
- Maintain Compatibility to Standard TTL Levels, Functions and Pin Outs.



Bankcard
Mail Orders
Welcome

Please debit my Bankcard
Bankcard No.
Expiry Date
Name
Signature


Prices subject to change without notice. Phone or write for quantity discounts.
MAIL ORDERS: To ELLISTRONICS, 797 SPRINGVALE RD MULGRAVE 3170
Minimum pack and post \$2.00. Phone (03) 561 5844

ELUSTRONICS

PTY LTD

797 SPRINGVALE RD. MULGRAVE, MELBOURNE, VIC. 3170. PH:(03)561 5844 TELEX AA37758 LSTRON
SUITE 18. 47 FALCON ST. CROWS NEST, SYDNEY N.S.W. 2065 PH:(02)922 3220 TELEX AA37758 LSTRON

FAST




* TUBE LOTS

74F00PC	.51
74F02PC	.53
74F04PC	.53
74F08PC	.53
74F109PC	.65
74F10PC	.53
74F11PC	.51
74F138PC	\$1.26
74F139PC	\$1.12
74F151PC	\$1.12
74F153PC	\$1.12
74F157PC	\$1.30
74F158PC	\$1.12
74F161PC	\$2.50
74F164PC	\$1.39

* TUBE LOTS

74F175PC	\$1.73
74F181PC	\$2.90
74F182PC	\$1.65
74F189PC	\$4.56
74F190PC	\$2.48
74F191PC	\$2.80

* Prices
single item
in Tube Lots.



* TUBE LOTS


74F194PC	\$1.50
74F20PC	.49
74F240PC	\$2.20
74F241PC	\$2.20
74F243PC	\$2.70
74F244PC	\$2.20
74F245PC	\$5.45
74F251PC	\$1.20
74F253PC	\$1.05
74F257PC	\$1.26
74F258PC	\$1.25
74F283PC	\$2.66

* TUBE LOTS

74F32PC	.59
74F350PC	\$2.20
74F352PC	\$1.22
74F353PC	\$1.22
74F373PC	\$2.48
74F374PC	\$2.80
74F379PC	\$1.55
74F399PC	\$1.65
74F521PC	\$2.60
74F533PC	\$2.89
74F534PC	\$2.63
74F537PC	\$3.54
74F539PC	\$4.30
74F64PC	.63
74F74PC	.55
74F160PC	\$2.50
74F162PC	\$2.50
74F163PC	\$2.50
74F174PC	\$1.49

* TUBE LOTS

74F381PC	\$3.55
74F382PC	\$3.68
74F398PC	\$2.70
74F538PC	\$3.55



HIGHEST PERFORMANCE
FAMILY OF THE 80s

Fairchild Advanced Schottky TTL, FAST, is a family of TTL circuits that exhibits a combination of performance and efficiency unapproached by any other TTL family. Made with the proven Isoplanar process, 54F/74F circuits offer the switching speed and output drive capability of Schottky TTL, with superior noise margins and only one-fourth the power consumption.

LARGER QUANTITIES
PRICES ON APPLICATION

PRODUCTS MANUFACTURED BY

FAIRCHILD

A Schlumberger Company

ONE OF THE WORLDS LEADING
SEMICONDUCTOR MANUFACTURERS

ferrite rod stocked by Dick Smith (cat. no. L-1401) but, as mentioned, transformer iron would probably be better. If you want to stay with the ferrite it must first be cut in half. To do this, measure off *exactly* half way on the rod and score it with a three corner file. Score a nick all the way around the rod then, holding the rod firmly both sides of the score, tap the rod firmly against the edge of a table or somesuch so the rod is given a sharp blow on the score. It should break cleanly on the score.

Ferrite is very brittle stuff so don't smash it down — you'll break it into a trillion pieces. A firm rap is sufficient. Next, glue the two pieces together side by side to make a double thickness rod. Araldite or some form of superglue will do fine here.


If you want to use iron (or can get it!) use "I" laminations 100 mm long by 8 to 10 mm wide and the stack should be about 7 to 8 mm thick. Whatever core you use the next thing is to completely insulate it. As the primary winding goes directly over this insulation and the primary has 300 V imposed across it, it's a good idea to be sure about this layer.

Using ordinary plastic insulating tape, wind a double thickness layer over the core. Wind it so each turn of tape overlaps the previous turn by slightly over half. In this way you have a double layer covering with no single layer gaps (but make sure that the turns do actually overlap by the bit more than half).

The primary winding is the next to go on and consists of four parallel windings of 1 mm diameter wire (say, 18 B&S). You will need about five metres of wire cut into four equal lengths. Four parallel windings are used for two reasons. Very high currents flow in the windings and you want the power to go into the mouse, not copper losses, and also using four wires gives a nice flat surface to build the secondary winding on.

Make sure that the four wires are straight then, holding all four side by side, start winding them around the insulated core. As the wire is nice and thick there is no need to tape down the start end of the winding — when you bend it around the core it should stay put. Wind twenty turns on so they're exactly close spaced with no gaps whatever between the wires. It's important that the wires lie flat as a secondary must later be built up over this layer and bumps become a damn nuisance. Both ends of this winding should come out to the one side of the core so they can be terminated easily on the board. If you're using the ferrite core they should come out along the narrow axis of the core.

Next, using fine, long-nosed pliers, bend the four wires sharply so they protrude out the ends of the core (see diagram). It doesn't particularly matter if you damage the insulation as there isn't any voltage between the turns and its more important to keep the coil neat. Do both ends the same then wind another layer of insulating tape over the completed primary winding the



same as you did for the core insulation. You'll have to hold the ends of the winding down when the layer of tape is wound on. Take the tape right over the ends of the core then trim them back flush with the core. It's very important that the primary be properly insulated as it's connected (through resistors, but still connected) to the mains and we'd prefer not to have you hurt yourself!

As most tapes can only be relied on for about 500 V, and the secondary goes directly over this covering, one double layer is nowhere near enough to insulate it. Wind on another *five* layers using the same technique, so each layer gives a double thickness of tape, and winding each layer so it spirals in the opposite direction to the layer under it. This makes for a great lump of a coil but ensures that no flashovers occur. Each layer of tape should be taken right over the ends of the coil then trimmed back.

Now comes the fun bit — winding the secondary. I used 0.16 mm (say, 34 B&S) diameter wire. It is entirely too easy to break, so be warned! You'll need about 30

metres of wire, which works out at about seven grams weight, unless my calculator is in error. To protect and insulate the ends of the wire, cut two pieces of silicone rubber sleeving about 50 mm long and slip one piece over the end of the wire so about 100 mm protrudes.

Then, using a piece of insulating tape 10 mm long, tape the start of the wire down on one end of the coil so the tape covers half sleeving and half bare wire. The wire should be 10 mm in from the end of the coil and perpendicular to the long axis.

Now start winding on the secondary so each turn is tight (not too tight!) and laying hard up against the turn before. A very good idea here is to cut a piece of tape and, as you wind 7 or 8 mm of coil, tape the winding down. As the winding progresses, move the tape along so if you drop the coil you don't have to do the whole thing again! Each turn of the winding develops 15 V so you must be careful not to allow any windings to overlay other turns — if you get a shorted turn the coil is absolutely useless.

Keep on winding until you get to within 10 mm of the other end and you should have 75 to 80 mm of even, tight-spaced copper wire. If there are some narrow spaces between some of the windings it doesn't particularly matter but don't have too many — you're throwing away volts. Cut off the end of the wire so you have 100 mm of free end and slip the second piece of sleeving over it. Using another piece of tape terminate the free end the same as you did for the start. Then cover the whole secondary with a double layer tape winding and the coil is finished.

At this stage I checked out the coil in the following manner. Connect the 2.7 μ F capacitor, used for C5 in the final circuit, in parallel with the coil primary and connect the two to your audio oscillator. Measure the ac volts across the parallel circuit and adjust the frequency until you find the resonance. For my coil it occurred at 19 kHz and was very sharp (3 dB down only a few hundred Herz either side of resonance). With the primary at resonance, measure the secondary voltage and you should find it 20 times the primary voltage. If you find the coil has a very poor Q you probably have a shorted turn somewhere so you'll have to find and fix it. I didn't try making an iron-cored coil so I can't give figures but I'd expect that the resonant frequency would be lower (maybe around 10 to 15 kHz) and the Q would probably be lower too due to iron losses.

The next step is to make the printed circuit board. If you've bought a kit, this is the easiest part as it's ready-made. But if not, use the layout given. As the components are not passed through holes in the board as normal, avoid using paper-phenolic board material as the copper tends to come off easily. Stick to the epoxy-glass-type where the copper bonding is better.

After you've made the board, assemble it according to the layout given. The compo-

nent leads are formed by bending them down sharply as if you were going to solder them in a normal board with holes then, with pliers, bending the leads out flat again shown in the drawing above the component layout. Pre-tin all the pads that have components attached, then hold the components in place and solder them in. The power transformer centre tap is cut off short as it isn't needed. Use countersunk-head screws to mount the transformer and mains terminal block and mount them in place also. The two power transformer secondary leads go onto the two round pads.

Before attempting to tin the cut ends, hold the coil so the ends of the wires are resting on the edge of a table and scrape away all the enamel insulation where you want the solder. This enables the solder to "take" quickly and doesn't let things get too hot. The plastic insulating tape in the coil is not at all tolerant to heat and if you let things get too hot when tinning the leads the coil may flash over in use. When actually tinning the ends be as quick as possible and try to cool them as soon as they're done. I used a pressure pack cold spray to freeze them after they were tinned.

Attach the coil to the board using double-sided adhesive foam strip. This can be bought from any hardware store and solder the primary leads to their pads. Trim back the silicone sleeving to the right length so the secondary leads lie neatly on their pads. Being careful not to damage the wires inside, tin the leads (no worry here about excess heat) and solder them to the board.

Cut and bare back the two mains leads from the mains transformer so there's a bit of slack when they're inserted into the terminal block. You only need 6 or 7 mm of bare wire and I won't labour the point about having bare wire protruding from the terminal block being dangerous. Use the pieces of wire you cut off the transformer to connect to the resistors R10 and R11. Bare the same amount of wire as you did for the transformer, twist the transformer leads together with the pieces of wire and connect them to the terminal block. Solder the other


Take the piece of earth lead you originally cut off and cut it to 50 mm long. Bare 10 mm of wire at each end. Twist the end of this piece together with the bared end of the earth lead from the flex and solder them together then clamp the soldered end in the terminal that is NOT connected to the transformer. Solder the other end of the earth lead that's protruding from the terminal block to the ground on the board, using lots of solder and make absolutely sure that it has properly taken. The graveyards are full of people who thought "Yeah! yeah! I'll fix the earth up later" so make *absolutely and positively sure* that you can trace the earth from the flex to the terminal block then out again directly to the ground on the board. When you're quite satisfied that all is well, connect the neutral from the flex to the terminal block so blue wire goes to blue wire.

Finally, cut a hole in the plastic jiffy box where you are going to mount the fuse holder and clamp it in place. Loop the bared end of the active (brown) lead through the end terminal of the fuse holder and solder it in place. Bare the ends of the spare piece of active lead you have and solder one end of the wire to the side terminal of the fuse holder and tape up both soldered joints as best you can (or slip on heatshrink tubing beforehand). Connect the other free end of the active lead from the fuse holder and the mousetrap is wired up. Attach a three-pin plug to the end of the flex, paying attention to the active and neutral pins on the plug, and you're ready to start testing.

Testing it


Testing is quite straightforward. Plug in the trap and turn it on with the jiffy box cover off to one side. Watch to see that nothing bursts into flames. Then, using your DVM, check that the trigger circuit power supply is in fact generating about 13 V. Next, check that the main dump capacitor, C5, has in fact fully charged to about 300 V. Measure the voltage between the anode of the SCR and either end of the coil primary (the anode of the SCR is the case). Bear in mind that the energy stored in the capacitor here is *dangerous*.

If all is well, you can try triggering the trap by touching the base of Q1 with your multimeter probe while the other probe is earthed. There should be a clear, audible click when it fires. The final test is to actually trigger the trap with a 1M resistor. Earth one end of the resistor (I used a lead with alligator clips on either end) then gently touch the centre electrode with the other end. Once again you should hear the click. If you increase the resistor to 2.2 megohms, the trap may or may not trigger and higher values don't work at all. As a final test, try triggering the trap with a 2k resistor. This is just the right impedance to get the full benefit of the trap. When it fires, it will blow the side out of the resistor! If you get a satisfactory "splat" and a destroyed, open-circuit resistor, all you need to do is screw on the lid, bait your trap (when it's off!) then go hunting mice.



ment leads are formed by bending them down sharply as if you were going to solder them in a normal board with holes then, with pliers, bending the leads out flat again shown in the drawing above the component layout. Pre-tin all the pads that have components attached, then hold the components in place and solder them in. The power transformer centre tap is cut off short as it isn't needed. Use countersunk-head screws to mount the transformer and mains terminal block and mount them in place also. The two power transformer secondary leads go onto the two round pads.

Before attempting to mount the coil, it's



ends of the pieces of wire to the pads on the board and assembly is almost complete.

Strip back the outer insulation of the mains flex for about 250 mm then cut off all three (if you only have two you've got the wrong sort of flex!) leads 120 mm from the end of the outer insulation. Cut the active lead to 100 mm and bare 10 mm of the end. Trim the neutral lead (blue) so it protrudes 50 mm from the cable's outer insulation. Bare the neutral and earth lead ends from 10 mm and clamp the flex to the board with a cable clamp.

NEW PRODUCTS

TRAVELLERS WORLDWIDE ADAPTOR PLUG

The all in one travel plug for use all over the world. The SUPER-PLUG is an international Travel Plug Adaptor designed to take standard 2 pin plugs plus the Australian 3 pin and adapt them to fit 2 and 3 pin mains socket outlets throughout the world.

It's quick and easy to use, you simply insert your standard 2 pin plug at one end and select the required pins at the other end and hey presto you're instantly connected.

Now you can take with you all those electrical appliances such as Hairdryers, Styling Brushes, Heated Curlers, Shavers, Electric Toothbrushes etc without having to change plugs. SPECIAL NOTE: Super-plug is a worldwide socket adaptor, it does NOT allow for voltage changes and is for use only with non-earthed appliances having 2 wire cords.



\$16.95

Purchase one of these adaptors in August and we will give you a JET PHONE ADAPTOR for only \$4.50 - That's 1/2 PRICE!!

USE SUPER-PLUG IN THE FOLLOWING COUNTRIES:

☆ Africa ☆ Austria ☆ Australia ☆ Belgium ☆ Bermuda ☆ Brazil ☆ Canada ☆ Caribbean ☆ Chile ☆ Denmark ☆ Egypt ☆ Finland ☆ France ☆ Germany ☆ Great Britain ☆ Greece ☆ Hong Kong ☆ Ireland ☆ Italy ☆ Japan ☆ Holland ☆ Mexico ☆ Middle East ☆ New Zealand ☆ Norway ☆ Philippines ☆ Portugal ☆ Spain ☆ Sri Lanka ☆ Sweden ☆ Switzerland ☆ Venezuela ☆ USA

Fits all these plus many other parts of the world.
Cat. PA-4200

LARGE COLOUR LED DISPLAYS!

Jaycar is proud to announce a NEW range of 7 segment LED displays featuring LARGE digits and alternate colours!

NOTE THE LOW PRICES!!

Cat. No.	DESCRIPTION	1-9	10+
ZD1870 0.4" (10mm)	Comm Anode Red	\$1.00	0.95
ZD1875 0.6" (15mm)	Comm Anode Red	\$2.50	\$2.25
ZD1880 0.6" (15mm)	Comm Cath Green	\$2.95	\$2.50
ZD1885 0.6" (15mm)	Comm Cath Yellow	\$2.95	\$2.50

All devices have connection data supplied.




★ ★ AMAZING ★ ★ SOLDER BREAKTHROUGH Solder Paste In A Tube!!

Jaycar is proud to announce a new breakthrough in soldering.

Supa Solder is an extremely versatile and easy to use soldering compound that contains tin, silver and non toxic chemicals to enable quick low temperature melting super penetration and outstanding bonds.

UNBELIEVABLE



To use just put some paste on the joint to be soldered and heat up with a cigarette lighter. Suitable for use on brass, bronze, nickel, stainless steel, copper base metals and steel.

FEATURES:

- ☆ low melting point of 222°C
- ☆ 8 times stronger than lead solder
- ☆ easy to use, no waste
- ☆ joins ferrous and non-ferrous metals with the heat from a cigarette lighter
- ☆ non toxic, contains no lead, zinc or cadmium
- ☆ highly conductive

Cat. NS-3000

\$7.95

Supplied in a handy dispenser

DISCONTINUED SPECIALS

STRICTLY LIMITED QUANTITIES

MOVING COIL CARTRIDGE

We can't understand why it didn't sell! High output, top quality cartridge. You don't need any special transformer.
Cat. AA-0210

**WAS \$49.50 NOW \$39.50
SAVE \$10.00**

6 x 9 CAR SPEAKER

This quality speaker has a built-in tweeter and midrange and can handle 60 watts. Great sound.
Cat. AK-0812

**WAS \$39.50 NOW \$29.50
SAVE \$10.00**

CAR CASSETTE PLAYER

If you're selling your car and need a hole filler, this is it. Guaranteed.
Cat. AC-1504

**WAS \$34.95 NOW \$24.50
SAVE OVER \$10.00**

REEL TO REEL TAPE

We had this on special 12 months ago and sold mountains of it. We found another boxfull in the warehouse. 2500', 10" tape, metal reels, NAB.
Cat. AL-1560

**WAS \$19.95 NOW \$9.95
SAVE OVER 50%**

CAR STEREO FADER SWITCH




The usual black type with faders for front/rear, left/right and two switches to switch either front or rear off.
Cat. AX-3502

**WAS \$9.95 NOW \$6.95
SAVE \$3.00**

5' HELICAL CB WHIPS

Includes base and cable. Quality Mobile One brand.
Cat. DC-3030

**WAS \$29.50 NOW \$19.50
SAVE \$10.00**



RIBBON TWEETER


**SAVE \$16.95
NORMALLY \$36.90**

**AUGUST ONLY SAVE A
FURTHER \$5.00**

NOW ONLY \$14.95

Unique regular phase design drives the entire diaphragm, uniformly and completely in phase over the full frequency range. The performance of an electrostatic speaker with the ruggedness and ease of use of a dynamic.

★ 91dB sensitivity ★ 5,000 - 40,000Hz ★ 50W system power ★ No voice coil
Cat. CT-2042



VHS PLASTIC TAPE BOX

Quality plastic box to keep your tapes in 1st class condition.
Cat. AX-6592

**WAS \$2.95 NOW \$1.95
SAVE \$1.00**

Some BETA also available
Cat. AX-6590

**WAS \$2.95 NOW \$1.50
SAVE OVER \$1.00**

**Jaycar
ELECTRONICS**

Incorporating
ELECTRONIC AGENCIES

NUMBER 1 FOR KITS

SHOWROOMS

SYDNEY

117 YORK STREET

Tel: (02) 264 6688 & (02) 267 1614

Telex: 72293

CARLINGFORD

Cnr. CARLINGFORD & PENNANT

HILLS ROAD

Tel: (02) 872 4444

CONCORD

115-117 PARRAMATTA ROAD

Tel: (02) 745 3077

HURSTVILLE

121 FOREST ROAD

Tel: (02) 570 7000

**MAIL ORDERS
& CORRESPONDENCE**

P.O. BOX 185

CONCORD, 2137

Tel: (02) 745 3077


30W + 30W STEREO PREAMPLIFIER

★ Fully built and tested ★ Separate Bass, Treble, Balance and Volume controls ★ Less than 0.1% distortion ★ Mic, Phono and Aux inputs (line) ★ Power supply components on board.

Back at last! No hassle amplifiers. Just connect a transformer, speakers a signal and you're away!

STAGGERING VALUE


ONLY \$34.95



RACK CABINETS

Beautifully crafted all Aluminium rack cabinets with top and bottom removable panels. Plain or black finish. Ventilated lid. Deluxe brushed anodised front panel. Supplied in flat pack but takes only minutes to put together. Dimensions conform to International Standard.

Cat. No.	Finish	Price 1-4	Price 5 up	Front panel ht.
HB-5411	Natural	\$45.00	\$42.50	44mm
HB-5413	Natural	\$55.00	\$52.50	44
HB-5415	Natural	\$59.95	\$55.00	88
HB-5410	Black	\$45.00	\$42.50	88
HB-5412	Black	\$55.00	\$52.50	132
HB-5414	Black	\$59.95	\$55.00	132



Cat. KA-1118

**VIDEO
ENHANCER**

REF: EA OCTOBER 1983

The Jaycar kit includes the box and Scotchcal label.

\$35

JAYCAR - WELCOMES YOU TO A WONDERLAND OF ELECTRONICS

WHAT ARE STICKIES?

As you can see, 'stickies' are stick-on templates. Attach the template to a panel (note the crosshairs for accurate alignment) and proceed to cut out a perfect hole! The plastic film also protects the panel from scratches while you are working on it.

Stickies are available for the common irregular hole cutouts i.e. Cannon DB-25, XL series chassis plug and socket and IEC-320 chassis (mains) plug.

Cat. No.	Description	Price
NL-4010	25 way 'D' template - pkt 6	\$1.95
NL-4014	XLR-31 series template - pkt 6	\$1.95
NL-4018	XLR-32 series template - pkt 6	\$1.95
NL-4020	IEC 320 chassis plug - pkt 6	\$1.95
NL-4024	DIN chassis socket - pkt 6	\$1.95

THE RED FLASHER

Car theft has risen dramatically recently, is your car safe? Thieves stay away from cars which have those expensive flashing light alarms. The ones with the red square push button switch that flashes.

Now you can make your car look like it has one of those alarms, whether you have one or not.

We supply a quality Swiss push button illuminated square switch and the electronics to make it flash. We even put in 2 deterrent stickers.

ALL THIS PEACE OF MIND FOR ONLY \$20.95

Cat. KJ-7000

ONLY \$20.95

ETI 330 DELUXE CAR ALARM

KIT - We have sold hundreds of this brilliant car alarm. Its been replaced by the ETI 340 and we are overstocked! Reference ETI July 1981.

It has a dash mounted flashing light to deter would-be thieves, an alarm trip light to tell you if the alarm's been triggered, and entry and exit delays - you don't need to remember to switch the unit on. Compact design housed in a rugged die cast box. Alarm triggers a relay which switches the car's horn on at one second intervals.

WAS \$29.50 NOW \$22.50

SAVE \$7.00

QUALITY "AIRPAX" DC CIRCUIT BREAKER

Unbelievable bargain! Quality Airpax US MADE unit features large on/off rocker switch and snap-in panel mount capability.

★ Trip current 10 amps ★ Full load 8 amps @ 50V DC

★ Delay 59ms ★ Measures 35(d) x 40(h) x 18(w)mm

body only.
Cat. SY-4080

ONLY \$2.95 each
10 or more \$1.95 each



TELEPHONE EXTENSION LEAD \$34.50

10 metres in length. You can now have your telephone exactly where you want it. Perfect for those confined to bed, or for business, or around the pool.


Cat. YT-6000

KEYLESS CAR ALARM

You will never forget to switch the alarm on when you leave your car as it does it automatically when you remove the ignition key. The alarm is incredibly easy to wire up, and comes complete with cable, door switches and an aluminium siren with all of the electronics built in the rear.

Cat. LA-5315

WAS \$49.95
AUGUST ONLY \$39.95
SAVE \$10.00



POST & PACKING CHARGES

\$5 - \$9.99	\$1.50
\$10 - \$24.99	\$3.20
\$25 - \$49.99	\$4.50
\$50 - \$99.99	\$6.50
\$100 - \$198	\$8.00
Over \$199	\$10.00

**COMET ROAD FREIGHT
ANYWHERE IN AUSTRALIA
ONLY \$12.00**

SHOP HOURS

CARLINGFORD, CONCORD &
HURSTVILLE

Mon - Fri: 9 am - 5.30 pm

Sat: 9 am - 12 pm

Thurs Night: 8.30 pm (Not Concord)

SHOP HOURS SYDNEY

Mon - Fri: 8.30 am - 5.30 pm

Sat: 8.30 am - 12 pm

Thurs Night: 8.30 pm

MAIL ORDER BY



bankcard


**VIA YOUR
PHONE**

MasterCard

VISA

150W BASS GUITAR AMP


Robert Irwin



FEATURES

ETI-1410 BASS GUITAR AMP

- 150 W RMS output into 4 ohms using the renowned ETI-499 MOSFET module
- High gain and low gain inputs
- 6-band graphic equaliser; 50, 100, 250, 500, 1k and 3k Hertz
- Line output facility
- Bi-amp facility
- Output limiter to avoid power amp overdrive
- Housed in a standard 19" rack-mount case.



Block Diagram. Overall arrangement of the project. Designed by a bass player, for bass players — no wucking furries. The main power amp uses the ETI-499 150 W MOSFET module, a proven reliable performer.

This guitar amp for impecunious bass players features many facilities found on expensive 'bought' ones. It delivers 150 watts into 4 ohms, has a 6-band graphic, limiter, line out and bi-amp facilities.

THERE HAVE BEEN many requests over the years from the growing numbers of build-it-yourself musicians for some good quality musical projects, particularly for stage amps of various descriptions. In the past, ETI has published some excellent power amp designs such as the old faithful '480 module, and in more recent times the '490 MOSFET module. Both of these amps are very suitable as the driver stage in a guitar or keyboard stage amp but, up until now, there have been no designs published for really suitable preamp stages to go with them. This has meant that these power modules have been primarily used in PA applications where they have been driven from a mixer or small mixing preamp.

This project describes a complete 150 W bass guitar amp using the ETI-499 MOSFET power amp module. The amp is housed in a standard 19" rack-mount case which allows it to be dropped into a standard wooden road case or mounted in an amp rack. The preamp contains features

HOW IT WORKS — ETI 1410

This article describes the design and construction of the preamp, equaliser, and 12 V power supply sections of the Bass Guitar Amp, so only these three items are covered here. The other sections are covered in Part 2.

ETI-1410a PREAMP

This is the input board. It comprises three main sections. IC3 is a 5534 op-amp configured as an inverting amplifier stage. The gain is dependent on which input is chosen. If the LOW GAIN input is chosen, then the gain is given by $-R5/R3$, which two for the values shown. If the HIGH GAIN input is chosen, then the gain is given by $-R5/R4$, which is -10 (i.e. $\times 10$ inverted, for the values shown).

The gain of this stage may be altered by changing resistors R3, R4 or R5 and can be tailored to suit different input levels. It should be noted however, that if the gain is increased by any great amount (say, to 20), then it would require only a few hundred millivolts to saturate the input amp and drive it into clipping. Therefore, it is recommended that, unless the expected input signal is only a few hundred millivolts, the input stage gain should be left at unity. Also, the input resistance is set by the parallel combination of R1 and R3 for the LOW GAIN input, and R2/R4 for the HIGH GAIN input. These should be kept above about




Figure 1. Tone control at low frequencies.




Figure 2. Tone control at high frequencies.





Figure 3. Bode plot of tone control circuit behaviour.



30k or so to give minimum loading to the bass pickups.

The input is ac-coupled via C7 or C8. Resistors R1 and R2 ensure that no charge can build up on the input line due to stray capacitances.

Capacitor C10 compensates IC3 at unity gain. Actually, the value used overcompensates the 5534, but since a very wide bandwidth is not essential in bass applications, it was decided to overcompensate for the greater stability it provides.

The output of IC3 is fed to IC4 via RV1 which provides signal level control. IC4 is a 5534 op-amp configured as a unity gain buffer. This isolates the input section from the tone control network and provides a low impedance drive for that network. Capacitor C12 provides the necessary compensation for IC4.

The tone control network itself is an active 'Baxandall' negative feedback type. Bass control is provided by RV2 and treble control by RV3. To see how it works, let us

examine simplified circuits for the high and low frequency operation.

Figure 1 shows the simplified low frequency model. The capacitors become virtual open circuits at low frequency and the gain is dependent on the setting of RV2 only.

Figure 2 shows the equivalent high frequency circuit. This time, the capacitors become virtual short circuits and the gain is dependent on the setting of RV3 only.

The values for the tone control network were found using the equations for this type of circuit derived in the *National Audio Handbook*.

Figure 3 shows a Bode frequency plot for this circuit.

The circuit was designed for $A_{VB} = A_{VT} = 14 \text{ dB}$, and $f_L = 40 \text{ Hz}$, $f_{LB} = 200 \text{ Hz}$, $f_{HB} = 600 \text{ Hz}$ and $f_H = 3 \text{ kHz}$.

The op-amp used is, once again, a 5534. Capacitor C15 provides the compensation for unity gain operation. An offset null adjustment is provided via RV4 and R12. This

allows cancellation of any dc offset at the output which could affect the bass control operation and generate noise.

ETI-1410b 12 V POWER SUPPLY

Referring to the circuit diagram, T1 has 15-0-15 Vac which is rectified by diodes D1 to D4. The two diode pairs provide positive and negative outputs which are filtered by capacitors C1 and C2, respectively. This yields two supplies of around +18 V and -18 V or so.

A three-terminal regulator, IC1, produces a regulated +12 V from the +18 V supply. Similarly, another three-terminal regulator, IC2, produces a -12 V output. Capacitors C3 to C6 are necessary for stable operations of the regulators.

The circuit diagram also shows the mains wiring, including the mains input fuse and neon bezel. These components are not mounted on the pc board and are covered in the general constructional details in Part 2.

These OSCILLOSCOPES are so good that for THIS MONTH ONLY we are offering a 2 YEAR WARRANTY card with each RITRON high performance


Oscilloscope sold.

ROD IRVING ELECTRONICS PRESENTS

"RITRON"

★ LOW PRICE ★ HIGH QUALITY ★ 12 MONTHS WARRANTY ★

DUAL TRACE OSCILLOSCOPES



**MODEL
OS-645
15KV
45 MHz
&
1mV/div**

- ★ **WIDE FREQUENCY BANDWIDTH (70MHz-6dB)**
- ★ **OPTIMAL SENSITIVITY**
All the steps of vertical deflection factors are multiplied 5 times for the highest sensitivity of 1mV/div; 10MHz.
- ★ **DELAYED TRIGGERING SWEEP**
Any point of the waveform is addressed as a triggering start. So, any waveforms can be substantially and brightly magnified, thanks to the 5KV bright CRT.

- ★ **EXTREMELY BRIGHT DISPLAY**
The metal-back CRT (PDA) provides brightest trace display.
- ★ **DELAY LINE (for BS-625)**
Approximately 20 nsec before triggering point is displayed for real analysis of rise times.
- ★ **SCALE ILLUMINATION**
- ★ **SINGLE SWEEP**
A triggered sweep of a single waveform can be displayed.
- ★ **TV-SYNC**
TV composite signals can be easily synchronized.
- ★ **MAGNIFIERS**
Both vertical and sweep time are simply magnified to 5 times (1mV/div, 40nsec/div).
- ★ **X-Y, or X-Y-Z OPERATION**
Simply by turning the SWEEP TIME/DIV knob to CH-B, this functions as a very high sensitivity X-Y oscilloscope (1 mV/div) with intensity modulation.
- ★ **HF REJ**
High frequency noises can be rejected for the stayble triggering by use of the low pass filter built in the triggering circuit.

POINTS TO REMEMBER:


Ex Stock
12 Month Warranty
High Quality Components
Direct Import
Flat Face Internal Graticule Screen
On View at our 2 Stores
Our Eighth Year Of Business

COMPLETE MODEL RANGE SPECIFICATION CHART:

MODEL	SCREEN	SENS	SIG	TRIG	DEL	B'WIDTH	T'BASE	WITHOUT PROBES	TAX EXEMPT	WITH PROBES	CAT No.	COMMENTS
645	150mm	1mV	Y	Y	45MHz	0 2uS	0 5Sdiv	\$995.00	\$895.00	\$1055	Q12110	(70MHz-6dB)
620	150mm	5mV	N	N	20MHz	0 5uS	0 5Sdiv	\$495.00	\$425.00	\$549.00	Q12105	(45MHz-6dB)
615S	95mm	5mV	N	N	15MHz	0 5uS	0 5Sdiv	\$695.00	\$615.00	\$759.00	Q12100	AC-DC Operation

**BELOW
MANUFACTURER'S
COST!!**

**ONLY
\$125
COMPLETE
MASSIVE SAVING
OF \$74**



**FULL 90 DAY
WARRANTY**



Mail Order By
BANKCARD
Via Your Phone

At \$199 the Voyager Car Computer represented absolutely outstanding value for money. No one else had such a low priced **FULL FUNCTION** car computer. The Voyager is the only low cost unit that will give you full consumption, the most important feature in a car computer, in both miles driven, **TRIP** AND **average MILES PER GALLON**. At \$199 many, many hundreds have been sold. **NOW** you can get one absolutely complete for only \$125 including **12 MONTH** WARRANTY. The Voyager comes absolutely complete with all fitting hardware - means down to a roll of insulation! Installation generally takes between 10 and 15 minutes, depending on car type.

Spare Flow Sensor's We will be supporting this product for many years to come. To avoid problems changing cars, why not buy a spare fuel flow sensor? They are about the only things that wear out.


**X12036
ONLY \$29.50**

AS REVIEWED
OCT '82
EA (p.26-28)
ETI NOV '82 (p.26)

X12010

**NEW IMPROVED
MODEL!**

VOYAGER OPERATING FEATURES



ROD IRVING ELECTRONICS

425 High St., Northcote 3070 (03) 489 8866 (03) 489 8131
48-50 A Beckett St., Melbourne (03) 347 9251

Mail Order and Correspondence
P.O. Box 235 Northcote 3070



To Order By Phone

Mail Order Hotline (03) 481 1436

POSTAGE RATES


\$1-\$9.99	\$2.00	\$10-24.99	\$3.50
\$25-49.99	\$4.50	\$50-99.99	\$6.00
\$100-199	\$8.00	\$200-499	\$10.00
\$500+	\$12.00		

(All above charges are for surface mail and some heavy items will vary from these rates.)

Cert. post for orders over \$100 included "free"
Reg. post for orders over \$200 included "free"
Account orders from schools, govt. depts., public co's., gratefully accepted. Min order amount \$20.00 (or a min. \$5.00 accounting charge will apply.) Comet Road Freight, Airmail etc. are extra.




PROFESSIONAL QUALITY ELECTRONIC COMPONENTS




OKW

Uni-mess Box
Hand held enclosure
with battery
compartment and
digital or analog
readout panel




odu

D-Subminiature
Ribbon cable D-
Subminiature
connectors from
9-50 pin




OKW

Shell-case
Universal range of
shell-type cases, with
optional battery
compartment,
front-back panels



micro-parts electronic Ltd.

"NIF" No Insertion Force IC
Socket: Low profile, small
body size. Available in 24,
28, 40 and 48 pin.



OKW

Combi-knobs
Collet fixture knobs
utilizing a modular
assembly principle
including nut covers,
dial discs etc.



MAYER KRIEG & CO.


248 ANGAS ST., ADELAIDE, S.A. 5000.

For further information and data sheets contact your local distributor.
NSW: Mayer Krieg (02) 684 1900; M. Rutty (02) 476 4066. NEWCASTLE:
DGE Systems (049) 69 1625; QLD: E.C.Q. Electronics (07) 376 5677; Fred
Hoe (07) 277 4311. SA: Anelco Electronics (08) 294 2600. TAS: D & I
Agencies (002) 23 2842. VIC: Mayer Krieg (03) 579 5722. WA: Pro-Spec
Distributors (09) 362 5011. NZ: Channelmaster (9) 59 9003.

KITS


ECHO & REVERBERATION AMP

Kit includes all components, predrill cabinet, transformer and LED display. (See EA Nov., 83). \$ Special \$150



GRAPHIC EQUALISER + PHONO PRE-AMP

Compact two in one system with predrill cabinet. THD 0.05%,
±12 dB/octave TC, Phono input 2mV/47K, others
130mV/50K. \$ Special \$140



HIGH POWER HYBRID & MOSFET AMP IC's.

THD less than 0.005%, slew rate 15V/us (20V for MOS),
Damping factor over 400, 8R @ 100Hz. Bridging unit
available to double output power.

OUTPUT	HYBRID	MOSFET	TOROIDAL
180W/8R	\$119	\$205	500VA/40 \$90.50
120W/8R	\$ 82	\$139	300VA/35 \$66.50
60W/8R	\$ 62	\$ 82	160VA/25 \$46.50

Heatsink included, full year guarantee.

TRY OUR NEW DC NE5534 + FET OP-AMP high quality
PRE-AMP kit.

HI-FI ACCESSORIES

Gold plated RCA plugs and sockets, Jumbo Speaker cable
\$2.40/M

3 1/2 digit LED voltmeter

Autorange 0.1mV to 299.9V
with case \$49

Two ranges 6V and 60V \$29


Video Amp EA \$14.95

Video RF modulator \$17.50

Led Bargraph peak display \$16.50

Music colour IV EA \$89.50

Infra-red remote control switch \$39.00



PLUS MANY OTHERS

KEYBOARDS

MEMBRANE KEYBOARDS

as used in HIFI, VIDEO and control system.

Keys	4	12	16
Keyboards	\$4.80	\$7.80	\$9.20
Face Plate	\$0.70	\$1.20	\$1.60
Overlay	\$0.70	\$1.20	\$1.60
Bezels (black)	\$2.70	\$3.30	\$3.90
Colour Patches	\$0.80		
Letterset	\$3.50	per sheet	

Soft click operation conductive rubber keyboards

Spec: contact rating: DC24V 5mA; 500 R max, min 1000K life
times.


PK1200

\$9.00



PK1600


\$9.80



53 KEYS

FULL SIZE KEYBOARD

16 tracks matrix output. \$55



COMPUTER MONITORS SPECIAL

12" 80 col. green monitor \$199 now \$159

Ambre, swivel base and non-reflective screen \$275 now \$189

Slim line Disk Drive for Apple IIe, MPF-DD \$390

HICOM UNITRONICS INT. P/L

7 President Lane, Caringbah,
NSW 2229. (Next to McDonalds)

POST & PACKING

Under \$25	\$2.00
\$25-\$50	\$3.00
\$50-\$100	\$5.00
Over \$100	\$6.00
Heavy items	\$10.00

Phone (02) 524-7878

BANKCARD WELCOME

NOTE: Board artwork is reproduced on page 158.

such as 6-band graphics, limiter, line out and bi-amp facilities, which are usually found on only the more expensive commercial units.

This article details the overall concept and goes into the construction of the input board, the 12 V power supply and the power amp section. Part 2 will complete the project, giving details of the graphic equaliser and limiter/output boards and final assembly. Some options on setting up and using the amp will also be discussed.

It should be noted that, although far cheaper than a comparable commercial unit, this project would cost up to a few hundred dollars to build. Therefore, to avoid seeing some hard earned cash going up in smoke, only you folks with some experience in building electronic projects should attempt this one. If you still want to attempt it but don't have much electronic experience, then perhaps you can find a friend who does and is willing to give a helping hand to a starving muso.


The basic design approach

Several factors must be taken into account in the design of an amp for an electric bass guitar. Firstly, the frequency response. The low E string on a bass is usually tuned to 41 Hz. This means that the highest notes played on the bass will be only around three or four hundred hertz. As well as this, the average bass speaker box (a TL box for instance) will usually have an upper -3 dB cutoff frequency of around 1 kHz. With this in mind, it is important to design the bass and treble and equaliser sections to work in a suitable range. It's no good putting equalisation at 15 kHz since all you'll be equalising will be noise. Taking into account the need to be able to amplify harmonics as well as the fundamental of the notes it was decided to design the amp to work in the range 20 Hz to 5 kHz.

Unlike a normal guitar, a bass is usually amplified 'clean' (i.e. no clipping) and therefore it is important to ensure that there is plenty of "headroom" in the preamp stage. Most modern bass pickups are capable of putting out signal levels of a couple of volts peak (or more if pickups such as EMGs are used). Therefore the gain structure of the preamp should allow this level of input without causing clipping at the input stages. To facilitate the use of a bass with older pickups which may not have as high an output level, low gain and high gain inputs have been provided.

The power amp

The power amp used as the driver section for this amp is the ETI-499 150 W MOS-FET power amp module described in the March 1982 issue of ETI. This module was chosen as it is very reliable, reasonably easy to construct and offers excellent perform-



ance and stability. The module will deliver 100 W into an 8 ohm load and 150 W into a 4 ohm load. All the components, including the power supply components, are mounted on the one pc board and the pc board mounts directly onto a heatsink.

The circuit of this amp module will not be reprinted in this article and, for the purposes of description, the power amp module will be treated as a 'black box'. For full details of the specifications and circuit of this module see the article in the March 1982 issue of ETI. (Photostats are available from ETI Reader Services for \$3).

12 V power supply

The transformer specified for the ETI-499 power amp module (which is also the transformer used in this project) has an auxiliary 15-0-15 V winding which is used, in this project, to provide the positive and negative supply rails for the op-amps in the preamp boards.

The power supply board consists of a full-wave diode bridge rectifier which is filtered with two 2500 µF capacitors to form split rails of around 20 V. This is used to power 7812 and 7912 three-terminal regulators to provide the plus and minus 12 V rails used to run the op-amps.

Input board

The input board contains the initial gain control stage and the tone controls. Two inputs are provided which are designed to give maximum gains of 20 dB and 3 dB respectively. The tone controls are of the Baxandall type. These provide bass and treble control works in the region 20 Hz to 200 Hz and the treble control covers 400 Hz and up.

Equaliser board

The equaliser section is designed to provide unity gain with all controls set flat and 14 dB of boost and cut for each equaliser section. The equaliser consists of a series of filters incorporated into the feedback loop of an op-amp. This is based on the Series 5000 1/3-octave graphic equaliser published

in the November 1982 issue of ETI. The equaliser has been configured to give centre frequencies of 50, 100, 250, 500, 1 kHz and 3 kHz, a total of six bands.

The output of the equaliser section is fed into a gain section which acts as master volume control with a maximum gain of 34 dB. This will give an overall maximum gain from the preamp of 34 dB or 40 dB depending on the input used. If the bass you are using has high output pickups, such as EMG types, then you may want to decrease this gain so as to get full use from your volume controls.


Slider pots are used to control the amount of boost or cut at the equaliser frequencies. These were mounted on a separate pc board which will mount on the front panel of the amp. The only problem you may encounter in this is cutting the slots in the front panel to accommodate the six sliders. This problem will be discussed in 'Constructional details' section in Part

Limiter/output board

This board contains several sections of the circuitry. Firstly, a limiter circuit. This uses an NE570 IC compander. Its function is to limit the output of the preamp to a maximum of 1 V RMS which means that large transients, such as occur when a bass string is struck hard, will not over-drive the power amp and cause unwanted clipping.

The output section of the board provides the drive stages for a line level output which can be used to feed a mixer or for recording. A state-variable filter is used to provide high-pass and low-pass outputs with the cut-offs variable from about 50 Hz to a few hundred Hertz. These outputs are used in the bi-amping facility which allows the use of an external power amp to drive a speaker covering the low frequency end of the spectrum. The internal power amp is then fed from the high-pass filter and amplifies the higher frequencies only.

Level controls are provided for the line and bi-amp outputs to enable matching of the signal levels to the equipment they're driving.



The output facilities provided on this board make the amp very versatile and easily expandable into a large, higher-powered system if 150 watts doesn't hurt your ears enough.

Construction of the pc boards

All of the boards are relatively easy to construct. First, however, check the boards to see that all holes are correctly drilled and that there are no broken tracks or 'bridges' between closely-spaced tracks. Start with the 12 V power supply board (ETI-1410a). Solder in the big electrolytic capacitors (C1 and C2) followed by four tantalum caps. Make sure that you get the correct orientation of these capacitors as they are all polarised and tend to fail rather spectacularly if inserted the wrong way round.

Next, solder the diodes in place followed by the two voltage regulators, IC1 and IC2. These too are polarised and must be placed the correct way round. It is advisable to use solder pegs on the lead connections to this board since several leads may need to be soldered to the same point.

Tackle the input board next. Start by locating and soldering the small link wires in place. Solder in all the resistors and capacitors next. Note that RV1, RV2 and RV3 are specified as the miniature pc mount type with the standard size shaft. These will sit directly on the pc board and are soldered in place. Standard pots can be used but these will have to be attached to the board with hookup wire and, since the prototype board was held on the front panel by the miniature pots, an alternative board mounting scheme would have to be used. The only thing that remains to be done on this board is the mounting of the ICs, one transistor and

diode.

The use of IC sockets is not recommended when mounting audio ICs since the stray resistances and capacitances associated may affect the performance of the circuit. For this reason it is very important to put them in the right way round first time. It can be a real pain in the thumb to go round de-soldering ICs if a mistake is made. This then completes the construction of the input board.

The board left to construct at this stage is the main power amp board. As previously mentioned, this is the ETI-499 MOSFET power module which was described in the March 1982 issue. This should be constructed as shown in the original article (with the omission of the large heatsink since a different one is used in this project). If you are one of the very few people who do not have every copy of ETI ever published, then you can obtain a photocopy of the article by writing to our general enquiries service as detailed on page 3 of this issue.

Once all the boards have been completed a thorough check should be made to ensure that there are no small solder bridges between tracks on any of the boards and that all ICs and any other polarised components are mounted the correct way round. This then, completes the first part of the construction of the bass amp.

Next Part

In Part 2 of this article, the details of the final board (the limiter/output circuits) will be given as well as full constructional details, wiring diagrams and front panel artwork. For those experimenters out there, a few optional circuit ideas will be discussed which could be incorporated into the amp if you're after some super-deluxe features. ●

PARTS LIST — ETI-1410a PREAMP

Resistors	all 1/4W, 5% unless noted
R1.....	1M
R2, 3.....	220k
R4.....	47k
R5.....	470k
R6, 7, 10.....	6k8
R8, 9.....	5k6
R12.....	22k
R11, 13, 14, 15, 16, 17, 18.....	100R
R19.....	12k
RV1.....	10k/C rotary pot (Soanar V16L)
RV2.....	25k/A rotary pot (Soanar V16L)
RV3.....	500k/A rotary pot (Soanar V16L)
RV4.....	100k min trimpot
Capacitors	
C7.....	1µ/10 V tant
C8, C22.....	6µ8/10 V tant
C9.....	15p ceramic
C10, 12, 15.....	22p ceramic
C11.....	10µ tant
C13.....	150n greencap
C14.....	10n ceramic
C16, 17, 18, 19, 20, 21.....	100n ceramic bypass
Semiconductors	
IC3, 4, 5.....	NE5534N, LM5534N
Miscellaneous	
SK1, SK2.....	6.5 mm insulated, earthing-type, panel-mount mono jack sockets.

ETI-1410a pc board; hookup wire.

Price estimate: \$17-\$20


PARTS LIST — ETI 1410b ±12 V SUPPLY

Capacitors	
C1, C2.....	2500µ/35 V axial electros
C3, 4, 5, 6.....	10µ/35 V tant
Semiconductors	
D1-D4.....	1N4001, 1N4002, etc
IC1.....	µA7812, LM340/T12
IC2.....	µA7912, LM7912

Miscellaneous

ETI-1410b pc board; pc pins; hookup wire (T1 is the main transformer, the HT secondary of which supplies the power amp section of the project — see Part 2).

Price Estimate: \$12-\$14



ALL ELECTRONIC COMPONENTS


118-122 LONSDALE STREET, MELBOURNE, VIC. 3000
(03) 662-3506

Kitset Specialists

THIS MONTH'S KIT SPECIALS

JOIN THE GOLDRUSH

ETI 1500 KITSET



Superb unit featuring:

- Tune and discriminate.
- 4 modes of operation.
- VLF/TR design.
- Ground balance.
- Auto balance push buttons.
- Pre-wound search heads.
- Very professional unit.
- Approximately 1/3 price of many similar commercial built up locators.
- Audio and meter indication.

Lets you know when to rejoice.

PRICE: \$236.74 including pre-drilled and punched case, or \$200.00 including blank case. Plus \$10.50 p&p reg. post.

Stac Timer

ETI 650

\$140.15

incl. tax

Plus \$6.00 p&p



This unit has four different programmable outputs, clock controlled switch-ons/switch-off times. Selected days from the seven or eight day cycle can be "skipped". Ideal for operating air conditioning, fish tanks, hi-fi systems, tape recorders, slide & movie projectors, laboratory control, video equipment, etc.

EA DELUXE CAR ALARM

Includes Aluminium F/P speaker, P.C.B., case, keyswitch, etc...

PROTECT YOUR CAR FOR ONLY \$89.54

HAVING TROUBLE TALKING TO YOUR PILLION PASSENGER?

E.A. Motorcycle Intercom

includes P.C.B., case, F/P, electret mics, headphones etc.

\$53.33 inc. tax


GREAT FOR RALLY CARS TOO!

'PRO' BENCH POWER SUPPLY

ETI 142
0-30 VOLTS;
0-15 AMPS!

\$322.26 plus \$10.50 pack & reg. post.

A phenomenal supply with professional finish and professional performance. It features 20 mV regulation from zero to full load, 10 mV ripple and noise, voltage and current metering on separate meters, overload protection and adjustable current limiting. Sturdy metal cabinet with silk-screened aluminium front panel supplied.



ETI 547 TELEPHONE BELL EXTENDER

Ideal for those of us hard of hearing or working in high noise environments

ONLY \$31.40

EA VCR SOUND PROCESSOR KITSET

\$51.68 less flp and whistle filter

Whistle Filter—\$20.50

Importers ■ General Sales ■ Radio Equipment ■ Microwave Equipment ■ Radar Equipment ■ Pulse Techniques ■ Industrial Electronics ■ Instrumentation

Mains frequency generator

H. Nacinovich, Gulgong NSW

This circuit was designed to operate a 240 V/3 W telescope drive motor but it would be suitable for many other low power applications. It could also provide the basis for a high power version, with suitable modification to the output stage.

For its present purpose, the most important requirement is for a highly stable, 50 Hz operating frequency. This is achieved by using a 3.5795 MHz crystal and an MM5369EYRN IC, which were chosen for their low cost and ready availability. The MM5369EYRN IC contains an oscillator and all the divider circuitry necessary to produce a precise 50 Hz square wave output when used in conjunction with the 3.5795 MHz crystal.

One disadvantage of this IC, however, is that its output is not an exact 50/50 duty cycle square wave. For some applications this may not matter but,

if used directly to drive an output stage in a high power convertor, for example, the asymmetrical waveform could result in significant unbalanced dc currents sufficient to saturate the output transformer. Also, for high power convertor applications, at least, it is desirable to drive the output transistors (usually in push-pull) with a delay between turn-off of one set of output transistors and turn-on of its complementary set of transistors.

This circuit provides both a symmetrical drive current waveform to the output transistors and the delay referred to above. This is achieved using only two low cost, easily obtainable ICs, a 4046 CMOS phase lock loop and a 4022 octal counter.

The counter is arranged in a feedback loop with the 4046 in such a way that the output is locked precisely to the 50 Hz input derived from the 5369 IC. The 4022 has, in fact, eight

outputs which go sequentially high when the counter is clocked. In this case the 4022 is connected as a divide-by-6 counter, with four of its outputs being used to supply input drive to transistors Q1, Q2. The sequential operation of the 4022 outputs is taken advantage of here to obtain the waveforms shown in the diagram without the need for any extra gating. The idealised ac output waveform has a 4:2 on/off ratio which gives a theoretical peak/rms ratio similar to that for a sine voltage waveform.

The output section is conventional. It comprises a pair of transistors Q1, Q2 in push-pull driving a pair of output transistors Q3, Q4 respectively, which in turn are coupled to an output transformer, T1. The transistors Q1, Q2 are ac coupled to the 4022 outputs, rather than dc coupled, to ensure that all the transistors are turned off in case oscillation ceases for any reason, e.g. in case of a



fault.

The output transformer is a commonly available type with a 240 V/15 V centre-tapped winding ratio which, assuming a 12 V battery supplying the circuit, will theoretically give a 384 V peak (256 RMS). In practice an output closer to 360 V peak (240 V RMS) is obtained due to circuit losses.

Maximum continuous output power is around 10 W. If higher output power is required it will be necessary to substitute a suitably rated transformer and output transistors with correspondingly increased current/power ratings. It may also be necessary to use Darlington output pairs to obtain the increased output current.

Diodes D3, D4 and a series RC network across the transformer secondary minimise switching spikes in the ac output. Some experimentation with the values of C_x , R_x may be necessary for optimum suppression depending on transformer type and output loads.

OPERATING WAVEFORMS




ROD IRVING ELECTRONICS

425 HIGH ST, NORTHCOTE 3070 VIC

PHONE (03) 489 8866

THIS MONTH'S KITS

Please ring for price and availability



150 WATT BASS GUITAR AMP

Featuring a five-band graphic equaliser and 150 watts output (using the popular and reliable ETI-499 MOSFET module), this rack-mounted amp performs really well. We know, the designer plays bass in Sydney group, Rafequats Right Foot!



ELECTRONIC MOUSE TRAP

The breaking of the drought has brought on a mouse plague.

Tried to buy a mouse trap lately? You can't. Well, here is an electronic mouse trap that despatches the beasts swiftly and perhaps a little more humanely than traditional methods. What's more, it re-sets itself. Simple, and cheap to build.




\$89.50

ETI-669 PANGALACTIC EPROM ERASER

If you walk into the restaurant at the end of the universe and tell the bartender you're confused, he'll say "don't panic! have a pangalactic gargleblaster. It will erase your current existence allowing The Master to reprogram you for another time and space". Well, our little EPROM eraser does a similar job for your 2716s, 2732s, 2764s ... et al. Parts list attached.

Led Head Lightchaser



(Battery and headband extra)

\$12

REMOTE INFRARED TV SOUND CONTROL



E.A. JANUARY '83

Designed to relieve the long-suffering TV viewer from painful, brain-killing advertisements, our TV Sound Control provides remote control of volume. It gives eight steps of control, including full off, when total silence is called for. Give yourself a break and relieve advertising tedium today.

\$40



PLUG PACK REGULATOR

\$14

Plugpack Extra

PH METER

\$135

with probes



12/240 volt Inverter

40 WATTS



MAY EA 1982

\$49.50

BOGGLE GOGGLES

\$9.60


Short form



EA POWER UP

\$38.50

EA NOV 1982



EA DIGITAL READOUT FOR SW RECIEVERS

\$72.00 COMPLETE

OCTOBER EA 1982



Want to add digital frequency readout to an AM radio or shortwave communications receiver that uses an old fashioned analog dial? This unit features a bright four digit LED display, 1kHz resolution, and a 0.2s update time that's fast enough to follow the tuning knob.

Errors and Omissions Excepted


Ranges (full scale): 0 10MHz and 10 30MHz (optional).

Display: Four digit

Resolution: 1kHz with division switch set to divide by one; 10kHz with division switch set to divide by 10.

Sensitivity: Less than 100mV from 500kHz to 30MHz.

Offset frequency: Prototype set to 455kHz, but any offset frequency can be programmed.



\$48.50

Engine Analyser Kit




Analogue and Digital Storage CRO Kit

\$189.00


EA EASY-TO-BUILD FREEZER ALARM

OCTOBER EA 1982



STEREO SYNTHESISER FOR TUNERS AND VCRs

Enjoy the benefits of stereo sound from your video cassette recorder, TV or AM tuner with this Stereo Synthesiser. The circuit uses just four ICs and is easy to build.



EA ELECTRONIC STARTER


FOR FLUORESCENT LAMPS

\$4.95

OCTOBER EA 1982

OVER 200 NOW SOLD EA INVERTER INCLUDING TRANSFORMER 300 WATTS

\$195



JUNE EA 1982

P & P \$10.00
Anywhere in Australia

SPECIFICATIONS FOR 300W INVERTER

Nominal Supply Voltage	12V DC
Output voltage	see table
Frequency	50Hz \pm .005%
Regulation	see table
Maximum Load	300VA
Current Limiting	30A (primary)
Efficiency	see table

Resistive load W	Output voltage (RMS)	Input current (A)	Efficiency (%)	Battery life 40Ah/20h rate (minutes)
10	21.0	1.2	0	240
30	21.3	1.5	60	80
100	21.0	1.1	62	60
150	21.0	1.5	64	50
200	21.0	2.0	78	32
250	21.0	2.5	79	28
300	21.3	2.9	82	28

ROD IRVING ELECTRONICS

425 High St., Northcote 3070 (03) 489 8866 (03) 489 8131
48-50 A Beckett St., Melbourne (03) 347 9251

Mail Order and Correspondence
P.O. Box 235 Northcote 3070



To Order By Phone

Mail Order Hotline (03) 481 1436

POSTAGE RATES

\$1-\$9.99	\$2.00	\$10-\$24.99	\$3.50
\$25-\$49.99	\$4.50	\$50-\$99.99	\$6.00
\$100-\$199	\$8.00	\$200-\$499	\$10.00
\$500+	\$12.00		


(All above charges are for surface mail and some heavy items will vary from these rates.)

Cert. post for orders over \$100 included "free".
Reg. post for orders over \$200 included "free".
Account orders from schools, govt. depts., public co's, gratefully accepted. Min order amount \$20.00 (or a min. \$5.00 accounting charge will apply.) Comet Road Freight, Airmail etc. are extra.



ETI 662D Darkroom Timer

Another in our series of photography projects. Digital readout, countdown - Style timer.



ETI MAY 84

Please ring for price availability on new kits

ETI 659 VIC-20 Cassette Interface

ETI MAY 84




ETI 1421 Indoor Paging Amp. System

For clubs, halls, offices, etc.

ETI MAY 84

ETI 737 UHF Pre-amp


ETI MAY 84



ETI-662A GENERAL PURPOSE MICROPROCESSOR CONTROLLER

ETI APRIL 84


A microprocessor with a bit of ROM, a bit of RAM and some I/O lines. This project based on the 6802 will form the basis of a series of projects.



ETI-1521 DIGITAL EXPOSURE METER

Don't be caught with indecent exposure! Our digital exposure meter is low in cost, simple to build and operate and includes a three digit readout.

\$9.00




\$18.50

ETI Oct 83

ETI-412 PEAK PROGRAMME METER

This project uses a 10-LED bargraph display module to show audio level from -23 dB to +6 dB. It's simple to build and set up.




ETI Oct 83

\$16.50

ETI-672 MICROBEE TELETYPE INTERFACE

The 'Claytons' of printers is the old surplus teletype—such as the Model 15 etc. For around a tenth the price of a dot-matrix printer, you can have hard copy from your microbee using this simple interface.




ETI MAY '83

ETI-163 LAB SUPPLY

\$165

Fully variable 0-40 V current limited 0.5 A supply with both voltage and current metering (two ranges 0-0.5 A 0-5 A). This employs a conventional series-pass regulator, not a switchmode type with its attendant problems, but dissipation is reduced by a unique relay switching system switching between taps on the transformer secondary.



ETI-668 MICROBEE EPROM PROGRAMMER

ETI FEB '83

\$47.50

Simple, low cost programmer for the MicroBee can program 2716s, 2732s and 2764s.


ETI-153 TEMP. PROBE

\$19.95

ETI JUNE '83



Can measure temperature from -50°C to +150°C. It simply plugs into your multimeter—great for digital multimeters. Accuracy of 0.1°C resolution of 0.1°C.




ETI-678 MICROBEE ROM READER

This project enables your favourite games or utilities to be loaded quickly into your Microbee from an EPROM—no more agonising waiting for a cassette to load or going to the expense of a disk system.

ETI MARCH 84

\$17.50




\$13.50

ETI Oct 83

ETI-671 MICROBEE PRINTER INTERFACE

A simple interface unit for parallel printers.




ETI-162 30 V/1 A FULLY PROTECTED POWER SUPPLY

ETI DEC '83

\$47.50

The last power supply we did was the phenomenally popular ETI-131. This low cost supply features full protection, output variation from 0 V to 30 V and selectable current limit. Both voltage and current metering is provided.



ETI-662B TIMER/CONTROLLER

This project supercedes the ETI-650 STAC Timer providing more versatility and easy programmability.

ETI APRIL 84

ETI-688

BIPOLAR PROM PROGRAMMER

\$47.50

ETI JUNE '83

Every digital workshop should have one! Can be used to program the popular fusible-link PROMs like the 74S188 288 82S23 and 82S123 etc.




ETI-461 GENERAL PURPOSE BALANCED INPUT PREAMP

\$20.00


ETI Oct '82

This project can be used as a balanced mic amp with low impedance input, a low or high impedance input differential amplifier or a balanced input instrumentation amplifier.



ETI-340 CAR ALARM/MONITOR SYSTEM

Features three delays—entry, exit and alarm length. Immediate-trip perimeter alarm sounds if battery, tyres lights, etc are disconnected. Circuitry is based on all common parts (555s, 40001s, BC457/8/9s, 1n4002s etc.).



ETI-1522 CONTROL FOUR ROOM LIGHTS OVER A TWO-WIRE PAIR

It is probably a not-uncommon problem to want to replace the single ceiling light in a room with a more exotic arrangement only to find that the control wires to the switch are concreted in! Either that, or you don't want to "chase" more wires through the wall and have to replace the wallpaper and/or redecorate. This project fixes that.




ETI-335 PUSHBUTTON-PROGRAMMABLE WIPER CONTROLLER

\$28.50

ETI MARCH '83

No more fiddling with knobs and not getting the delay between wipes that you want—this windscreen wiper controller is simply programmed with two pushbuttons to provide the wiping delay you need.



ETI-733 RADIOTELETYPE CONVERTER FOR THE MICROBEE

\$20.00

Have your computer print the latest news from the international shortwave news service. Just hook up this project between your shortwave receiver's audio output and the MicroBee's parallel port. A simple bit of software does the decoding. Can be hooked up to other computers too.

ROD IRVING ELECTRONICS

425 High St. Northcote 3070 (03) 489 8866 (03) 489 8131
48-50 A Beckett St. Melbourne (03) 347 9251

Mail Order and Correspondence
P.O. Box 235 Northcote 3070

To Order By Phone

Mail Order Hotline (03) 481 1436



POSTAGE RATES

\$1-\$9.99	\$2.00	\$10-\$24.99	\$3.50
\$25-\$49.99	\$4.50	\$50-\$99.99	\$6.00
\$100-\$199	\$8.00	\$200-\$499	\$10.00
\$500+	\$12.00		

(All above charges are for surface mail and some heavy items will vary from these rates.)

Cert. post for orders over \$100 included. free
Reg. post for orders over \$200 included. free
Account orders from schools, govt. depts., public co.s., gratefully accepted. Min order amount \$20.00
(or a min. \$5.00 accounting charge will apply.) Comet Road Freight, Airmail etc. are extra.




IDEAS FOR EXPERIMENTERS

Screw-in LED


Utilising the metal bases from blown lilliput-type globes you can make screw-in LEDs to replace globes inside small switches and bezels. **Mike Home of Mitcham, Vic** has found this to be much more reliable than incandescent indicator lamps.

Just clean the solder from the base, cut a small slot in the rim, bend the leads (carefully) to fit

and solder in. File down if necessary. And don't forget to add a dropping resistor in series!



Rapid Fire Paddle



Here at ETI we suspect this idea is highly unethical, but **Nigel Senior of North Fitzroy Victoria**, has sent us this idea which assures you a better than even chance of winning at Space Invaders.


The idea is to put a simple

bistable inside the computer joystick. Pressing the fire button will make the system fire at a rate determined by the software of the game itself.

Now, to give the invaders a chance, play blindfolded!

ERRATA

The following bit of circuitry was left off the circuit diagram of our Idea of the Month in April 1984:




Notice that the WR lines of IC7 and IC5 should not be joined, but should be connected as shown.

There is also an error in the program listing that accompanied the article. These should read:

1.
LD A, 50H
LD (0D3H), A
LD A, 59H
LD (0D4H), A
LD HL, 0E1H
CALL 85A7H

There should be an inverter in the line from pin 1 of IC11 on the Microbee to pin 1 of IC6 as follows:



2.
LD A, 2
OUT (0CH), A
LD A, 59H
OUT (0DH), A
LD A, 1
OUT (0CH), A
LD A, 50H
OUT (0DH), A

'IDEA OF THE MONTH' CONTEST

COUPON

Cut and send to: **Scope/ETI 'Idea of the Month' Contest, ETI Magazine, P.O. Box 227, Waterloo NSW 2017.**

"I agree to the above terms and grant *Electronics Today International* all rights to publish my idea in ETI Magazine or other publications produced by it. I declare that the attached idea is my own original material, that it has not previously been published and that its publication does not violate any other copyright."

* Breach of copyright is now a criminal offence.

Title of idea


Signature

Name

Date

Address

Postcode



Scope pc board Work Centre

PRIZE WORTH \$123!

Scope Laboratories, which manufactures and distributes soldering irons and accessory tools, is sponsoring this contest with a prize given away every month for the best item submitted for publication in the 'Ideas for Experimenters' column — one of the most consistently popular features in ETI Magazine. Each month we will be giving away a pc board Work Centre consisting of the Model 315 adjustable pc board holder with capacity to accept 300 mm boards, Model 300 180° swivel and lock base which can be attached to the Model 312 tray base with wet sponge receptacle, Model 371 solder spool holder and Model STS 3 soldering iron safety stand. Please note prize does not include solder or scope TC60 temperature controlled iron shown above. The prize is worth \$123!

Selections will be made at the sole discretion of the editorial staff of ETI Magazine. Apart from the prize, each winner will be paid \$10 for the item published. You must submit original ideas of circuits which have not previously been published. You may send as many entries as you wish.

RULES

This contest is open to all persons normally resident in Australia, with the exception of members of the staff of Scope Laboratories, The Federal Publishing Company Pty Limited, ESN, The Litho Centre and/or associated companies.

Closing date for each issue is the last day of the month. Entries received within seven days of that date will be accepted if postmarked prior to and including the date of

the last day of the month.

The winning entry will be judged by the Editor of ETI Magazine, whose decision will be final. No correspondence can be entered into regarding the decision.

The winner will be advised by telegram the same day the result is declared. The name of the winner, together with the winning idea, will be published in the next possible issue of ETI Magazine.

Contestants must enter their names and addresses where indicated on each entry form. Photostats or clearly

written copies will be accepted but if sending copies you must cut out and include with each entry the month and page number from the bottom of the page of the contest. In other words, you can send in multiple entries but you will need extra copies of the magazine so that you send an original page number with each entry.

This contest is invalid in states where local laws prohibit entries. Entrants must sign the declaration on the coupon that they have read the above rules and agree to abide by their conditions.

ROD IRVING ELECTRONICS

50V 5A LABORATORY POWER SUPPLY




New switchmode supply can deliver anywhere from three to 50V DC and currents of 5A at 35V or lower. Highly efficient design.

EA May, June 1983

\$140.00

OVERLOAD INDICATOR



Will detect even slight overload conditions and is not affected by load impedance or varying supply voltages. E.A. JUNE '83

\$75.00

EFFECTS UNIT




An "Effects Unit" that can create phasing, flanging, echo, reverb and vibrato effects. E.A. JUNE '83

EPROM PROGRAMMER

\$43.00


No need for a Micro with EA's great Eprom Programmer suitable for 2716/2758 Eproms.

With Textool Sockets \$55.00
EA January 82



DUAL TRACKING POWER SUPPLY

\$87.50




Built around positive and negative 3-Terminal Regulators this versatile dual tracking Power Supply can provide voltages from $\pm 1.3V$ to $\pm 22V$ at currents up to 2A. In addition, the Supply features a fixed $+5V 0.9A$ output and is completely protected against short circuits, overloads and thermal runaway. EA March 82

SOUND TRIGGERED FLASH

\$26.50

This easy to build sound or light operated flash trigger has many features.


Catch those spectacular and humorous moments like that time your mother-in-law slipped on the moss covered patio and broke her neck. ETI 568 October 80



ELECTRONIC METRONOME


\$18.90

Great new Metronome Circuit with low current drain (less than one milliamp) drives a Loudspeaker and a Led Indicator. EA January 82



3 1/2 DIGIT LCD CAPACITANCE METER

Handy pocket size Digital Capacitance Meter, runs off a 9V battery and measure 1pF to 19.99uF in just three ranges. EA March 82




\$89.95

VOICE OPERATED RELAY

\$14.95

EA's great new Voice Operated Relay can be used to control a tape recorder, as a VOX circuit for a transmitter, or to control a slide projector. EA April 82



"LE GONG"

\$14.95


The "Le Gong" Doorbell with those unmistakable chimes generated by the LSI. A must for the man who has everything! EA February 81



LED LEVEL METER

\$27.00


Build a Led level Meter with simultaneous peak and average display plus 60dB dynamic range. This kit is ideal for any application requiring a wide dynamic range level display. ETI 458 June 81




LOW OHMS METER

\$34.50

How many times have you cursed your Multimeter when you had to measure a low-value resistance. Well alas, with the "Low Ohms Meter" you can solve those old problems and in fact measure resistance from 100 Ohms down to 0.005 Ohms. ETI 158 November 81



FUNCTION GENERATOR \$79.50




This Function Generator with digital readout produces Sine, Triangle and Square waves over a frequency range from below 20Hz to above 160kHz with low distortion and good envelope stability. It has an inbuilt four-digit frequency counter for ease and accuracy of frequency setting. EA April 82

LOTTO/POOL'S SELECTOR

\$22.50

You have to be in it to win it. Take the chance out of winning the Pools as well as Lotto, and build the great new Pools/Lotto Number Selector. EA July 81



LARGE SCREEN TV STORAGE CRO ADAPTER

\$119.00




For a low cost Storage CRO with Synchronised Display, Electronic Graticule, One-Shot Triggering and Optional Storage of up to four Screen Displays it can't be beaten. EA February 82

DIGITAL THERMOMETER: 3 1/2 DIGIT LCD

\$89.95


Measure temperatures from below freezing point to around boiling point. EA February 82



SOUNDBENDER

\$29.00

Have great fun creating your own recording effects with music and voice. The Sound Bender can receive from Electric Guitar, Microphones, etc. ETI February 82



Errors & omissions excepted

ROD IRVING ELECTRONICS

425 High St., Northcote 3070 (03) 489 8866 (03) 489 8131
48-50 A Beckett St., Melbourne (03) 347 9251

Mail Order and Correspondence
P.O. Box 235 Northcote 3070

To Order By Phone

Mail Order Hotline (03) 481 1436



POSTAGE RATES

\$1-\$9.99	\$2.00	\$10-24.99	\$3.50
\$25-49.99	\$4.50	\$50-99.99	\$6.00
\$100-199	\$8.00	\$200-499	\$10.00
\$500+	\$12.00		

(All above charges are for surface mail and some heavy items will vary from these rates.)

Cert. post for orders over \$100 included "free".
Reg. post for orders over \$200 included "free".
Account orders from schools, govt. depts., public co's., gratefully accepted. Min order amount \$20.00 (or a min. \$5.00 accounting charge will apply.) Comet Road Freight, Airmail etc. are extra.



NEW PRODUCTS!

FROM ROD IRVING ELECTRONICS

AUDIO DIGITAL DELAY



FEATURES:

- *Originally developed A/D adapting circuit (equivalent to 14-bit-circuit) is adopted.
- *The wide delay range of 1-1024mSec. enables you to obtain the big variety of sound effect (Slap Back, Doubling, Flanging, Chorus or Lond Delay).
- *The wide frequency range of 16 kHz enables you to use the apparatus for any purpose (Vocal, Guitar, Keyboard or P.A.).
- *The special function of "HOLD" is provided in this model. Hold time is 250-1024mSec.

\$479.00

ANTENNA AMPLIFIER and SPLITTER



\$29.95

Great Value at \$29.95
An ideal unit for where
you can't get to the top
of your antenna

AA1 ANTENNA AMPLIFIER/SPLITTER

UHF/VHF/FM indoor antenna amplifier and 2 way splitter-ideal for home, boats, caravans-Covers all Australian frequencies-75 ohm in 2 x 75 ohm out-gain 2 x 6dB-power supply 12V DC 100mA (supplied)

UHF TO VHF DOWN CONVERTER

L11042



\$59.95

A Ready Built Unit.
For units with VHF
O/PS line computers
and VCRs.

VUC1

UHF to VHF down converter-has built in amplifier to ensure no signal loss-selectable channel 1, 3, & 4-power supply 12V DC 100mA (supplied). Converts UHF signal to VHF-allows TV without UHF to use VCR-Video game or to receive off-air UHF signal-switchable to channel 1, 3 and 4

VIDEO PROCESSING CENTRE



VP5050

Combination stabiliser, enhancer, distribution amplifier, RF converter. The ultimate videophile component-designed to enhance all recording needs-will handle 3 VCRs simultaneously with virtually zero signal loss-built in RF converter permits in-line connection between VCR and TV for improving recording whilst viewing

Power Requirements:

12V DC-300mA

Inputs:

Video, Audio

Outputs:

3 Video, 3 Audio

RF UHF:

Channel 36

Output Level:

+0.3dB

Output Isolation:

More than 40dB

Audio Outputs:

Unity Gain

Input/Output:


75 ohms

*PP300 recommended power source

\$119.00

A13012

VIDEO TAPE STORAGE BOX.




\$19.95

A15037

TSC1

BOX-6 pcs PER CARTON

Tape storage cabinet-sturdy plywood cabinet-walnut grained vinyl-ABS storage trays-each tray holds 12 audio cassettes-a total of 36 cassettes in their boxes



\$52.50

A15038

TSC2

BOX-3 pcs PER CARTON

Video tape storage cabinet-walnut grained vinyl-plywood cabinet-ABS storage drawers-each drawer holds 12 VHS or BETA tapes-total storage 36 video tapes

NEW BENCH POWER SUPPLIES NEAT CONSTRUCTION MUL TI-VOLTAGE




\$19.95

M19025

PP1000

Power pack 1 amp-240V AC to 6-7 1/2-9-12V DC. Ideal for the workshop-DC connection with banana plugs or via screw terminals. Suits our MD 12 Mini Drill-MS402P powered speakers and many other applications



\$39.95

M19030

RPP2000

Regulated power pack-2 amp-240V AC to 12V DC. Ideal for CB and workshop use where large amounts of power are required-DC connection with banana plug or via screw terminals

MULTI- PURPOSE VIDEO DUBBING KITS IT'S AMAZING HOW MANY DIFFERENT TYPES OF VIDEO THERE ARE

VDK1 VIDEO DUBBING KIT

For European to Japanese machines-packed in plastic tray for easy storage and identification-contains:

Audio/Video: 6 pin DIN plug to 6 pin DIN plug 1.5 metres

Audio/Video: 6 pin DIN socket

to a) Video: RCA plug

b) Audio: 5 pin DIN plug

(both 16cm in length)

Video: 1 each plug adaptor-

(PA21) RCA socket to PL259

plug

(PA23) RCA socket to BNC

plug

Audio: 5 pin DIN socket to 2



P32190

\$16.00

RCA plugs 16cm length
2 plug adaptors (PA60)
RCA socket to 3.5mm phone plug

VDK2 VIDEO DUBBING KIT

All Japanese machines-old to new-packed in plastic tray for easy identification of part and tidy storage-contains:

Video: RCA PLUG TO RCA PLUG-1.5 metre-75 ohm

2 plug adaptors (PA23)

RCA socket to BNC plug

2 plug adaptors (PA21)

RCA socket to PL259

plug

Audio: RCA plug to RCA plug-

1.5 metres-shielded cable



P32192

\$19.95

2 pcs 5 pin DIN plug to 2 RCA sockets (in/out)-16cm

2 plug adaptors (PA60)
RCA socket to 3.5mm phone plug

ROD IRVING ELECTRONICS

425 High St., Northcote 3070 (03) 489 8866 (03) 489 8131
48-50 A Beckett St., Melbourne (03) 347 9251

Mail Order and Correspondence
P.O. Box 235 Northcote 3070



To Order By Phone

Mail Order Hotline (03) 481 1436

POSTAGE RATES

\$1-\$9.99	\$2.00	\$10-\$24.99	\$3.50
\$25-\$49.99	\$4.50	\$50-\$99.99	\$6.00
\$100-\$199	\$8.00	\$200-\$499	\$10.00
\$500+	\$12.00		

(All above charges are for surface mail and some heavy items will vary from these rates.)


Cert. post for orders over \$100 included "free".
Reg. post for orders over \$200 included "free".
Account orders from schools, govt. depts., public co's., gratefully accepted. Min order amount \$20.00 (or a min. \$5.00 accounting charge will apply.) Comet Road Freight, Airmail etc. are extra.



VIDEO & AUDIO ACCESSORIES, TAPES, DEMAGNETISERS, MICROPHONES

Built
and tested

VIDEO SWITCHING BOX



ON SPECIAL
\$39.50

Low loss R.F. switching—allows inputs for - VCR, video disc, antenna, cable TV, home computer and video games.

WE HAVE A GREAT RANGE OF VIDEO CONNECTORS AND CABLES FOR VIDEO TO VIDEO DUBBING.

Cables

PA-25

5 pin 180 degree dubbing adaptor—Reverse pins for video use **\$6.95**

VC-14

8 pin square plug to 8 pin square plug Cable length 2 metres **\$29.95**

VC-15

6 pin DIN plug to 6 pin DIN plug Cable length 1.5m **\$4.95**

VC-1

BNC plug to BNC plug Impedance-75Ohm Cable length 1.5m **\$6.50**

VC-2

BNC plug to PL259 plug Impedance-75Ohm Cable length 1.5m **\$6.75**

VC-3

PL 259 plug to PL 259 plug Impedance-75Ohm Cable length 1.5m **\$4.95**

VC-4

PL 259 plug to RCA plug Impedance-75Ohm Cable length 1.5m **\$4.95**

VC-5

RCA plug to RCA plug Impedance-75Ohm Cable length 1.5m **\$5.95**

VC-6

BNC plug to RCA plug Impedance-75Ohm Cable length 1.5m **\$5.95**

Video Connectors

VP-8

8 pin square video connector plug **\$7.50**

VS-8

8 pin square video connector inline socket **\$7.50**



VP-10

10 pin male video plug Used in J.V.C., Panasonic, Sharp and other VHS machines **\$11.50**

VS-10

10 pin female inline socket Used in J.V.C., Panasonic, Sharp and other VHS machines **\$11.50**

VP-14

14 pin male video plug Used in Sony, Sanyo, Toshiba and other Beta machines **\$16.50**

VS-14

14 pin female inline socket Used in Sony, Sanyo, Toshiba and other Beta machines **\$16.50**



Built
and tested

VIDEO ENHANCER



Bargain Price
\$75.00

Detail Enhancer VP5030 is another important contribution to the world of video accessories. The lightweight Detail Enhancer has been particularly designed to rectify loss in detail derived from VCR tapes and picture impairments. With simple adjustments for more or moderate detailing the detail enhancer can also overcome such picture impairments as loss of detail and disappearance of verticle lines.

Specifications:

1. Power requirement 12V DC 110mA
2. Input 1 Video (RCA connector)
3. Outputs 3 Videos (RCA connectors)
4. Output level Video outputs 1.0Vp-p 75 Ohm unbalanced below 1Vp-p out
5. Enhance Enhance 9dB (Reference 1.0Vp-p)
6. Signal-to-noise ratio Greater than 50dB below 1Vp-p out

VIDEO STABILIZER

VP-5010

Image stabilizer — ensures no vertical roll or blackout occurs. With slight adjustment immediately stabilises picture of pre-recorded tapes — removing the copyguard signal, which tends to upset video recorders

Power Requirement 9VDC negative earth*
Input 2 video (RCA connectors)
Output 1 video (RCA connector)
Oscillator Freq 3590Hz
Output Level Video out 1.0V P.P. 75 ohm unbalanced
Gain 1 (0dB)
*PP300 recommended power source



\$79.50

DM726L LOW IMPEDANCE — OMNI DIRECTIONAL . . . \$11.95 DM726H HIGH IMPEDANCE — OMNI DIRECTIONAL . . . \$12.50

Impedance: L = 500 ohm
H = 20K ohms
Freq. response: 40-14KHz
Cord/Plug: 1.5 metres/6.5mm plug
Dimensions: 500 x 272mm
With on/off switch



WIRELESS MICROPHONE

Tunable 88-108MHz
Freq. Response 100-10KHz
Battery 1.5V UM3/AA
Type Electret condenser

\$11.95

THIS MONTH ONLY



DM-18 STOP/START CASSETTE MICROPHONE

Impedance: 200 ohm
Freq. Response: 250-10KHz
Sensitivity: -74dB
2.5 and 3.5mm plugs




\$5.95

VIDEO HEAD CLEANERS

HC-1 V.H.S. Video head cleaner
HC-2 Beta Video head cleaner

A professional head cleaner — employs new "double sided cleaning action"—no need to "operate" on your machine. Just insert the cassette, play for 30 seconds and the job is done. Effective for 100 operations.



HC-1 \$17.50 HC-2 \$17.50

ELECTRONIC CASSETTE DEMAGNETISER

Cassette heads should be demagnetised every 30 hours for optimum performance. Technically the best available and easy to use, completely automatic — with LED indicator

Battery LR 44, SR 44
Battery life 600 applications
Flux density 220 gauss/650Hz
Circuit 4 transistor — 4 diode

\$16.95



HD-2 HEAD DEMAGNETISER


Twin probe for more effective magnetic field 240V AC operation — on/off switch — indicator light insulated tip

\$14.95



Video library storage case — looks just like hard cover book — with identification card pouch

1.9 10+
A150J5 BETA \$2.75 \$2.25
A150J6 VHS \$2.95 \$2.35



TDK AUDIO TAPES

D 46	1.9	10+
D 50	2.54	1.93
D 90	2.86	2.09
D 120	3.08	2.31
AD 50	5.23	3.85
AD 60	3.47	2.86
AD 90	4.29	3.30
AD 120	6.49	5.39
ADX 60	4.46	3.30
ADX 90	5.28	4.18
SA 60	4.68	3.74
SA 90	5.28	4.29
SAX 60	5.78	5.06
SAX 90	6.38	5.72
MAC 60	10.45	9.35
MAC 90	11.28	8.75
MAR 60	13.42	10.95
MAR 90	17.29	15.35


TDK VIDEO TAPES

60	12.50	11.00
120	14.00	13.00
180	15.00	14.50
240	25.00	23.50

GN15

Goose neck 5/8" male to 5/8" female 15cm long


\$4.95



GN33

Gooseneck 5/8" male to 5/8" female 33cm long

\$6.95



ROD IRVING ELECTRONICS

425 High St. Northcote 3070 (03) 489 8866 (03) 489 8131
48-50 A Beckett St. Melbourne (03) 347 9251

Mail Order and Correspondence
P.O. Box 235 Northcote 3070



To Order By Phone

Mail Order Hotline (03) 481 1436

POSTAGE RATES

\$1-\$9.99	\$2.00	\$10-\$24.99	\$3.50
\$25-\$49.99	\$4.50	\$50-\$99.99	\$6.00
\$100-\$199	\$8.00	\$200-\$499	\$10.00
\$500+	\$12.00		

(All above charges are for surface mail and some heavy items will vary from these rates.)

Cert. post for orders over \$100 included "free"
Reg. post for orders over \$200 included "free"
Account orders from schools, govt. depts., public co's., gratefully accepted. Min order amount \$20.00 (or a min. \$5.00 accounting charge will apply.) Comet Road Freight, Airmail etc. are extra



Errors and omissions excepted.



ACTIVE ELECTRONICS

289 LATROBE STREET, MELBOURNE 3000 PH. 602 3499

9am-5.30pm MON-THURS 9am-8.30pm FRIDAYS 9am-12noon SATURDAY

NOW OPEN

THE LARGEST RANGE OF COMPONENTS IN THE CITY

E.T.I.- E.T. & T.E. ELECTRONICS KITS.

COMPUTERS-DISC DRIVES-POWER SUPPLIES

-MONITORS - CRO'S-MULTIMETERS-TEST CLIPS

-LOGIC PROBES-INSTRUMENT CASES-TRANSFORMERS

-SOLDERING IRONS-TOOLS-CAPACITORS-RESISTORS

-CONNECTORS-BREADBOARDS-VERO BOARD-PCB ARTWORK

-ALARM SYSTEMS AND COMPONENTS- SPEAKERS

-RELAYS-OK WIREWRAP-IC SOCKETS

-KNOBS-CHEMICALS-POTENTIOMETERS-SWITCHES

-RESNETS-WIRE & CABLES-

TRIMPOTS-AUDIO AND

VIDEO CABLE

ASSEMBLIES-ETC.

OVER 2000 DIFFERENT TYPES OF SEMICONDUCTORS ALWAYS IN STOCK

MAIL ORDER HOTLINE. (03) 671137

ACTIVE ALL YOU HAVE EVER WANTED IN AN ELECTRONIC STORE - AND MORE!

ALL ACTIVE
LOW PRICES
INCLUDE SALES TAX

SEND FOR A NEW
PRODUCT CATALOGUE
ACTIVE ELECTRONICS
70c EACH

RING 602 3499
3 LINE ROTARY NUMBER
& 671137
DIRECT MAIL ORDER
HOT LINE

MAIL ORDER & SHOP SALES

MAIL ORDER & SHOP SALES

MAIL ORDER & SHOP SALES

MAIL ORDER & SHOP SALES

MAIL ORDER & SHOP SALES

Personal 'lap' computers banned on flights

Several US-based airlines, including the big operator Eastern Airlines, have banned the use of personal computers while their aircraft are in the air.

Airlines have taken the move because of potential hazards caused by the RF radiations from the computer. The move complements long standing bans against the operation of radio transmitters of all types while the aircraft is in the air.

At present, major aircraft manufacturers are planning comprehensive tests to see whether a permanent ban is necessary. The problem has only just surfaced because of the growing complexity of aircraft.

In the 'good old days' it was difficult for a personal computer to interfere with aircraft systems, either because they were mechanical rather than electrical or because all the electronic systems were crowded up into the nose.

But the latest generation of aircraft are just like flying computers. The Boeing 767, for instance, has some 107 microprocessors scattered around the airframe, all taking to each other, and all vulnerable to low level RF radiation.

According to Tony Hill, of



Ansett, the trouble was first suspected when it was established that the in-flight operation of a personal computer had interfered with the cabin pressurisation system of a 767. There have been allegations that navigation systems have been interfered with, but until now there has been no proof.

Australian airlines are adopting a wait-and-see approach. As general policy, Ansett cabin staff have been instructed to ask pas-

sengers to refrain from operating computers in the air. They are also carrying out their own in-service checks on the 767. The current view is that the Boeing 727, which is the result of 20-year-old technology, is not sophisticated enough to be vulnerable.

No other Australian airlines have yet introduced a ban on the use of personal computers, but they are all watching the situation closely. The International

Air Transport Association (IATA) has a technical committee looking at the question at the moment, and no doubt its recommendations will seriously influence the course of events.

In the meantime, not all airlines are taking the situation seriously. United Airlines, another big US operator, is offering its passengers free in-flight video games as a sales gimmick. They are specially built into the food trays on its DC 8 airliners.

Universal EPROM programmer

AJ Distributors has just announced the release of its latest import, the Digelec EP-804 universal EPROM programmer and simulator.

According to Digelec, the EP-804 can accept over 90 different types of EPROMs without additional hardware. It combines simplified programming methods with comprehensive data handling and editing functions. All the programming algorithms are software-controlled so the need for hardware adaption is avoided.

The EP-804 has an RS232 interface port with which it can communicate with a host computer. It can handle baud rates up to 19.2K.

There is an EPROM simulator in the EP-804 which can be used for the development of programs. This on-board RAM has a 300 ns access time, so it can simulate the fastest EPROMs. RAM space is 32K.

For more information contact A. J. Distributors, 214 Lyons Rd, Five Dock NSW 2046. (02)712-1077.



The EP-804 EPROM programmer and simulator.

Tell them you read it in ETI

Mini-pak

Pulsar Electronics, a manufacturer of STD buss micros has announced the release of its mini 'Mini-Pak' series of micro-computers.

The systems can be configured using a number of combinations e.g: twin 1.3M 5 1/4" hard disk drives or 15M hard disc with 1.3M back-up drive. Each system contains a four way STD buss ac card cage to enable the use of Pulsar's 256K RAM card and auto dial/auto answer



modem card (along with 1800 different STD cards available world wide).

The Mini-Pak uses the Pulsar Little Big Board as the CPU and runs various operating systems such as CP/M 2.2, MP/M II, CP/NET and Pulsar Turbodos.

Under Turbodos, multi-user or network systems to 512MB are available with upwards of 200 users.

For further information contact **Pulsar Electronics, Lot 2, Melrose Drive, Tullamarine Vic 3043. (03)330-2555.**

Software battlefield

According to a US market research firm, a lot of apparent benefits are going to wind up surprising software industry players who welcome them.

One example of this is 'hard' software — software produced on silicon chips. Software publishers tend to view this favorably since it seems to promise a reduction of the illegal copying that accounts for up to 50% of the software in use today.

However the report points out that it will transfer software publishing power into the hands of the hardware manufacturers. It predicts that machines like Apple's Lisa are the wave of the future and independents will be reduced to OEM'ing for the hardware suppliers or looking for a niche market themselves.

Teledistribution, the downloading of software in lieu of multi-copy publication, could spell the end of the retail shop when high speed downloading direct to end users becomes widely feasible.

Apple sound

Thinking Systems has announced that they are to be sole distributors of the DX-1 sound processor.


The DX-1 is a new product for the Apple II for recording, processing, and playing back ordinary sound. With the DX-1 sound can be entered, saved,

processed, sequenced, played, and generally modified under computer control in ways never before possible. While other systems generate and produce computer sound, DX-1 works with real sound, entered directly by a microphone or another source.

Sounds are converted to digital data through a high speed analogue-to-digital converter; software routines are then

selected (or programmed) for playing and sequencing the sound data; the data is then output to a digital-to-analogue converter where sounds are reconstructed. The software can speed up, slow down, play backwards, forwards, and sequence sounds in any way.

For more information contact **Thinking Systems, P.O. Box 260, Cammeray NSW 2062. (02)90-6868.**



AUS TOS

Many microcomputer users can now send and receive telexes without the added expense of installing a separate telex machine.

Sydney-based communications specialist, Offcom Pty Ltd, has developed a new version of its successful TOS (Telex Operating System) designed to suit most MS-DOS/PC-DOS micro-computer systems.

The sophisticated TOS system from Offcom allows the user to create and format messages on

the microcomputer — either within the existing word processing package or from within TOS.

While TOS is activated the microcomputer becomes a multi-tasking machine capable of handling separate tasks at once. The operator can be preparing one telex on the screen while a second message is being transmitted and a third being printed.

Incoming calls are received and stored on diskette and out-

going calls are scheduled for later transmission. The messages can then be easily accessed and used at a later date — incorporated in a report or similar word processing document — without any rekeying, simply by using whatever word processing package runs on the micro-computer.

Up to 1000 frequently called numbers and answerbacks can be stored and recalled by abbreviated dialling or mailcode addressing, eliminating the need to look up and key in these numbers.

Even though the system is capable of automatically handling all the telex functions, the operator has options available for over-riding control — the facility to change or cancel the priority of messages queued for transmission, start, stop and restart the transmission queue and search and display from the queue.

The TOS package for micro-computers will be available through microcomputer dealers and dealer enquiries are welcome.

For further information contact **Offcom Pty Ltd, 28 Chandos St, St Leonards NSW 2062. (02)438-4199.**

Microsoft for Apple IIc

Microsoft has unveiled a new version of the Microsoft Multiplan electronic spreadsheet software that has been specially modified to run on the new Apple IIc.

Multiplan, the leading spreadsheet program for the Apple II family, is ideal for a wide range of budgeting, forecasting, and other financial analysis tasks in a home or office environment. Commands are always visible on the screen so the user never has to guess what to do next. Other features include on-line help, the ability to link worksheets together, and the ability to sort columns of data.

This 1.07 version runs on the Apple II, II Plus, and IIc in addition to the Apple IIc. It takes full advantage of the computer's 128K RAM memory to allow for larger worksheets and runs on either 40 or 80 column displays.

Retail price for Multiplan version 1.07 is \$395. For more information contact **Microsoft at 1 York St, Sydney NSW 2001. (02)27-3571.**


First prize

A final year Electrical Engineering student at the Queensland Institute of Technology, Michael Philippi, departed on an eight-week advanced technology study visit to the USA on June 18 as part of an award for outstanding course project work involving computer aided design of a computer-controlled digital tachometer.

Michael of Wynnum in Brisbane, will visit the Semiconductor Products Division of Rockwell International at Newport Beach, USA. Rockwell is the prime contractor on the Space Shuttle and a world leader in advanced technology.

The award valued at \$6500 and including a Rockwell AIM 65-100 microcomputer, was donated by Energy Control, Brisbane-based distributors for Rockwell.

From L-R. Michael Philippi, Dr John Corderoy, Head of School of Engineering, QIT and Ken Curry from Energy Control.



SPHERE COMPUTERS

The CCT 100 Intelligent Terminal for Intelligent decision makers.

SPECIFICATIONS

Keyboard

- Detachable, compactive, typewriter-style keyboard
- N-key rollover with auto repeat capability
- 4 LED indicators for caps lock, on line, block mode and keyboard lock/protect
- Audible keyclick enable/disable
- Auto repeat enable/disable
- Keyboard lock enable/disable
- Repeat rate 20 characters per second
- 5 cursor control keys, 10 editing function keys with 14-key numeric key-pad

Communication

- Code: 128 ASCII characters
- Baud rate: 75, 110, 150, 300, 600, 1200, 1800, 2400, 4800, 9600, 19200
- Parity: odd, even, mark, space
- Operating Mode: full duplex, half duplex or block mode
- Interface: EIA RS-232C or 20-mA Current Loop

Emulation

- LEAR SIEGLER ADM 3A ADM 5A, HAZELTINE 1500, ADDS VIEWPOINT

Screen Presentation

- Display format: 24 lines x 80 characters
- Display unit: 12-inch, non-glare CRT
- Character type: 7 x 9 dot matrix
- Refresh rate: 50/60 Hz
- Character set: 96 ASCII characters, 15 graphic symbols, 32 control character symbols
- 5 screen attributes: blink, underline, blank, reverse, dual intensity
- Cursor type: selectable slow, fast blinking or steady cursor, block, underline or invisible cursor

External Control

- Power on/off
- Contrast adjustment
- Baud rate
- Parity and data format

- Refresh rate
- Half duplex or full duplex
- Auto line feed
- Auto new line

- EIA or 20-mA Current Loop
- Reverse video or standard video
- End of message
- Emulation mode



**ONLY
\$699.00**

+ Sales Tax if applicable
F.O.B. Ex-Sydney.

bankcard
welcome here

**AVAILABLE FROM OFFICES AND SHOWROOM PARIS RADIO ELECTRONICS,
SHOP 1, 165 BUNNORONG ROAD, KINGSFORD, NSW 2032. TEL. (02) 344 9111. TELEX AA22579.**

UNIVERSAL TEST LEAD KITS

P10190 Lead Set...\$3.95



DOUBLE POWER POINT

1-9 10+ P18030
\$6.95 \$5.95

DON'T FORGET TO CHECK
OUR STORE SPECIALS

WE WILL GIVE YOU
THE BEST DEAL ON
COMMODORE COMPUTERS
PLEASE RING BERNEICE
FOR THE BEST PRICE
POSSIBLE ON
(03) 489-8866


ELECTRET MIC INSERTS
WITH PINS FOR EASY
BOARD INSERTION



1-9 10-99 100+
\$1.25 \$1.10 \$1.00

**DON'T PAY TOO MUCH
BREADBOARD SPECIALS**

CAT.	No.	HOLES	COMP.	OUR
			PRICE	PRICE
P11000	100		2.95	\$1.50
P11005	640		8.95	\$5.95
P11009	840		14.85	\$10.95
P11012	1680		27.95	\$19.95
P11015	2420		45.00	\$29.95



**HALF HEIGHT
5" DRIVE SPECIALISTS**

	BARE DRIVE	WITH BOX + P.S.
MITSUBISHI		
M4851 500K BYTE	\$329.00	\$369.00
M4853 1M BYTE	\$359.00	\$399.00
M4854 1.6M BYTE	\$399.00	\$439.00

MP 5" STANDARD DRIVES

B51	\$0269.00	\$299.00
B52	\$349.00	\$379.00
B91	\$349.00	\$379.00
B92	\$439.00	\$459.00

ALL DRIVE PRICES INCLUDE SALES TAX

COMPUTER CABLES

QUARTZ CRYSTAL CLOCK MOVEMENT

- Very compact and reliable
- Self starting one-second stepping motor has strong torque
- Powered by 1.5V AA battery that lasts for a year
- Supplied with two sets of hands, one short and one long
- ± 15 second/month accuracy
- 56mm square, 15mm deep
- Complete with data sheet, instructions and wall hanger bracket
- Cat. XC-0100

\$14.95




T03 HEATSINK

1-9 10-99 100+
\$1.00 90c 75c



Errors and Omissions Excepted



T11302

UNIVERSAL SOLDERING IRON STAND

1-9 10+
\$4.95 \$3.95

DATA BOOKS, DATA BOOKS

YOU WILL NEED THESE FOR SCHOOL

FAIRCHILD CMOS	\$9.95
NATIONAL LOGIC TTL	\$9.95
NATIONAL LINEAR I	\$9.50
NATIONAL LINEAR II	\$9.50
NATIONAL CMOS	\$9.50
NATIONAL LINEAR APPLICATIONS	\$14.50

CHASIS PUNCH SET

(WE KNOCK A HOLE IN THE
OPPOSITION'S PRICES
ON THIS ONE) **\$16.95**



JOYSTICKS



(AS USED IN YOUR STANDARD COIN OPERATED MACHINE'S. THESE SHOULD GIVE YEARS' OF SERVICE AS USED BY THE PROFESSIONAL OPERATORS.)

2 WAY (2 MICROSWITCHES)	1-9 21-50 18-50
4 WAY (4 MICROSWITCHES)	23-50 19-50

DIP SWITCHES 4 WAY \$1.00
8 WAY \$1.50

AA NICADS 1-9 10-99 100+
1-75 1-60 1-50
NORMALLY \$2.50 EACH


BARGAIN HUNTERS CORNER

(GET YOUR BIG GAME HERE)

THE STING DISK FOR MICROBEE™ 50 only in stock WAS \$395.00 NOW \$195.00. GET IN QUICK.

5 CP-80 RIBBONS FOR \$49.50 (HOW DO WE DO IT?)

NEON TEST SCREWDRIVER
WE HAVE ZAPPED THE PRICE TO 75 CENTS



**OUR NEW RANGE OF OSCILLOSCOPES
is in stock**

15 MHz AC-DC PORTABLE	\$695.00 Including Tax
20MHz Dual Track	\$495.00 Including Tax
45MHz Dual Track	\$995.00 Including Tax

Probes are extra at \$29.50 each

BUY IN LOTS OF 10 AND SAVE

PIC A PAK SPECIALS

10 2SJ49 for \$49.00	10 74C926 for \$59.00
10 2SK134 for \$49.00	10 2732 for \$49.00
10 2N3055 for \$7.50	10 2764 for \$79.00
10 BUX80 for \$39.00	10 74LS245 \$12.00
10 BD139 for \$3.90	10 4164 for \$69.00
10 BD140 for \$3.90	10 7400 for \$2.90
10 RED LEDS 5mm .90	10 H1044 DELUXE
10 GREEN LEDS \$1.40	METAL CASES for \$49.50

LINE FILTERS 3 AMP 240 VAC.
\$11.95



**JUST ARRIVED
NEW DIGITAL MULTIMETER**

PUSH
BUTTON
CONTROLS
BUT UNDER
\$60.00



**WOW!!!
10 AMP**

1-9 10+
59-95 52.50

MN3001
(SCOOP PURCHASE FOR OUR KITS)
NORMALLY \$19.95

THIS MONTH

1-9 10+
\$12.95 \$10.95

BUCKET BRIGADE IC'S
SAVE, SAVE, SAVE,
EX1 IC EXTRACTOR

DON'T DAMAGE YOUR IC'S WHEN YOU
HAVE TO PULL THEM OUT.

1-9 10+
\$1.20 .95

2K OHM MULTIMETER
11 RANGES POCKET SIZE



SPECIFICATIONS

11 RANGES

DC VOLTAGE: 0-10-50-250-1000 volts
2000 ohms/volt

AC VOLTAGE: 0-10-50-250-1000 volts
2000 ohms/volt

DECIBELS: -10 TO +22dB in four ranges

OHMMETER: 0-10 k/ohms, 0-1 megaohms

DC CURRENT: 1-100mA

NORMALLY \$14.95

THIS MONTH \$9.95

BUTTON CELLS

FREE CHART ON WHAT THEY FIT. CHARGE
YOUR FRIENDS \$4.00 TO FIT THEM INCLUD-
ING THE BATTERY FOR FIVE MINUTES WORK.

SG13/G13	1-9 1.50	10+ 1.00
SG12/12	1-9 1.20	10+ .80
SG10/G10	1-9 1.20	10+ .80
SG3/G3	1-9 1.20	10+ .80
AG13/LR44	1-9 1.00	10+ .75
AG12/LR43	1-9 .75	10+ .60



HI WATT BATTERIES

WE JUST LANDED A TONNE OF THESE LITTLE
"HEART" STARTERS TO CHEAP THAT YOU
CAN THROW THEM AWAY AFTER USING THEM
ONCE IF YOU WANT TO.

AA	1-9 15c	10+ 10c
C	20c	15d
D	25c	20c
9V	40c	30c

SOLDER CENTRONICS PLUGS

(UNREAL PRICE. BUT
ABSOLUTE TOP QUALITY)

1-9 10-99 100+
\$6.95 \$5.95 \$4.95

NORMALLY \$14.95. (OUR OPPOSITION
CHARGE UP TO \$19.95. ARE YOU PAYING
TOO MUCH FOR OTHER PRODUCTS FROM
THEM AS WELL.)



ROD IRVING ELECTRONICS

425 High St. Northcote 3070 (03) 489 8866 (03) 489 8131
48-50 A Beckett St. Melbourne (03) 347 9251

Mail Order and Correspondence
P.O. Box 235 Northcote 3070



To Order By Phone

Mail Order Hotline (03) 481 1436

POSTAGE RATES

\$1-\$9.99	\$2.00	\$10-\$24.99	\$3.50
\$25-\$49.99	\$4.50	\$50-\$99.99	\$6.00
\$100-\$199	\$8.00	\$200-\$499	\$10.00
\$500+	\$12.00		

(All above charges are for surface mail and some
heavy items will vary from these rates.)


Cert. post for orders over \$100 included "free"
Reg. post for orders over \$200 included "free"
Account orders from schools, govt. depts., public co's., gratefully accepted. Min order amount \$20.00
(or a min. \$5.00 accounting charge will apply.) Comet Road Freight, Airmail etc. are extra.



8 PEN MULTI COLOR PLOTTER

at an affordable price

NEW



National A-3 Type Digital Plotter
VP 6802A

1. MULTICOLOR HIGH SPEED PLOTTING

**EIGHT COLOR GRAPHICS AT
450mm/sec
(18 inch/sec)**

The high plotting speed of 450mm/sec (18 inch/sec), the variety of pens (fibre, ball point, plastic tip) and colors allows great versatility in the creation of graphs.

2. SIMPLE PROGRAMMING A VARIETY OF INTELLIGENT FUNCTIONS

The high level of intelligence built into this Digital Plotter greatly simplifies the programming required to generate the complicated engineering drawings or business charts.

3. RELIABLE PAPER SECURITY

**ELECTROSTATIC PAPER
HOLDING**

The highly reliable, electrostatic paper-holding method guarantees secure paper holding, which is applied by simple switch operation.



4. QUIET MOVEMENT AND SAFETY

**DESIGN CONSIDERATION
ON MECHANICAL
CONSTRUCTION AND
SOFTWARE PLUS
PROTECTIVE COVER**

The detachable plastic cover assures durability and safety while suppressing the movement noise substantially.

5. CONTINUOUS PLOTTING

**AUTOMATIC CHART
ADVANCE "OPTION"**

By combining the automatic chart advance option, this plotter can function in a totally unattended mode. This makes it possible to build up fully automatic drawing system which does not need any human care.

6. COMPUTER INTERFACES

THREE TYPES

Eight bit parallel, RS-232-C and GP-IB interfaces are able with VP-6802A. The above interfaces allow the plotter to be used as a computer graphics device as well as an instrumentation graphics device.

CICADA 300 Baud DATA MODEMS



- CICADA 300
- CICADA 300T with telephone
- CICADA 300 for use with Commodore 64 and Vic 20 computers



CENTRE INDUSTRIES

**ELECTRONICS &
TELECOMMUNICATIONS
EXPERTISE**

187 Allambie Road,
Allambie Heights,
NSW 2100.
P.O. Box 184, Brookvale,
NSW 2100.
Telephone: (02) 451-5555
Telex: AA22671

*Dealer enquires
welcome.*

Scientific Devices Australia Pty. Ltd.

2 Jacks Road, South Oakleigh Vic. 3167 Phone: (03) 579 3622
31 Halsey Road, Elizabeth East, S.A. 5112 Phone: (08) 255 6575
559A Willoughby Road, Willoughby N.S.W. 2068 Phone: (02) 95 2064



HAVING BEEN programming for several weeks now on the new British-made Memotech MTX500, I still find I am only scratching the surface of the graphics and sound possibilities of this quite compact and very light piece of computing machinery. Manufactured near Oxford in the UK, it is obvious that a great deal of thought has gone into the design of this Z80-based machine.

Available in two models, one has the choice of 32K or 64K (the MTX512) of RAM as standard, with a whopping 512K as the upper limit using optional extensions. This is accomplished by "paging". This facility also allows the MTX to operate in the normal BASIC mode via monitor/interpreter in ROM from address 0000, or in a CP/M mode where RAM occupies these lower addresses. An additional option is 'silicon disks' which are RAM boards that emulate a disk configuration but operate much more quickly. Up to 32 megabytes of storage may be obtained using this feature.

A most important attribute of the MTX is that video RAM occupies a separate 16K from that of the user; ie: virtually all of RAM is useable by the operator, a facility not offered by many other economical computers. (This does have a slight disadvantage insofar as making video RAM less accessible).

The microprocessor is a Z80A, operating at 4 MHz. The MTX has been designed with CP/M as a final objective so as to take advantage of the vast quantities of software available. For this configuration one has the option of using either floppies or Winchester disks for mass data storage. At this clock speed, the Z80A of the MTX is somewhat faster than the Commodore 64's 6502 processor in BASIC programs, but not quite as fast as that of the BBC.

Since this computer only appeared on the UK market late last year, and recently in Australia, much of the peripheral equipment is still in the process of being released. However, already there is a range of both hardware and software available including a word processor and an extensive range of games. Although my contact with the word processor has only been short, it seems adequate for most requirements, being based essentially on the popular "Wordstar" format and providing the normal menu-driven editing facilities. As a 'Zardax-ophile', I am hopelessly biased in commenting.

Memotech's version of Frogger, "TOADO", comprises some 8K bytes of assembly language programming. The Chess tape is particularly detailed, taking 105 seconds to load, even at the MTX's very fast cassette rate of 2400 baud. The

baud rate is adjusted by POKEing a location in RAM, given by the list of system variables in the manual. (A niece of mine, although unable to beat the machine, was able to extend the MTX games to several hours. A tutorial is also included.)

Graphics use

As a personal application, I have been able to utilise the extensive graphics capabilities in several areas of electronics problems. Multicolour graphics of load line analysis for a transistor amplifier, as well as the circuits themselves, were easily obtained from BASIC by use of such standard commands as CIRCLE, PLOT, LINE. Similarly, using the 100-hour in-built digital clock, I was able, in a few instructions, to program the MTX to display an analogue clock face with the position of the hands being updated each minute.

There are two graphics modes; text and multicolour, which can be controlled via assembly language or the BASIC commands provided. These include the GENPAT command for made-to-order sprites or characters, and others to control their movement.

There are 31 planes on which the sprites can be placed, with a foreground and background plane behind these. It is also possible to control the framing by a VIEW command which controls the window onto

BLACK MAGIC

The Memotech

Lance Wilson



The Memotech MTX500 has enjoyed a successful launch in the UK and is now available here. It has some unusual features not found on machines around the same market price. Worth a considered look.

these visuals. Display control is by a TMS 9918 chip.

With the virtual text and graphics screens which one can set up on the MTX, it is possible to switch between textual and display material under simple program control. Contributing to this ease of interaction is the built-in text handling language NODDY which is also accessed from BASIC. This language operates via virtual text screens, treated as pages which can be called by simple NODDY commands. Possible applications would include programmed learning material, providing text in accordance with response.

There is also the option of changing the character font to various foreign language alphabets.

Sound

Sound capabilities are amongst the best around at the moment. The chip used is the 74689A (three tone channels and one noise), as used in the BBC machine, but MTX BASIC lacks the ENVELOPE command. However, programming sound is far easier than with such computers as the Commodore 64, which has the more powerful SID chip, but a weak interpreter.

Envelopes may be implemented on the MTX, using normal BASIC commands. There are two SOUND commands, one

MEMOTECH REPORT SHEET

Processor	Z80A
Clock	4 MHz
ROM	24K
RAM	32K (MTX-500), 64K (MTX-512)
Video RAM	16K (does not rob user RAM)
Languages	MTX-BASIC (with MTX graphics) NODDY (11-command, easy-learn language) Z80 Assembler
Keyboard	79 keys, numeric keypad and eight function keys
Display	24 lines of 40 characters Up to 16 colours Up to 32 sprite characters
I/O	Cassette port (2400 baud max speed) Parallel I/O port Two joystick ports Audio output Composite video output RF output (for TV set) ROM cartridge port Centronics printer port
Options	Communications board (two RS232 ports). 'Oxford Ring' links up to 255 units. PASCAL and NEWORD (W-P) on ROM (for MTX-512) 80-column colour card RAM expansion to 512K Floppy disk systems: single and twin 500K drives (CP/M, with 80-column colour card, NEWORD and SUPERCALC) Hard disk system: 10, 20 or 32 Megabytes Silicon disk: 256K RAM that operates as a super fast disk
Price:	MTX-500: \$699 (32K) MTX-512: \$849 (64K)
Supplier	Interfaceware, PO Box 214, Lindfield NSW 2070. (02)46-4374.

with the three parameters of channel, frequency and volume which is useful for slotting any bursts of tone into games programs, for example.

The other command has seven parameters, the additional ones being frequency and volume gradients, plus duration and chaining. With this very functional command and a bit of arithmetic, one may easily string an envelope together. Having recently purchased a piano-type keyboard, I am currently working on having the MTX work as a fully programmable synthesiser.

Since some of the parameter ranges mentioned in the manual seem to be in error, a bit of experimentation is worth trying when using these commands.

Probably the aspect of the MTX that most qualifies it for criticism is the BASIC interpreter, being a somewhat primitive implementation using "LET" in its assignment statements. The number of commands is also rather meagre, (except in the area of graphics), when compared with common benchmarks such as Tandy's Extended Colour BASIC or the regular Microsoft implementation. One command sorely missed is line renumbering. However, a useful programming facility is that the user has the option of entering abbreviated versions of commands. Using Memotech's example:

```
if x = 5 t.g.500
comes up as  IF X = 5 THEN GOTO 500
```

Manual

The "BASIC Tutor, Reference & Operator's Manual" has a very adequate technical description and explanation for the use of graphics and sound commands but tends to be insubstantial as the claimed "BASIC tutor". The first mistake was probably in the concept of a "combine everything" book rather than segmenting the various sections of the title between three different covers.

By splitting into sections, the task of revising (or even scrapping and rewriting) various areas would have been made easier, to the user's ultimate benefit. This manual does need a rewrite, with more information required on those areas where the programmer can take advantage of the machine's obvious strengths.

For a start, there should be a section on

utilising the ROM subroutines and material on directly accessing video RAM from BASIC. Since an emphasis of design has been ease of assembly language programming via BASIC, it seems a little shortsighted not to have provided extensive documentation for its use. But then, manuals with most machines are a whole lot worse.

Nevertheless, it is reassuring to see that in the various UK computer magazines, a substantial amount of independent writing on the Memotech by authors such as Keith Hook (eg: in *Personal Computing News*) has already appeared.

A significant factor in buying a computer should be the quantity of backup literature available and articles by such erudite and knowledgeable writers as Hook are an important aid in getting the most out of any computer. Much of the ageing BBC computer's success has been due to the enormous numbers of books and magazine articles that it has inspired. This can be an important aid in getting the most out of any computer. Much of the ageing BBC computer's success has been due to the enormous numbers of books and magazine articles that it has inspired. This can be thought of as one example of the importance of *software* in choosing a computer. It is this factor (as well as its powerful BASIC) which keeps the BBC from sliding into overpriced obsolescence.

The aforementioned BBC BASIC is a dialect that Acorn wrote for its BBC machine which provides an element of structure and facilities not so far equalled elsewhere in this language. Unfortunately, the BBC is currently somewhat overpriced, particularly in Australia.

Since assembler operates many times faster than BASIC, it is an essential for use with any fast-moving display. Obviously, this immediately means *games* to most of you, but applications graphics that plot anything on the screen in a slow, laborious fashion have limitations. (Ever seen an Apple circuit-drawing program in action? Take your sandwiches).

Black mark to Memotech for not following that same route as Acorn and putting a large effort into BASIC interpreter development rather than only relying on CP/M to provide the wherewithal. It is interesting to note that Ian Sinclair, the fa-

mous Clive's brother, has already added the Memotech to his range of introductory books on computer programming.

For the serious

For all the inadequacies of the BASIC, the facilities available for the serious machine-level programmer are *second to none*. It is possible to incorporate assembly language subroutines into BASIC programs by just typing:

```
ASSEM <linenumber>
```

at the appropriate stage, keying in the necessary code, and returning to BASIC at the next line.

For debugging purposes there is access to memory locations and registers via the PANEL command, which also incorporates a disassembler to translate the machine code into assembly language. Thus, one is able to write a program just one level away from machine code, assemble it, and check its operation by single-stepping through each instruction, viewing the effect on registers and memory as you go.

It is probably as a *splendid graphics machine* with a powerful built-in assembler that the Memotech achieves top rating over many another computer in the under-\$800 price range.


One problem encountered, for which clarification is being sought from Memotech, is that commands for locating code at particular memory locations do not seem to operate as the manual states.

The Memotech, because of its many ancillary facilities such as the Assembler and the PANEL instruction, plus its capacity to be expanded to a full CP/M system, can be recommended to the serious (ie: machine code) neophyte programmer, as well as the businessman looking for a versatile, innovative system.

It is more state-of-the-art as an 8-bit machine than its somewhat cheaper competitors, such as the Commodore 64, Tandy Colour Computer or the Atari 800XL. It is potentially more powerful than those of its competitors with vaguely-defined limitations of compatibility, such as the pseudo-Apple Dick Smith CAT (ie: which Apple software will it run, like Zardex, and what accessories does it need to do it?).

Those in the computer marketing game who are ever ready to push the latest N-bit microprocessor would generally prefer that the customer forget the adage "software first, hardware second". However, CP/M, Apple and to a lesser extent Tandy, Atari and Commodore, are the most prolific sources of applications software (and textbook backup) for those who would have their computer perform useful functions, without extended forays into obscure and difficult programming.

Until the IBMs and look-alike challengers, as well as MSX BASIC machines such as the Spectravideo, have been around for two or three years, they will have a measure of difficulty in competing with CP/M for breadth of available software.



Pascal and beyond

Although the BASIC leaves something to be desired, Memotech has a Pascal option. This language, for the past ten years, has been the darling of academics who have been saying (and saying and saying) that it was the coming innovation that would sweep all other languages away. Since Memotech's implementation has only recently become available I have not had the opportunity to investigate it; hopefully it compensates for certain of BASIC's weaknesses.

Memotech's Pascal comes in a ROM pack, as does their FORTH. Because RAM can be slotted into page zero and the ROM can be extended, it is possible that independent software designers will supplement the interpreter with tape or disk languages similar to Simon's and BC BASIC available for the Commodore 64.

Hardware aspects

The keyboard is of a very high standard, set in a compact aluminium assembly which has the appearance of a professional terminal, similar to those appearing in so many offices these days.

Apart from its pleasing appearance, the black, satin finish has the practical spinoff of a greater heat radiation coefficient, resulting in more efficient cooling, assisted by the aluminium construction.

The MTX is so light and compact that it could almost double as a portable terminal, although the length somewhat precludes this.

A most annoying fault encountered on my particular machine is that certain keys have a degree of bounce if not hit carefully. Thus, "O" as in "LOAD" produces displays such as "LOOAD" or "LOOOAD", resulting in extra effort and concentration being required at the keyboard. Probably this could be eliminated by POKEing a location in RAM to extend the time interval between which the keys are strobed, but such information is not easily available. In other respects the keyboard sets a standard that other manufacturers should certainly follow, convenience being of the *first order*, with divisions of alphanumeric, eight function keys plus a numeric keypad with shifted screen editing functions.

Interfacing to the real world is provided by several ports; although RS232 is not built in as standard, the communications board option provides two of these and is fairly inexpensive.

There are two joystick ports which are wired to the Atari standard; printer connection is via a Centronics port.

There is an independent audio output for connection to a sound system.

One can view on either a TV or a monitor, the latter being via composite video signal; both are easy to read on the 40-column display. RGB output is an option which comes with the 80-column board (100 UK).

MEMOTECH BASIC

Command words

INPUT	ATTR	BAUD	ELSE
LIST	COLOUR	CLOCK	STEP
LOAD	ADJSPR	INK	CSR
PRINT	MVSPR	PAPER	DIM
OUT	SPRITE	EDIT	GOSUB
POKE	CTLSPR	GOTO	LLIST
READ	NODE	IF	NEW
SOUND	GENPAT	LET	ON
PLOT	RANGLE	LPRINT	PANEL
CODE	WINDOW	NEXT	RETURN
OFF	RESTORE	NODDY	SAVE
TO	SELECT	PLOD	DRAW
REM	EDITOR	PAUSE	FKEY
CLS	DSI	RAND	THEN
ASSEMBLE	AANGLE	RUN	CONT
AUTO	SNDBUF	STOP	CLEAR
VS	ARC	VERIFY	DATA
CRVS	LINE	CIRCLE	FOR

Operands

+	/	>	<=
-	↑	<	<>
*	=	>=	

Functions

AND	ASC	PI	SQR
ABS	RND	OR	USR
EXP	NOT	ATN	LEN
SGN	COS	LN	MOD
TAN	INT	SIN	
VAL	PEEK	INP	

Strings

CHRS	RIGHT\$	TIMES
LEFT\$	INKEY\$	GREAD\$
MID\$	STR\$	SPK\$

The MTX character set

Aside from the normal character set, the MTX-500 provides fonts for all the special letters and accents used in: English, American, French, German, Swedish and Spanish. However, there is a corresponding loss of certain mathematical and punctuation symbols.

Provision exists for mounting the communications board and an extension RAM inside the MTX keyboard chassis. Options such as the 80-column board would normally mount within the disk drive cage. A light pen input is also available on this particular board.

Further embellishing the mooted role of terminal is the "Node/Ring System" option which is only briefly detailed in literature accompanying my own machine. Modems and driving software should shortly be available and thus the MTX has prospective applications in office or educational networks, as well as providing communications access.

The price of the Memotech in Australia is about 35% higher than its UK pound equivalent. Not much when freight, duty/tax and the provision of local back-up is taken into account. Thus the Memotech price structure here can be seen to be a very fair one. Although the full CP/M system is not cheaper than equivalent Asian equipment, the MTX has already established a position in terms of the literature available; obviously it will still be around in two or three years when many of its competitors are but a memory.

For a machine costing not much more than half the BBC, the MTX packs a lot of clout.

MAIL ORDER

MAIL ORDER

MAIL ORDER

RITRONICS WHOLESALE PTY LTD

COMPUTER PAPER 9" x 11" 2000 SHEETS \$29.50 + TAX A BOX.

1st floor 425 High St. Northcote 3070 (03) 489 7099 (03) 481 1923 Telex AA 38897

BULK DISCOUNTS AVAILABLE
YOU WILL NEVER HAVE TO PAY FULL PRICE FOR COMPONENTS AGAIN

Wholesalers, Retailers, DEMs Please ring or telex for quotes.

MAIL ORDER TO P.O. BOX 235, NORTHCOTE 3070.

THIS MONTH'S SPECIALS

 1-9 10+
 C NICADS 3.50 3.30
 D NICADS 7.90 7.00

M4851 500K

\$260 + tax.

M2896-63
THE MITSUBISHI RANGE OF DISK DRIVES

 Slimline 8" Disk Drive, Double Sided, Double Density, No AC Power required, 3ms track to track, 1.6 mbytes unformatted, 77 track side, 10⁶ bit soft error rate.

\$525 + tax Box & Power supply to suit \$105 + tax

M2894

 Standard size 8" drive, Double sides, double density, 3ms track to track access, 1.6 mbytes unformatted, 77 track side, 10⁶ bit soft error rate.

\$525 + tax Box & Power supply \$105 + tax

M4854

Slimline 5.14" disk drive, Double sides, double density, 96 track inch, 9621 bits inch, 1.6 mbytes unformatted, 3ms track to track access, 77 track side.

\$325 + tax. Box & Power supply \$75 + tax

M4853

Slimline 5.14" disk drive, Double sides, double density, 1 mbyte unformatted, 3ms track to track, 80 track side, 5922 bits inch, Steel band drive system.

\$295 + tax. Box & Power supply \$75 + tax

**HI TECHNOLOGY
PRODUCTS AND
EXPERIENCE**

LINEAR REGULATORS

UA309KC	1.40	BU126	0.60
UA317KC	1.95	BU326	1.40
UA317UC	1.20	BUX80	2.00
UA494PC	2.60	2N3771	3.50
UA723PC	0.50	2N3772	3.50
LM396K	15.00	2N3773	3.50
UA7805KC	1.20	FN5000	1.10
UA7805UC	0.60	FN5007	1.10
UA7808UC	0.60	MAN74A	1.90
UA7812KC	1.20	MAN72A	1.90
UA7812UC	0.50	4N28	0.50
UA7815KC	1.20	4N33	0.70
UA7815UC	0.50	BDV64B	2.50
UA7818KC	1.00	BDV65B	2.50
UA7818UC	0.60	AD149	1.50
UA7824KC	1.20	25K134	3.50
UA7824UC	0.60	25J49	3.50
UA78L05AWC	0.27	W02	0.20
UA78L12AWC	0.27	W04	0.25
UA78S40DC	3.50	IN5401	0.10
UA7905KC	1.20	IN5404	0.12
UA7905UC	0.60	BC547	0.08
UA7908KC	1.20	BC548	0.08
UA7908UC	0.50	BC549	0.08
UA7912KC	1.20	C122D	0.65
UA7912UC	0.60	SC141D	0.90
UA7915KC	1.20	BU208	1.90
UA7915UC	0.50		

MEMORY SPECIALS

HYBRID REGULATORS

SH1605	\$9.50	27C16 CMOS PROM	\$9.50	74LS00	\$0.30
SH323C 3ASV	\$2.50	27C32 CMOS PROM	\$12.50	74LS04	\$0.30
UA78H05SC 5ASV	\$5.90	56725 2Kx8 RAM	5.50	74LS14	\$0.30
UA78H12SC 5A12V	\$5.90	2716 500NS	4.50	74LS30	\$0.30
UA78HGSC 5A variable	\$5.90	2732 450NS	5.50	74LS32	\$0.30
UA79HGSC	\$10.00	2764 450NS	7.00	74LS47	\$0.34
UA78P05SC 5A10V	\$10.00	4164 150NS	7.00	74LS90	\$0.26
		per 100 + @	6.50	74LS161	\$0.33

TRANSISTORS

BD139	0.23	1791	14.00	74LS244	\$1.50
BD140	0.23	1793	15.00	74LS245	\$1.50
MJ802	3.40	Z80 CPU	\$2.40	74LS366	\$0.45
				74LS367	\$0.40

SCOTCHCAL RANGE OF PHOTSENSITIVE PRODUCTS.

			Per Sheet	Per Box
8001	Red on Aluminium	250mm x 300mm	\$6.50	\$45.00 (10sh)
8001	Red on Aluminium	300mm x 600mm	\$10.00	\$48.00 (5sh)
8005	Black on Aluminium	250mm x 300mm	\$6.50	\$45.00 (10sh)
8005	Black on Aluminium	300mm x 600mm	\$10.00	\$48.00 (5sh)
8009	Blue on Aluminium	250mm x 300mm	\$6.50	\$45.00 (10sh)
8009	Blue on Aluminium	300mm x 600mm	\$10.00	\$48.00 (5sh)
8007	Reversing Film	250mm x 300mm	\$ 4.00	\$22.50 (10sh)
8007	Reversing Film	300mm x 600mm	\$ 8.50	\$48.00 (10sh)
8011	Red on White Plastic	250mm x 300mm		\$48.00 (10sh)
8013	Black on Yellow Plastic	250mm x 300mm		\$48.00 (10sh)
8015	Black on White Plastic	250mm x 300mm		\$48.00 (10sh)
8016	Blue on White Plastic	250mm x 300mm		\$48.00 (10sh)
8018	Green on White Plastic	250mm x 300mm		\$48.00 (10sh)
8500	1 Litre Developer			\$9.00 per bottle
8500	250ml Developer			\$2.50 per bottle
3900	Scotch Clear Finish	368gm Aerosol		\$10.00 per can

 All prices plus Sales Tax. Dealer and Trade inquiries welcome.
 Please note full range of products are available on order.
 Please contact Peter Jones on (03) 489 7099 for further information

GREAT FLOPPY DISCOUNTS

VERBATIM DISCS

5 YEAR DATALIFE GUARANTEE

MD525-01	Single Sided, Double Density	soft sector	\$27.50
MD525-10	SSDD 10 Sectors 40 Tracks		\$35.00
MD525-16	SSDD 16 Sectors 40 Tracks		\$35.00
MD550-01	Double Sided, Double Density		\$41.00
MD550-10	DSDD 10 Sectors 40 Tracks		\$41.00
MD550-16	DSDD 16 Sectors 40 Tracks		\$41.00
MD577-01	SSDD Soft Sect 80 Tracks		\$41.00
MD577-10	SSDD 10 Sectors 80 Tracks		\$47.00
MD577-16	SSDD 16 Sectors 80 Tracks		\$47.00
MD557-01	DSDD Soft Sect 80 Tracks		\$43.00
MD557-16	DSDD 16 Sectors 80 Tracks		\$43.00

8" VERBATIM

FD32-1000	Single Sided, Single Density	hard sector	\$33.00
FD32-8000	Single Sided, Double Density		\$54.00
FD32-9000	SSDD Critically Certified		\$53.00
FD34-1000	Single Sided, Single Density	soft sector	\$31.00
FD34-8000	Single Sided, Double Density		\$51.00
FD10-4008	Double Sided, Single Density		\$59.00
FD10-4015	Double Sided, Single Density		\$59.00
FD10-4026	Double Sided, Single Density		\$59.00
FF32-2000	SD FLIPPY FLOPPY		\$62.00
FF34-2000	SD FLIPPY FLOPPY		\$62.00
DD32-4000	Double Sided, Double Density	hard sector	\$53.00
DD34-4001	Double Sided, Double Density		\$41.00
DD34-4008	Double Sided, Double Density		\$41.00
DD34-4016	Double Sided, Double Density		\$41.00
DD34-4026	Double Sided, Double Density		\$41.00

Single Disc Packs 10% Extra

ALL PRICES + 20% S.T.


DIRECT IMPORT RESISTORS

1/4W Carbon Film E12 Values	per thousand	
50c/100		\$4.00/1000
1/4W Metal Film E24 Values	per thousand	
150c/100		\$13.00/1000
1W Carbon E12 Values	per thousand	
300c/100		\$28.00/1000

RITRON

*Low Price *High Quality *12 Months Warranty

Dual Trace Oscilloscopes

 Model
 OS-645
 15KV
 45 MHz
 &
 1mV/div


COMPLETE MODEL RANGE SPECIFICATION CHART:

MODEL	SCREEN	SENS	SIG DEL	TRIG DEL	B'WIDTH	T'BASE	TAX EXEMPT	CAT NO.
645	150mm	1mV	Y	Y	45MHz	0.2uS 0.5Sdiv	\$895.00	Q12110
620	150mm	5mV	N	N	20MHz	0.5uS 0.5Sdiv	\$425.00	Q12105
615S	95mm	5mV	N	N	15MHz	0.5uS 0.5Sdiv	\$615.00	Q12100

POINTS TO REMEMBER:

 Ex Stock
 12 Month Warranty
 High Quality Components

Direct Import

 Flat Face Internal Graticule Screen
 On View at our 2 Stores
 Our Eighth Year of Business

 ALL PRICES PLUS 20% TAX. TRANSISTORS PLUS 32.5% TAX.
 MIN POST \$3.00 Heavy Items Extra

FAIRCHILD DISTRIBUTORS.

RITRONICS WHOLESALE PTY LTD

MAIL ORDER to PO Box 235, Northcote 3070 Victoria.

Minimum MAIL ORDER \$20.00

MAIL ORDER

MAIL ORDER

MAIL ORDER

Introducing

MEMOTECH the MTX SERIES

**A World
Apart from
the Ordinary.**

48K (MTX500), 80K (MTX512), EXPANDABLE TO 512K RAM

Take a close look at the MTX 512 and MTX 500; which begins with the sleek black metal housing, the design is elegant in its simplicity. Remarkable for the power and complexity it represents.

MTX 512, 64K. MTX 500, 32K. USER RAM built in, with total expansion to 512K. And that doesn't include 16K of dedicated VIDEO RAM.


Speaking of video, the MTX starts off where other micros end up. Vivid screen capabilities with 256 x 192 pixels interference free high resolution graphics. 16 brilliant colours and 32 programmable sprites. Also the MTX has 8 separate definable windows on the world. Thus, you can manipulate spread sheets on the MTX and see the impact of changing variables in graphics at the same time. Far from ordinary as well are the built-in system outputs that come standard on the MTX. The Centronics parallel printer port, the two industry-standard joystick ports. The uncommitted parallel I/O port. The Cassette port with 2400 baud. Separate TV and Video Monitor Ports. The 4 channel sound hi-fi output. Plus a ROM cartridge port, optional twin RS232 ports on communications board.




INTERACTIVE LANGUAGES AND ROUTINES — A LOOK AT THE WAY ALL MICROS WILL ONE DAY PERFORM.

With the MTX, you can create and manipulate programs using four different languages interactively through the FRONT PANEL DISPLAY.

Housed in the MTX's 24K ROM is MTX BASIC "Extended Basic", MTX GRAPHICS, MTX NODDY an 11-command "Easy Learn" Language for children, ie "LOGO" and MTX Assembler, enabling programming in assembly language. Assembler/Disassembler tied to basic provides keyboard access to Z80 CPU STORAGE locations memory and program PASCAL FORTH are also available in ROM packs.



Also, a numeric keypad, eight dual function keys. Abbreviated basic commands, built-in Syntax verifier. Automatic cursor-honing to errors, auto-line numbering and automatic scrolling.



The 160 MEGABYTE CONNECTION.

Unbelievable expandability. Z80A Processor running at 4MHZ. FDX Floppy disk system single and twin 500K disk drives operates in CPM 80 Version 2.2 MDX HARD DISK system, 10, 20 or 32 Megabytes. SDX SILICON DISK (256K). Dramatically increases the efficiency of proven eight bit CP/M SOFTWARE to the speed of 16/32 BIT SOFTWARE levels and greatly reduces disk wear.

SYSTEM provides up to 160 Megabytes of storage capacity via twin RS 232 C. NODE Software and OXFORD RING Communications Network which links 255 units.

WORD PROCESSING PACKAGE FROM ONLY \$1,199 (EX. TAX)

The package includes A MEMOTECH MTX 512. The powerful NEW WORD (TM) Professional word processing software in ROM CARTRIDGE PLUS A correspondence quality printer, exceptional value.

A LOOK AT THE PRICE

There is one simple Equation for pricing, the more the engineering, the lower the cost.

MTX 500 (48K) ONLY \$616.00 (Ex. Tax)
MTX 512 (80K) ONLY \$745.00 (Ex. Tax)
SOFTWARE FROM ONLY \$19.95

Make no mistake. When you turn this page, you'll be returning to a world very different from this one. A world in which all microcomputers will suddenly seem very ordinary.

For more information and the location of your nearest dealer, contact —

interfaceware

P.O. Box 214, LINDFIELD, NSW 2070
or PHONE (02) 46-4374,

the sole Australian distributor for MEMOTECH.
DEALER ENQUIRIES WELCOME.
SERVICE NATIONWIDE

KNOW YOUR COMPUTER NUT

IT HAS LONG been a fascination of mine identifying computer owners by the environment they program (or 'hack') in and by the personality traits they exhibit in said environment.

On a recent visit to a nearby system, the decaying stench of week-old pizzas and salami-soaked carpet revealed to me a true purveyor of the age-old belief that *computing precedes all evils*. Interesting to note was the chaste state of the hardware — sparkling clean with listings well filed and disks locked with labels (gasp!) updated. Exhibiting startling contrasts of personality, we shall label this individual "Real Programmer, Class 1", or simply, RP1 (to employ the acronym form, of which computer people are so fond).

Near RP1 I found a hacker of a different nature. Given to arguing a lot, this type, in order to save money, has his system talking via jam tins and wet string over the back fence at 50 baud to a like soul. This individual is totally different and can only be labelled a 'Hacker, Class 1'. A classic case, where hardware is unimportant so long as it works and the disks can't be seen through. He has an introverted nature and won't even speak to the dog lest it asked him a question. But at the keyboard — a *whiz*! His environment is unique. To minimize labour, every peripheral is stacked on top of the other in a room that makes the average broom closet look *huge*. It is specifically designed to house a system and a person. No more. It has about ten locks on the paper-thin door as a safeguard against piracy. The floor is a myriad of old listings, supposedly in a logical order on the Coke-stained carpet, now impossible to see under the pile of footworn paper. The H1 writes machine code at a huge rate, completing a program in two hours flat (regardless of its complexity) and prefers to debug it months later. The software he has sold is never pirated and pays for a box of disks a year. He never smokes or drinks and drives other hackers to suicide with his never-ending borrowing of their magazines.


H1 and RP1 types have only one thing in common: *they wear T-shirts!*

Well-dressed hackers are different. Their system room has a floor unstained but lit-

tered with shirts, pants, ties, socks and shoes, invariably strewn over a floor heating vent. The room is normally huge and the air cold. Such individuals crave money and talk of very little else. They can be observed sleeping in computer club meetings pretending to be waiting for someone to employ them on a consulting basis. They

normally have pagers which they beep to check if they still work. We shall call this Herbert: 'Dressing Programmer, Class 1'.

The DP1 is often confused with the DP2, a man of achieved ambition who also sleeps in strange places. DP2 actually knows things and people. He has a pager which is turned off when he dozes through a monologue.



Do you know a 'Hacker, Class 1'?
How about a 'Dressing Programmer, Class 2'?
How do you become a 'Real Programmer/Hacker, Mark 3'?

Here's a humorous look at
the various 'classes'
of that modern phenomenon
— the computer nut!

Nigel Leith

DP1 types emulate DP2 and many clashes occur which the DP1 always loses, causing DP1 to move to yet another computer club with his wealth of sleeping knowledge.

A 'Real Programmer, Class 2' *never* goes to club meetings. He smokes incessantly, wears ties when asked and holed T-shirts when dress is unspecified. The RP2 has a

similar system room to the RP1, with notable exceptions. Primarily, there is a closed window, shuttered, inadequate ventilation and a constant pall of smoke in the room. An RP2's cigarette butts are balanced on the table. An RP2 types gently. Finances are dedicated to the system alone, which grows internally to mammoth proportions.


The RP2 enjoys scrapes with the RP1, questions a H1 until he cries, wakes up a DP1 with an illogical statement which the DP1 invariably agrees with, and ignores the DP2 for pure satisfaction. RP2s are rarely sighted as they mainly talk by phone and communicate via modem. When sighted they size up the second party until categorised and take the appropriate action.

An RP2 can be approached by a 'Hacker, Mark 2'. The H2 is a nondescript soul who has been writing code since diaper days. The H2 has a neat room, normally his bedroom, with disks in a magnetic eraser safe should people decide to steal software. He knows all systems, from their clock speed to what type of casters they have, and is a mine of information with low morals. Where the H1 tries to break into computer systems which are well-documented and publicised via a cheap modem, the H2 backcharges OTC 'phone bills to an Australian system previously broken into with a second auto-dial modem attached to a remote node on the system which the engineers forgot to detach. The H2 normally has a good night when crossing the Pacific many times and closing his system down with all the used systems sending random data to each other and tying up all outside callers.

The H2 scoffs at all and regards anybody's software as public domain because he could write better code anyway. An RP2 is intimidated by an H2 and avoids the haunting hacker like the plague. Upon confrontation, the H2 downgrades the RP2 whilst the latter, exercising a superior wit, attacks all comments with a barbed tongue. An RP2 and a H2 ally only against DP1 types who unwittingly engage in futile conversations on expertise. After such talks, both the H2 and the RP2 leave the room in uncontrollable fits of laughter.

The H2 is normally morally bankrupt, untidy and unkempt. You'll find Coca-Cola bottles and glasses around the keyboard. The H2 prefers tea to coffee. The H2 enjoys \$2 dinners and doesn't smoke or drink much. The H2 is often confused with the hybrid 'Real Programmer/Hacker, Mark 3'.

The RPH3 is just as lunatic as the H2 in wit and nature, lapses between H1 introversion and H2 extroversion on occasions and



KNOW YOUR COMPUTER NUT


The RPH3 is only seen by visitation, voids clubs and burns magazines. The RPH3 enjoys music, food and Big M calendars almost as much as sleeping off hangovers. When programming, the RPH3 can carry on a conversation, change a tape,



Eccentricity makes the world go around, or so they say. Computing must keep the mice running up the treadmill. ●

Now's your chance! For 1 MONTH ONLY, we've slashed prices on a great selection of computer books. Top-selling titles . . . now at rock-bottom prices! You'll have to be quick, though — specials apply only during August 1984. Order now.

Two software boxes are shown. The top box is dark with 'apple basic' in white. The bottom box is light-colored with 'Mostly BASIC: Applications for TRS-80' in dark text. The TRS-80 logo is also visible on the bottom box.



All phone enquiries: (02) 663-9999, ext 242

SWIVEL BASE MONITORS FROM \$179 THIS MONTH

WHAT'S NEW AT ROD IRVING ELECTRONICS

Ritron 11 Monitors are now available to increase our range of Data Displays. They feature a unique adjustable swivel base that tilts forward or back 30 degrees and swivels right to left 60 degrees. Technical specifications are listed below:

SPECIFICATIONS — CRT SIZE: 12 inches non-glare 90 degree deflection **INPUT SIGNAL:** 1.0-2.5V p-p composite video signal **INPUT IMPEDANCE:** Normal 75ohm, high approx 50K ohm **INPUT TERMINALS:** RCA phone jack **RISE TIME AND FALL TIME:** Less than 25 us **VIDEO BANDWIDTH:** 20 MHz \pm 3dB **SCANNING FREQUENCY:** Horizontal, 15.75KHz \pm 0.5KHz; Vertical, 50Hz/60Hz **Horizontal Retrace Time:** Approx 8.5us **Vertical Retrace Time:** Approx 800us **PHOSPHORS AVAILABLE:** Amber, Green **RESOLUTION:** Centre, 1000 Lines, Corner, 800 Lines, Geometric distortion, 2% or less; Linearity, less than 2% **CONTROLS:** Front, POWER ON/OFF, brightness contrast, Rear, V-Hold, H-Hold, V-Line, V-Size.



AVAILABILITY: Green Phosphor in Stock \$179.00
Amber Phosphor Early March \$199.00
SCHOOL AND DEALER ENQUIRIES WELCOME

APPLE™ COMPATIBLE DISK DRIVE


TM
Registered trade mark
Apple Corporation

SPECIFICATIONS

HIGH-SPEED ACCESS, HIGH ACCURACY POSITIONING Instead of plastic CAM positioner or lead screws positioner, a high microprecision metal band positioner is adopted in the mechanism to position the head.
BRUSHLESS DC DIRECT-DRIVE MOTOR Direct drive means that there is no improper belt seating, so the variations in speed and friction-producing side loading can be eliminated, which allows motor running lifetime to be over 10,000 hours.
MOTOR CLOSED LOOP SERVO Hall effect devices are utilized as speed control sensor in DC motor system, so motor can run stably and accurately.
SLIM, HALF-HEIGHT DRIVE The disk drive is only 41mm high. It is only half the size of conventional models.
NO CONTACT WRITE-PROTECTED SENSOR Photo coupler is used as write-protected sensor. It means no damage, long lifetime and good reliability for disk media.
GENERAL SPECIFICATIONS
Capacity (formatted) 163K (20K bytes more than the original)
No. of tracks 40 tracks (5 tracks more)
No. of sectors track 13 to 16 sectors
Disk rotation speed 300 rpm
Track density 48TPI
Track to track time Less than 6 msec

\$289.00

**INCLUDES
CONTROLLER
CARD**



BARE DRIVE & CASE

\$269.00

**New Silent Drives On
The Way—Ring For A Price**

**OTHER CARDS
ALSO AVAILABLE.
ASK AT OUR CITY STORE.**

DO YOU NEED A CASE FOR A SINGLE BOARD COMPUTER


This stylish low profile case will give your system the professional look it needs. This case comes complete with an encoded, parallel output keyboard. The keyboard is in its own case attached via a coiled connector, so it can be placed for maximum comfort. Sit one of our new swivel monitors on top and make your system look like it's worth thousands. Cut outs are for 2 x 5 1/4 in Slimline disk drives.

GREAT FOR SINGLE BOARD COMPUTERS, TERMINAL CARDS, ETC.

CASE AND ENCODER KEYBOARD \$249.00 Tax Ex \$199.00

Dimensions:
Box W 450mm D 295mm H 110mm
Box Cat. No. X11080

Dimensions:
Keyboard W 450mm D 195mm H 40 (28mm)
K/B Cat. No. X11081




NEW VIDEO MONITORS

Get a clear honest image!

Computer data and graphic displays never looked better, brighter, sharper

High Resolution

• Recommended Display Characters:
1920 (80x24)



**SCHOOL AND CLUB BULK BUYS —
Please ring for pricing**

• High quality non-glare CRT • Compact and lightweight with all Controls inside Front Panel • All units 100% Factory Burned in • 800 lines centre resolution • Suitable for Apple* and other computers (Apple is a registered trademark of Apple Computer Company, Inc.) • Green or Orange Phosphor available • 18VHz • First shipment arriving middle of June, 1983 • Direct Import Price for June

**Green Phosphor \$189 (\$162 Exempt)
Orange Phosphor \$199 (\$179 Exempt)**

GREAT VALUE

ROD IRVING ELECTRONICS

425 High St., Northcote, Vic. 48-50 A Beckett St., Melb., Vic.
Phone (03) 489 8866, (03) 489 8131, Mail Order Hotline (03) 481 1436
Mail orders to P.O. Box 235 Northcote 3070 Vic.

'THE PRINTER PEOPLE' SPECIALS

AS REVIEWED BY EA NOVEMBER '83

**THESE ARE THE REAL THING.
NOT A CHEAP SUBSTITUTE.**

A NEW PRINTER NOW! CP-80/I, 80-COLUMN IMPACT PRINTER

SPECIFICATIONS

Functional Specifications

Printing method — Serial impact dot matrix. Printing format — Alpha-numeric — 7 x 8 in 8 x 9 dot matrix field. Semi-graphic (character graphic) — 7 x 8 dot matrix. Bit image graphic — Vertical 8 dots parallel horizontal 640 dots serial line.
Character size — 21mm (0.083")-W x 2.4mm (0.09")-H 7 x 8 dot matrix.
Character set — 228 ASCII characters. Normal and italic alpha-numeric fonts, symbols and semi-graphics.
Printing speed — 80 CPS 640 dots/lines per second.
Line feed time — approximately 200 msec at 4.23mm (1.6") line feed.
Printing direction — Normal — Bidirectional logic seeking. Superscript and bit image graphics — Unidirectional left to right.
Dot graphic intensity — Normal — 640 dots 190.5mm (7.5") line horizontal. Compressed characters — 1,280 dots 190.5mm (7.5") line horizontal. Line spacing — Normal — 4.23mm (1.6"). Programmable in increments of 0.35mm (1.72") and 0.118mm (1.216").
Columns/line — Normal size — 80 columns. Double width — 40 columns. Compressed print — 142 columns. Compressed double width — 71 columns. The above can be mixed in a line.
Paper feed — Adjustable sprocket feed and friction feed.
Paper type — Fanfold Single sheet. Thickness — 0.05mm (0.002") to 0.25mm (0.01"). Paper width — 101.6mm (4") to 254mm (10").
Number of copies — Original plus 3 copies by normal thickness paper.
Mechanical Specifications
Ribbon — Cartridge ribbon (exclusive use), black.
MTBF — 5 million lines (excluding print head life).
Print head life — Approximately 30 million characters (replaceable).
Dimensions — 377mm (14.8")-W x 295mm (11.6")-D 125mm (4.9")-H incl sprocket cover.

Parallel CP 80 \$339.00 Serial CP80 \$559.00

2000 Sheets "Keen Edge" Paper \$39.50

Minimum P. & P \$3.00. Errors & omissions excepted.
Please address tax exempt, school, wholesale and dealer enquiries

RITRONICS WHOLESALE

1st floor 425 High St. Northcote 3070 (03) 489 7099 (03) 481 1923
Telex AA 38897

ROD IRVING ELECTRONICS

425 High St., Northcote 3070 (03) 489 8866 (03) 489 8131
48-50 A Beckett St., Melbourne (03) 347 9251

Mail Order and Correspondence
P.O. Box 235 Northcote 3070

To Order By Phone

Mail Order Hotline (03) 481 1436



POSTAGE RATES

\$1-99.99	\$2.00	\$10-24.99	\$3.50
\$25-49.99	\$4.50	\$50-99.99	\$6.00
\$100-199	\$8.00	\$200-499	\$10.00
\$500+	\$12.00		

(All above charges are for surface mail and some heavy items will vary from these rates.)

Cert post for orders over \$100 included "free"
Reg post for orders over \$200 included "free"
Account orders from schools, govt. depts., public co's, gratefully accepted. Min order amount \$20.00 (or a min. \$5.00 accounting charge will apply.) Comet Road Freight, Airmail etc. are extra




ERRORS AND OMISSIONS EXCEPTED

More

ARCADE GAMES

Chopper — a rescue game. You have to rescue the hostages trapped on the ground without getting shot down by enemy jets or air-to-ground missiles. Based on a real life story . . .



— for

BACK in ETI November 1983 we looked at some of the then new games being sold for the Microbee. Most of them made good use of the computer's graphics system based on a programmable character generator (PCG). As the months rolled on many independent software writers learned to put the Microbee's PCG to good use. The result is a crop of new graphics games that have to be seen to be believed.

All the programs reviewed this month are distributed by Mytek of Western Australia, not because they're necessarily better than anyone else, but because they are the ones that I could get a hold of easily. At the moment there's not one computer shop in Hobart supporting the Microbee, so whatever new software comes along is either borrowed from someone or it arrives through the post.

Before getting into the programs themselves, perhaps we should briefly look at how the PCG works. Each location in the screen memory simply contains a pointer to some block of data that the Microbee's character generator accesses to make pretty patterns on the screen. In a normal 'Bee there are 1024 of these points, and the CRT controller chip determines the area of the screen for which each pointer will provide data. Usually there are 64 locations across by 16 locations down.

Microbee has a read only memory chip containing the data the CRT controller needs to make letters, numbers, and punctuations, and this is the one accessed when you are typing away on the keyboard. But if you send to the screen memory any character code higher than 127, it will switch from the character ROM and access the PCG instead. The nice thing about the PCG is

that you can record into it any character data you desire . . . italics, inverse video characters, or little squiggly shapes of any description.

A normal character cell is 16 dots high and 8 wide. This is arranged as a continuous series of 16 bytes, with bit 8 of the first byte located at the upper left hand point of the cell. Below it is bit 8 of the second byte, then bit 8 of the third, etc.

The contents of a character cell will appear on the screen at any location where there is a pointer byte asking for it. So if the pointers at the screen's four corners and the one in the centre all contain, say 35, then the contents of character cell number 35 will appear at those 5 locations. Now the beauty of the PCG system is this: if you change the contents of cell 35, what you see at those 5 locations will change as well, simultaneously, all five copies. So if you look at graphics games like kilopede for instance, you'll see things all over the screen changing in unison.

We will refer to the above system as 16 line graphics. But somewhere along the line somebody decided some interesting effects could be had if there were more than 1024 different locations to play with. So they changed the system to allow 2048 screen locations, 64 wide by 32 high. But with the number of dots remaining the same cell could only be eight dots high instead of 16. The extra screen memory was already in the Microbee, virtually unused, so all that was needed was to reprogram the CRT controller chip to the new standards. We'll call this alternative system '32-line' graphics.

The only real problem with 32-line graphics is that the Mixrobee's character ROM is still on the 16-line standard, so there's no

longer access to numbers and letters. But the solution is to simply abandon the ROM and program the letters and figures you will be using into 8 x 8 dot character cells, just like graphics characters. Ever wonder why the text in some of these games looks a little 'different'? Mytek's word processor contains its own upper and lower case character set to exploit this technique . . . that's how they get 32 lines of text onto a Microbee screen.

You can't say that the 16-line or the 32-line system is 'better'. Which one is used in a game depends mostly on the shape of the most important characters to be displayed. Now on the games:


Chopper

Word has it that this one was based on the abortive American attempt to rescue their imprisoned hostages from Iran using a fleet of helicopters. You lift off from your home base in your trusty Jet Ranger and fly out over enemy territory. On the ground below you are the hostages, waving madly for help. You fly on and on as a panorama of buildings sweeps below you; the entire layout being several times as wide as one Microbee screen. You can fly your chopper with either a joystick or the keyboard.


As you fly along, enemy jets attack you and ground-to-air missiles shoot up from below. Contact with either of these results in the demise of your chopper. You can fire back at the planes, or drop bombs on the missile sites. When you find a group of hostages, you land near them and eight of them jump aboard your chopper. You must then ferry them back to base before coming back for more.

The game uses 32 line graphics and

A review of some new arcade-style games using the Microbee PCG. A look at how they work and how you can play.




Another rescue game. Take your craft from the mother ship (top left) to the landing pad, pick up a man and return without getting hit by a meteor or missing the docking. Lively graphics on this one.



Centipede invaders! A variation on space invaders; #2074. This is Kilopepe. Use your battle-beetle to zap the centipedes, caterpillars, fleas and spiders. Lose — and a big foot comes down to squash you! Seen that in a dingy arcade somewhere . . .

Pack 'em in, chomp em up! Ghost Muncher — a variation on the popular Pac Man. Like Kilopepe, this game is very smooth and easy to get along with. And very inexpensive.



the Microbee

Tom Moffat

moves along very quickly. If you think it sounds like pretty good stuff, wait until you see the same thing on an Apple or a Commodore 64. The chopper moves with inertia as would a real one, and as it moves forward it drops its nose in the usual way, allowing you to shoot things on the ground with your forward cannon. And when your chopper is full, the remaining hostages wave goodbye to you. Now that's real class! But they use a lot more memory and cost up to three times the price of the Microbee version.

Chopper is the kind of game that will impress the hell out of people, especially non-computer people, when they first see it. But, if you're like me, the newness will wear off and you'll soon tire of it. In that case it's probably better that you paid \$20 instead of \$65, and the game is still there if some non-believer needs impressing.

Meteor Rescue

This program is based on a similar arcade game. It's another rescue operation like Chopper above, but there's a little show built in that will delight the kids.

At the top of the screen (see the picture) is a mother ship containing a rescue landing craft. On the surface of a planet, (or is it a meteor?), are two platforms, each with three little men awaiting transport to the mother ship. You guide the landing craft down through a cluster of spinning geometric shapes (like in the Asteroids game) to the three landing pads below. If you hit an object, or miss a pad, you blow up with a most frightful noise.

When you succeed in landing, everything stops while one of the men moves forward onto a little lift that lowers him down to the

landing pad level. He then trots over to the rescue ship and climbs aboard. During the journey back to the mother ship the space objects again threaten, but now you can fire at them and blow them away. If you fail to accurately re-dock with the mother ship, it's curtains once again.

The attraction of Meteor Rescue is much like Chopper. It's got good lively graphics (16-line), and that clever little show as the lift lowers the people to the ground. But as for sitting in front of the computer for hours playing it, well . . .

Kilopepe and ghost muncher

I'll treat these two as a pair, because that's the way they're being sold . . . two for the price of one. Both are written by Matthew Hickey and they're very similar in appearance. Kilopepe is the arcade game 'Centipede' and Ghost Muncher is an implementation of 'Pac Man'. Both use 32-line graphics.

In Kilopepe, centipede-type objects stream down through a field of mushrooms, and you control a little battle-beetle at the bottom. He does the shooting. As you blast away at the marauding centipedes they split apart, turn into mushrooms, or sometimes turn into longer centipedes made up of individual cells. If you hit the first of a string of them the rest follow to oblivion, a wholly satisfying experience for the beetle.

As your score increases other baddies appear . . . caterpillars (that look more like boomerangs), fleas, and spiders. The fleas drop down the screen leaving a trail of mushrooms, and you can sometimes get below a flea and shoot it for points. If you're not quick enough, you die. The spider

ers bounce along the bottom of the screen and you must get under them to exterminate them, otherwise you die. If any bits of centipede make it to the bottom of the screen without you getting them first, you die. Your death comes straight out of a Monty Python film: a big human foot that goes "squash"! Too bad there's not the appropriate sound effect to go with it.

Ghost Muncher is pretty well classic Pac Man, although with power steering. As you move around the maze, you don't have to hold keys down, you just touch one to change direction. Your muncher never stops except when he gets stuck up against a wall; a technique you can sometimes use to attract monsters before you go on the attack. When you eat a "power pill" they become sedated and you can chomp away at them until they revert. Each monster destroyed from one power pill gives twice the score of the one before, so it's to your advantage to try to get them grouped together near your before eating the pill.

Kilopepe and Ghost Muncher are good illustrations of the use of the Microbee's PCG. In Kilopepe there is only one character cell describing the shape of a mushroom. But mushrooms appear all over the screen, at each place the screen memory points to "mushroom". If you changed the data in the PCG and turned the mushroom shape upside down, every mushroom on the screen would be upside down.

Likewise there is only one centipede shape, sometimes appearing on the screen as a single cell, or strung together to form a complete centipede. But every screen location pointing to "centipede" shows the same shape. The program can move the centipede around by erasing cells in one

MICROBEE ARCADE GAMES

screen location and re-writing them in another.

Ghost Muncher works in the same way . . . the monsters may move anywhere on the screen but they all look the same. The muncher running around the screen is the same as the one on the sidelines waiting for action.

Both these games are very smooth and easy to get along with; a credit to their author. I've never heard of this Hickey fellow but his programs published so far have real class and elegance. Maybe Mytek is under-selling him at \$10 a program. There is one fault in them . . . they disappear when you turn the computer off. Most Microbee software takes advantage of the battery-backed memory, so the programs restart when the computer is switched on, sometimes displaying previous high scores. It's also convenient when you want to leave a game in the computer for the kids.

Emu joust

A strange one, this. A floating shoot-em-up game in the Kingdom of Nordrill, again based on a standard arcade game. You control a flying emu, complete with rider and lance. You can move left and right, and up the screen by 'flapping' you wings. If you stop flapping you sink down again. The emus sort of dissolve onto the screen from the centre of platform. The picture with this article shows an emu 'forming'. Once you are complete you move around bumping into the dreaded Vulture Knights of Drass. Whoever is higher on the screen wins the joust. If you lose you die. If the vulture loses he turns into an egg which you then squash for points.

The graphics behave in a very unusual way. Every movement takes time to get

going, and more time to stop. In other words, everything has inertia, making what sounds like a trivial game into a real test of skill. Even the eggs bounce when they fall off a platform onto the ground.

Emu Joust is slow, although hard to master because of the floating motion. Mytek bills it as 'relaxing'. It's one of those games where you find yourself applying body English to make things move the way you want them to. It's not guaranteed that you'll immediately fall in love with Emu Joust, but it's the kind of game that will probably have a devoted band of followers.

One interesting mode of play is to get the emu down to the lowest level and then just sit back and watch. Eventually vultures will join him there, and since they're all on the same vertical level, all jousts are draws. So the participants simply scuttle around prodding each other in the backside with their lances, which is worth a few laughs. But if you 'flap' at just the right time you'll knock about three vultures over in one hit.

Star striker

It's Star Wars! That's what my five year old son said when he first saw Star Striker running. And it's exactly the impression the program is trying to get across.




In Star Striker you are inside the program, looking out (shades of TRON —). The screen is the window of your starship; at its centre are crosshairs. You go screaming through a cloud of stars, hunting down and blasting the ships of Darth Vader's fleet.

When I first saw the program I asked, "Is that all it does?" But then it sort of grows on you. Like one night when I was researching this article. A Tangerine Dream record playing on the stereo. One hand was wrapped around a stubby and the other around the joystick. The cockpit lights lowered and the amber monitor softly glowing with images of Darth's battle cruisers dropping like flies; ZAP-ZAP-ZAP!

With your joystick (or keyboard) you are actually flying your craft, with the clues to its attitude and position coming from the stream of stars you're flying through. The joystick controls their path, and the illusion is of you moving through the stars, instead of them moving past you.

On one occasion I noticed that it seemed easier to shoot enemy ships if my own ship was spiralling slightly downward and to the right. But as I stared at the screen I developed a slight feeling of nausea and dizziness . . . the damn thing was making me airsick!

Star Striker uses animation techniques to produce a very fast illusion of enemy ships approaching or receding from your own ship. The series of three pictures with this article show the screen appearance over a period of about a tenth of a second. In that time, three enemy ships appear, move closer, and then move nearly off the screen. Eventually, after the game has been running for awhile, one of the enemy ships will not move away, but will try to ram you. You





Phantoms ahead! Three screens from Star Striker, about 1/30th-second apart, illustrating the animation technique employed.

have a split second to dodge it; I've never yet succeeded. When the collision occurs the screen erupts in a blinding flash, the computer beeps, and then you get a real let-down message: GAME OVER.

This review can't even pretend to mention every rule or feature of every game; it only tries to show you what the state of the software art is at the moment, and explain how some of the games produce the stunning pictures they come up with.

Perhaps we're all getting a big jaded. This latest crop of games software is really quite magnificent but I just can't bring myself to rave about them. We've seen it all before, in the arcades and on other people's computers. We really need something completely new, but what? I've talked to some of the young computer whizzes around the place . . . asked them what sort of stuff they would write if they had access to the ultimate computer. Nobody's got any fresh ideas. Not a cracker. I haven't got any ideas. Have you got any ideas? If so, go for it! *The market is ready and waiting.*




We Are Overstocked—You Reap The Benefits



COMPONENT SPECIALS


Ends Sept 15th 1984

PANEL MOUNTING RCA SOCKETS




P10232	2 way	1-9	10+
		.35	.30
P10234	4 way	.45	.40
P10236	6 way	.60	.50

VIDEO RF MODULATOR UNBELIEVABLE PRICE



1-9	10+
\$4.95	\$3.95

DELUXE METAL CABINETS



A "STEEL" AT THESE PRICES


H10442	150x61x103mm	1-9	10+
		3.95	2.95
H10444	184x70x160mm	4.95	3.95

CANNON TYPE CONNECTORS DIRECT IMPORT PRICE



P10960	3 PIN LINE MALE	1-9	10+
		1.90	1.60
P10960	3 PIN CHASSIS MALE	1.90	1.60
P10964	3 PIN LINE FEMALE	2.50	2.10
P10966	3 PIN CHASSIS FEMALE	2.90	2.20

1/4 WATT 5% RESISTORS E24 VALUES CARBON FILM



\$1.00 per hundred That is 0.75 of a cent each
\$7.50 per thousand But Must Be The Same Value

34 WAY EDGE CONNECTORS FOR DISK DRIVES

SCOOP DIRECT IMPORT PURCHASE

1-9	10+
\$5.95	\$4.95

IC SPECIALS

6845	1-9	10+
	7.95	7.50
6809	5.95	5.50
6821	2.90	2.75
6840	4.95	4.75
VOLTAGE REGULATORS		
78H12 12V 5 AMP	6.95	6.75
78H05 5V 5 AMP	6.95	6.75
78P05 5V 10 AMP	12.50	11.95
LM323KC 5V 3 AMP	5.95	5.50

HIGH CLASS INSTRUMENT KNOBS



H10060	35mm	.50
H10061	24mm	.45
H10062	20mm	.40
H10063	15mm	.38

Half price this month

KEY SWITCHES



1-9	10+
\$3.95	\$3.75

MINIATURE PCB RELAYS



Massive 3A contacts at 24VDC or 100VAC Nominal 12V Coil but will work OK from 9-15V.

SPECIFICATIONS	S.P.D.T.	D.P.D.T.
Nominal Coil Voltage	12V	12V
Contact Current (max)	3A	3A
Contact Voltage (max)	125VAC	60VAC
Coil Resistance	400 ohm	300 ohm
PRICE		
1-9	\$1.20	\$1.50
10-24	\$1.00	\$1.20
25-99	\$0.80	\$1.00

ECONOMY TOGGLE SWITCHES

Unbelievable Value



S11010	SPDT	1-9	10+	100+
		1.00	.70	.65
S11020	DPDT	1.20	.80	.70

HORN SPEAKER



WOW \$6.95

5" A. B. S. Material Horn Speaker 8 ohm. Freq. Range: 600-5000Hz Max Power: 8 W

BRIDGES & DIODES

6A 400V Bridge \$1.50

	1-9	10+	100+
IN5404	.20	.18	.14
IN5408	.25	.20	.15



CAPACITOR SPECIALS

10 000uF 75V RG	7.95	10+
8 000uF 75V RG	6.95	6.95
2500uF 63V RP	2.95	2.80
5500uF 40V RP	4.95	4.50
200uF 35V RG	1.50	1.40
2200uF 50V RT	.60	.50
2200uF 25V RB	.70	.60
2200uF 16V RB	.60	.50
1000uF 0.16V RB	.30	.25


DISCOUNTED PANEL METERS BUT BE QUICK FOR THESE



PANEL METERS	NORMALLY THIS MONTH	
Q10500 MU45 0-1mA	9.75	6.95
Q10502 MU45 50-0-50uA	9.75	6.95
Q10504 MU45 0-100uA	9.75	6.95
Q10505 MU45 0-50uA	9.75	6.95
Q10518 MU45 0-1A	9.75	6.95
Q10510 MU45 0-5A	9.75	6.95
Q10515 MU45 0-10A	9.75	6.95
Q10520 MU45 0-20V	9.75	6.95
Q10525 MU45 0-30V	9.75	6.95
Q10535 MU45 VU	10.95	8.95
Q10530 MU52E 0-1mA	10.95	7.95
Q10533 MU52E 0-5A	10.95	7.95
Q10538 MU65 0-50uA	13.95	7.95
Q10540 MU65 0-1mA	13.95	7.95
Q10550 MU65 0-100uA	13.95	7.95
Q10560 MU65 0-20V	13.95	7.95

Errors and Omissions Excepted

IC SOCKETS (LOW PROFILE) HOW CHEAP CAN THEY GO



	1-9	10-99	100-999	1000+
8 Pin	.15	.14	.12	.9
14 Pin	.16	.15	.14	.10
16 Pin	.17	.16	.15	.11
18 Pin	.18	.17	.16	.13
20 Pin	.29	.28	.27	.26
24 Pin	.35	.33	.32	.28
40 Pin	.45	.40	.35	.30

5 WATT RESISTORS


WE ARE OVERSTOCKED YOU REAP THE SAVINGS

1-9	10-99	100+	1/2 PRICE
.25	.22	.20	

MORE PANEL METER BARGAINS



Q10400 250 ua Sensitivity Panel cut-out 36mm x 16mm. Mounting hole centres at 49mm.



Q10405 250 ua Sensitivity centre 'O' very useful for balanced circuit and applications needing a centre 'O' or null indication.

2 1/4" Speaker Only \$1.00



ROD IRVING ELECTRONICS

425 High St., Northcote 3070 (03) 489 8866 (03) 489 8131
48-50 A Beckett St., Melbourne (03) 347 9251

Mail Order and Correspondence
P.O. Box 235 Northcote 3070

To Order By Phone

Mail Order Hotline (03) 481 1436



POSTAGE RATES

\$1-\$9.99	\$2.00	\$10-\$24.99	\$3.50
\$25-\$49.99	\$4.50	\$50-\$99.99	\$6.00
\$100-\$199	\$8.00	\$200-\$499	\$10.00
\$500+	\$12.00		

(All above charges are for surface mail and some heavy items will vary from these rates.)

Cert. post for orders over \$100 included "free".
Reg. post for orders over \$200 included "free".
Account orders from schools, govt. depts., public co's., gratefully accepted. Min order amount \$20.00 (or a min. \$5.00 accounting charge will apply.) Comet Road Freight, Airmail etc. are extra.




ROD IRVING ELECTRONICS

425 HIGH ST, NORTHCOTE 3070 VIC


PHONE (03) 489 8866

100's SOLD VIDEO ENHANCER \$35



Like tone controls in a hi-fi amplifier, touch up the signal with this Video Enhancer. EA OCTOBER 83

1000's SOLD TRANSISTOR TESTER \$15



EA SEPTEMBER 83

Have you ever desoldered a suspect transistor, only to find that it checks O.K.? Troubleshooting exercises are often hindered by this type of false alarm, but many of them could be avoided with an "in-circuit" component tester such as the EA Handy Tester.

CAR ALARM \$29.00

This Car Alarm uses the battery earth strap as a sensor to detect when a "courtesy" light or other electrical load occurs when a thief enters a vehicle. The circuitry is simple and immune from false triggering problems. ETI July 81



VIDEO AMPLIFIER \$15




EA AUG 83

Bothered by smeary colours, signal beats and RF interference on your computer display? Throw away that cheap and nasty RF modulator and use a direct video connection instead. It's much better. The Video Amplifier features adjustable gain and provides both normal and inverted outputs. Power is derived from a 12V DC plugpack supply. INCLUDES JIFFY BAG

LOW OHMS METER \$34.50

How many times have you cursed your Multimeter when you had to measure a low-value resistance. Well, alas, with the "Low Ohms Meter" you can solve those old problems and in fact measure resistance from 100 Ohms down to 0.005 Ohms. ETI 158 November 81




NAIL FINDER \$10

Essential for the home handyman the Nail Finder will help locate timber studs behind Gyprock or plasterboard wall surfaces as well as locating pipes and wiring buried in walls.



EA OCTOBER 83

MOTORCYCLE INTERCOM \$40



EA Feb 84

Motorcycling is fun but conversation between rider and passenger is usually just not possible. Build this intercom and you can converse with your passenger at any time while you are on the move. OVER 300 SOLD

SLIDE CROSS FADER



PHONE MINDER \$25

EA Feb 84



Errors and Omissions Excepted

Dubbed the Phone Minder, this handy gadget functions as both a bell extender and paging unit, or can perform either function separately.


±12V RAILS FOR LAB POWER SUPPLY

EA July 1983




An inexpensive addition to the 50V 5A Lab Power Supply which should prove its worth many times over. It provides additional fixed ±12V outputs for lower power applications.

Driveway Sentry \$32



Activated by your car's headlights, the Driveway Sentry will turn on a driveway or garage light so that you can make a safe exit from your car on the darkest of nights. At the end of five minutes, it will automatically turn the light off again.


SPEED SENTRY \$21



EA OCTOBER 83

Paying speeding fines can be a painful business. Build this Speed Sentry and avoid further pains in the wallet.

50V 5A LABORATORY POWER SUPPLY



New switchmode supply can deliver anywhere from three to 50V DC and currents of 5A at 35V or lower. Highly efficient design.

EA May, June 1983

82 PS5

\$140.00

CAR IGNITION KILLER



Our kit includes the metal box

\$16.95

EA Feb 84

Most car burglar alarms are easily circumvented, but not our cunning "Ignition Killer". This sneaky antitheft device uses a 555 timer to place an intermittent short circuit across the points. Until disabled by its hidden switch the circuit effectively makes the car undrivable — a sure deterrent to thieves!

Electric fence \$19.50




Check our prices

SEPTEMBER EA 1982

Mains or battery powered, this electric fence controller is both inexpensive and versatile. Based on an automotive ignition coil, it should prove an adequate deterrent to all manner of livestock. Additionally, its operation conforms to the relevant clauses of Australian Standard 3129.

EA GUITAR BOOSTER

\$17.50



JUNE EA 1982

ROD IRVING ELECTRONICS

425 High St. Northcote 3070 (03) 489 8866 (03) 489 8131
48-50 A Beckett St., Melbourne (03) 347 9251

Mail Order and Correspondence
P.O. Box 235 Northcote 3070

To Order By Phone

Mail Order Hotline (03) 481 1436



POSTAGE RATES

\$1-\$9.99	\$2.00	\$10-\$24.99	\$3.50
\$25-\$49.99	\$4.50	\$50-\$99.99	\$6.00
\$100-\$199	\$8.00	\$200-\$499	\$10.00
\$500+	\$12.00		


(All above charges are for surface mail and some heavy items will vary from these rates.)

Cert. post for orders over \$100 included "free".
Reg. post for orders over \$200 included "free".
Account orders from schools, govt. depts., public co's., gratefully accepted. Min order amount \$20.00 (or a min. \$5.00 accounting charge will apply.) Comet Road Freight, Airmail etc. are extra.



PROLOG

A Programming Language



This article consolidates the basic framework of PROLOG. It employs some familiar examples to illustrate the use of recursion in PROLOG.

David M. W. Powers

Dept of Computer Science
University of New South Wales

COMPUTER BUFFS, programmers and initiates may have wondered about the total lack of control structure in the language as described in Part 1. The observation is valid, but it is not an omission on my part; logical relationships need no control structure since they are merely descriptive.

While certain devious in-built predicates provide side-effects which can be used to guide the search and avoid fruitless paths, the fundamental truth about PROLOG is that it is the responsibility of the system to find such paths that lead to a solution. Later, however, we will see some examples where PROLOG appears to abrogate that responsibility.

How then can PROLOG do the sort of tasks normally done in programming using (if we are assembler hackers) jumps and conditional branches, or (if we are Fortran or BASIC users) 'if' and 'goto' statements, or (if we are disciplined PASCAL or ALGOL programmers) 'repeat', 'while' and 'case' statements? Can PROLOG handle the full range of computing problems? Or, in theoretical terms, does PROLOG have the power of a Turing machine?

GOTO CONSIDERED IMPOSSIBLE

Readers may not be aware of the debate sparked by the letter, "The Goto Statement Considered Harmful", written in 1968 by E. W. Dijkstra to the editor of Communications of the ACM (March 1968, Vol 11, No 3, pp 147-8). Although this was not the first recognition that usage of the 'goto' correlated negatively with program 'quality' and Dijkstra refers to such observations as having been around for a number of years, this letter does seem to have been the seminal contribution on the nature of the statement.

Dijkstra points out that people are best at comprehending static relationships, while they are poor at visualizing temporal relationships. His letter expounds the view that the spatial analogue of the temporal progress of a process is important to human understanding, and points out that, for 'goto-less' programs, two 'action descriptions' which are successive in the program text, i.e: in space, are also successive in execution sequence, i.e: in time.

Where an 'action description' is actually a procedure, it may either be regarded as a unit, or examined as a separate textual and temporal sequence of 'action descriptions', our place in the original sequence being remembered (in this latter view). In the case of a conditional statement, a particular 'action description' either is or is not executed (according to the truth of the condition). This obviously does not affect the spatio-temporal correlation. This cannot be said of a branching statement.

'Logic programming' is an approach fundamentally different from the traditional sequential 'von Neumann' methodology. In a pure logic programming program, the sequence of operations is theoretically irrele-

vant. What is important are the logical relationships. A series of goals to be satisfied must all be simultaneously satisfied for a set of bindings to comprise a solution. What order the goals are satisfied in is, strictly speaking, or no consequence. What is important is that the goal and its bindings satisfy the relationships of the matching predicate.

This corresponds with the 'Structured Programming' view that a procedure should have well defined 'before' and 'after' specifications (pre-condition and post-condition). Thus the relationship between predicate and procedure is more than just the notational resemblance. There is a difference, however, and that is that there can be no distinction between 'before' and 'after' with respect to a predicate — the only difference, if a goal is satisfied, is that more variables may have been instantiated.

Thus we have seen that sequence is essentially irrelevant in logic programs. Unfortunately, for the moment at least, we are limited to using conventional sequential machines which can do only one thing at a time. For this reason PROLOG does have a particular search sequence defined. It uses a depth-first, top-down, left-to-right evaluation sequence. This is about the simplest algorithm for us to understand, and it results in the PROLOG system backtracking in a stack-efficient way.

In this context, a construct like 'goto' is completely meaningless. It is impossible in PROLOG for much the same reason as it is abhorrent to structured programmers; it is incompatible with the imposition of logical conditions on program units.


PROGRAMMING IN LOGIC

It is, in fact, quite hard to see how this class of control structures, the iterative and sequencing control structures, could be carried over into PROLOG. Later we will see how some of them can be simulated in PROLOG, but they are unnecessary, and a hindrance to clear thought and analysis of the problem.

Given the pure definition of PROLOG as a logical expression of logical relationships, how could you jump from the middle of one implication to the middle of another? On the other hand, it is natural to use the same relation several times in the process of reducing a complex goal to a simple one which can be handled directly. Thus in PROLOG, since the branching constructs cannot even be envisaged, recursion becomes the sole repetitive technique.

The extended family — descendants

Suppose we consider the family tree database example given in the panels, FAMILY TREES — examples and FAMILY TREES — exercises, in Part 1. We have the following family tree:



No. 4 in the panel, FAMILY TREES — exercises, posed the problem of defining a predicate to express 'ancestor' and 'descendant' relationships. This is actually the one relationship from two perspectives, so once one has been defined, the other can be defined analogously, or can be defined trivially in terms of that complementary relationship. Since 'child' has been defined ('fam.4'), descendant can be defined simply.

First, we must decide what a descendant is. Well, a descendant of someone is either his/her child, or grandchild, or great-grandchild, or great-great-grandchild, or . . . In other words a descendant is either a child, or a child of one's descendant — or looking at it another way, a descendant of one's child. Or looking at it yet another way, an ancestor and his descendant may be separated by a single generation (if they are parent and child), or by several generations (if there is a grand- and perhaps a great- or so in their relationship). In the latter case, one can either start from the descendant, and consider his lineage, ancestor by ancestor back through the ages, or we can start from the ancestor, and consider his progeny, descendant by descendant through the generations.

In PROLOG these respective alternatives are expressed
`descendant(Anc, Desc) :- child(DParent, Desc), descendant(Anc, DParent).`

or
`descendant(Anc, Desc) :- child(Anc, AChild), descendant(AChild, Desc).`

These implications are applicable whenever the relationship between the ancestor and descendant is not simply that of parent and child. In this latter case, the people found by 'child' as satisfying DParent would actually include Anc himself — and he is not his own descendant and thus 'descendant(Anc, DParent)' will fail! Similarly for AChild = Desc: he is not his own ancestor! Thus neither of the above rules is applicable.

These implications are only useful for bridging a generation gap! Examine them and satisfy yourself that they are always true. Paraphrase them: "A descendant of Anc is Desc if . . .". They are patently true, are they not? They are even true for the parent and child case, although they are not applicable since one of the conditions cannot be satisfied — in each case, the recursive 'descendant' condition.

How then do we handle the parent and child case? Simply:
`descendant(Anc, Desc) :- child(Anc, Desc).`

In general, in recursive definitions there will be one (sometimes more) simple rule (either a fact or an implication) which describes the simplest case, and has the effect of stopping the recursion. It thus provides a termination condition. In this case, the termination condition is "if a child of Anc is Desc". In some cases, no explicit body of conditions is necessary, as the condition imposed on the predicate by its unification (with a rule in the form of a fact) suffices

alone. We'll see some like this shortly.

For now, let's see some examples involving the 'ancestor' and 'descendant' definitions:

fam.6)

```
% Generation rules.
%
descendant(Anc, Desc) :- child(Anc, Desc).
descendant(Anc, Desc) :- child(Anc, ACh), descendant(ACh, Desc).
ancestor(Desc, Anc) :- descendant(Anc, Desc).
```

fam.7)

```
?- ancestor("Susan", Who).
% Who is an ancestor of Susan?
Who = "George"
Who = "Helen"
Who = "Anthony"
Who = "John"
Who = "Natalie"
Who = "Elizabeth"
```

fam.8)

```
?- ancestor(Who, "Anthony").
% Whose ancestor is Anthony?
Who = "George"
Who = "Susan"
Who = "Richard"
Who = "Michael"
```

There is no limit to the complexity of relationships which can be described recursively in this way. The recursive definitions should be written and understood as specifications rather than as procedures, but we have seen here that they can be used as procedures for establishing what satisfies the specifications. The simple two-clause form of recursive definition used for 'descendant' arises in a huge number of other applications. On closer inspection these applications can be seen to be analogous to the 'descendant' relationship.

First, remember that the structure of a family is something like a tree — which is why we talk about 'family trees'. In fact, it is not a tree in the mathematical sense because of the marriages which merge different branches of the family. In a mathematical tree there is but a single parent for each child, although each parent can of course have a number of children. The most important class of trees is probably the binary tree, in which each parent has at most two children.

If we consider only the father (our society is rather patriarchal, after all) the 'family tree' does become a pure tree. As it stands, the full family tree would be classified as a directed graph — since the parent-child relationship is not symmetric. The pure tree is also a directed graph. One has a fundamental choice, in either case, of pursuing a line of descendants (down the tree) or a line of ancestors (up the tree). Note that a tree has a 'root' at the top, being the ultimate ancestor of every 'node' in the tree, and that the 'branches' hang down from it. This is somewhat different from the way God grows his trees — we draw ours upside-down! The nodes which have no descendants are called 'leaves' and the other nodes are called 'interior nodes'.

Trees are intrinsically recursive structures, since every node is either a leaf, or the root of a 'subtree'. A subtree is simply a tree which is part of another tree. Thus our 'parent', 'child', 'ancestor' and 'descendant' predicates will apply to any tree, whatever the nodes may be, since 'descendant' will descend through the successive subtrees of a node, and 'ancestor' will ascend towards the root, just as if searching for such relatives.

More generally, these predicates will work to find a path between two nodes in any non-cyclic directed graph. They can, for example, find or check a route between any two points in a maze of one-way streets. The non-cyclic condition means that there can't be any way of getting from one node back to itself. If there is, then there is the possibility that PROLOG will run around and around in circles without realizing it — like people often do when in mazes which happen not to have this particular property. If the graph weren't directed, there would always be the possibility of immediately doubling back upon oneself.

Here is a plan of the City of Sydney in the year 2001: ▶

So let's look at how we would design a computer service to guide

us around Sydney 2001. You should be able to recognize that 'street' corresponds to 'child', and 'route' to 'descendant', in the following program. It is entirely the same story as before — only the names have been changed . . . to numbers (or traffic lights). Note that the introduction of an extra data field, the street name, does not affect how the recursion works. Note too that the closure of Market St between Castlereagh and Pitt (along with the choice of the 'one-way' direction of each street) has resulted in an acyclic directed graph.

Here then is the guide service:

syd.1)

```
% The map.
%
st("Bathurst",0,1). st("Bathurst",1,2).
st("Bathurst",2,3). st("Bathurst",3,4).
st("Park",5,6). st("Park",6,7).
st("Park",7,8). st("Park",8,9).
st("Market",14,13). closed("Market",13,12).
st("Market",12,11). st("Market",11,10).
st("Elizabeth",4,9). st("Elizabeth",9,14).
st("Castlereagh",3,8). st("Castlereagh",8,13).
st("Pitt",12,7). st("Pitt",7,2).
st("George",11,6). st("George",6,1).
st("York",10,5). st("York",5,0).

% The possible paths.
%
path(From, To) :- st(St, From, To).
path(From, To) :- st(St, From, Q), path(Q, To).
```

syd.2)

```
?- path(12,3).
% Can you go from Pitt & Market to Bathurst &
% Castlereagh?
** yes
** yes
** yes
** yes
** yes
** yes
```

FGCS, MITI, ICOT, KIPS and LIPS

Fifth generation computer systems

Japan, 19th October 1981. At an international conference it sponsored on Fifth Generation Computer Systems (FGCS), the Ministry of International Trade and Industry (MITI) announced a new national initiative — a project to develop the 'fifth generation' of computer for the 1990s.

14th April 1982. MITI, in association with eight major computer companies, formed the Institute for New Generation Computer Technology (ICOT), launching a 10-year project to develop hardware and software systems to meet the computer needs of the next decade.

May 1982. ICOT published their goals and plans in the report "Outline of Research and Development Plans for Fifth Generation Computers" — the FGCS are now firmly targeted as Knowledge Information Processing Systems (KIPS).

To produce their KIPS, the MITI/ICOT FGCS project is attacking three main frontiers.

- (1) The conventional central processing unit is to be replaced by problem solving and inference machines based on concurrent processing elements (this is where PROLOG enters the picture).
- (2) The traditional primary, secondary and virtual memory systems are to be oriented towards knowledge base management (cf today's 'fourth generation' computer languages and relational databases — this is an obvious application for PROLOG).
- (3) The standard Input/Output interfaces are to be upgraded to intelligent and natural communications, including human language, speech and picture processing (cf today's Artificial Intelligence research — this is currently a primary domain for PROLOG).

To focus on PROLOG; PROLOG uses a technique known as resolution to replace a goal by a number of new goals by employing a matching rule. This technique, whose principle was well known to Socrates and Plato, is known as a syllogistic inference step, or simply as an inference. PROLOG systems (and other deductive systems) may be rated in terms of the number of Logical Inferences Per Second (LIPS) they can perform.

Today micros, minis and mainframes clock in at about 100, 1000 and 10 000 LIPS respectively. The proposed KIPS will perform 100 to 1000 MLIPS (where MLIPS = Mega-LIPS = Millions of LIPS). Even the fifth generation personal computers are envisaged as being in the Mega-LIPS range.

References

- (1) T. Moto-oka (ed), 1981, *Proceedings of the International Conference on Fifth Generation Computer Systems*, JIPDC/Springer, Tokyo, Japan, October 1981 — the original announcement on FGCS.
- (2) ICOT, 1982, *Outline of Research and Development Plans for Fifth Generation Computer Systems*, JIPDC, May 1982 — the official desiderata for FGCS.
- (3) T. Moto-oka (ed), 1983ff, *New Generation Computing: An International Journal on Fifth Generation Computers*, Tokyo, Japan, July 1983ff — an entire journal on FGCS. (JIPDC is the Japan Information Processing Development Centre.)

syd.3)

```
?- path(X,5).
% Whence can you get to York & Park?
X = 10
X = 12
X = 11
```

syd.4)

```
?- path(8,X).
% Where can you go from Park & Castlereagh?
X = 9
X = 13
X = 14
X = 15
```

Comprehensible! Good! (If not go back to the discussion of 'descendant' and read through again.)

Computing Software

ATARI GAMES AND RECREATIONS

K0224P \$22.25
Beginners and advanced users can use the preprogrammed games in this book to improve their skill. Charts, flash cards, an error dictionary and graph paper designs are among the features.

TRS-80 ASSEMBLY-LANGUAGE MADE SIMPLE

K0208P \$19.25
If you have an understanding of BASIC programming, this will help you to plan, write and hand-assemble your own assembly-language programs in memory, using the T-bug and Level II BASIC ROM subroutines.

USING THE 6800 MICROPROCESSOR

J0163P \$13.25
Guides the reader through the conception, configuration, writing and running of a variety of programs that demonstrate practical use of a 6800 system.

APPLE II ASSEMBLY LANGUAGE

K0195P \$23.45
Teaches assembly-language programming at the beginning level — no prior knowledge of 6502 assembly language is needed. Includes hands-on computer exercises and experiments, with both software and hardware. Provides interfacing circuits and programs that can be used on the Apple II without modification.

CP/M PRIMER

K0191P \$26.95
A complete one-stop course on CP/M, the very popular operating system for 8080, 8085 and Z80-based microcomputers. Complete terminology, hardware and software concepts, startup of a CP/M system, and a complete list of CP/M-compatible software.

COMPUTER GRAPHICS PRIMER

K0180P \$21.95
Almost every page has a colour drawing, photograph, picture or a schematic to help you learn computer graphics quickly and easily. Programming concepts apply to all microcomputers, and examples are given in BASIC for the Apple II.

IBM PERSONAL COMPUTER — AN INTRODUCTION TO PROGRAMMING AND APPLICATIONS

J0360P \$21.95
Designed for beginners, this book offers an informal introduction to programming in BASIC. Also covers applications for business, graphics, games and word processing and includes comprehensive tables and charts.

PC DOS: USING THE IBM-PC OPERATING SYSTEM


J0278J \$24.50
This self-paced guide teaches you how to become an accomplished user of all the major disk-operating system functions and utilities, no matter how much or how little computer experience you have.

FIFTY BASIC EXERCISES

K0188A \$17.95
Designed to teach BASIC through actual practice, this book contains graduated exercises in math, business, operations research, games and statistics. The programs were designed to run directly on a TRS-80 but will run on any system with Microsoft BASIC.

THE ART OF PROGRAMMING THE 16K ZX81

K0213B \$8.75
A sequel to *The Art of Programming the 1K ZX81* (ETI Book Sales No K0226B), this book sets out to help you use your 16K RAM pack and ZX printer to the full. It concentrates on good programming style and introduces some interesting programs that are both fun and useful.



BASIC PROGRAMS FOR SCIENTISTS AND ENGINEERS

K0179A \$19.95
Contains scientific and engineering application programs written in BASIC.

APPLE MACHINE LANGUAGE

K0215P \$21.95
This straightforward book teaches machine language programming through BASIC, the transition being made step-by-step. Many sketches of video displays are provided, as well as exercises.

Electronics Today Book Sales

Simply fill out the reply-paid card insert and send to:

**ETI Book Sales,
140 Joynton Ave.,
Waterloo, NSW 2017**

(02) 663-9999, ext 242

DON LANCASTER'S MICRO COOKBOOK

J0159P \$22.20
This 'cookbook' starts with the very fundamentals of microprocessors and microcomputers and takes you through number systems, codes, etc, till you can work intelligently with micros.

THE \$100 AND OTHER MICRO BUSES

J0160P \$14.50
The key to successful computer expansion is a complete understanding of the bus system, through which the computer communicates with peripherals. This book will give you that understanding.



THE 6809 COMPANION

J0154B \$6.95
This is not a beginner's introduction to microprocessors in general but a discussion of the features of the 6809 and a reference.

Z80 MICROCOMPUTER HANDBOOK

J0171P \$20.50
This handbook covers hardware, software and microcomputers built around the Z80.

APPLE INTERFACING

J0273P \$15.95
Using this book, you will be able to perform useful experiments which will provide a much clearer understanding of the fundamentals of computer interfacing and computer electronics.

6502 APPLICATIONS BOOK

K0228A \$20.95
Use this book and a few low-cost components to build a complete home alarm system, an electric piano, a motor speed-regulator, a time-of-day clock, a simulated traffic control system and a Morse code generator, etc.

Z80 MICROCOMPUTER DESIGN PROJECTS

J0156P \$20.75
A complete look at the internal architecture of the Z80, the heart of many microcomputers, and even shows how to build a microcomputer, the EX80, using this powerful chip.

MICROPROCESSOR CIRCUITS

J0157P \$14.75
Presents basic microprocessor concepts in simple language for beginners and teaches you to construct a useful microcontroller system. Offers 30 demo circuits which take you through assembly, operation and programming of a microcontroller.

A Z80 WORKSHOP MANUAL

J0283B \$8.95
Intended for those who want to progress beyond BASIC programming to topics such as machine-code and assembly language programming or who need hardware details of the Z80-based computer.

EASY ADD-ON PROJECTS FOR SPECTRUM, ZX81 AND ACE

J0285B \$7.75
The projects include a pulse detector, picture digitiser, five-key pad, model controller, bleeper, lamp flasher, light pen, etc, etc.

THE 68000: PRINCIPLES AND PROGRAMMING

K0176P \$19.95
An easy-to-read, systematic approach to the 68000 advanced 16-bit microprocessor. The book guides you through the complex architecture, instruction set, pinouts and interfacing techniques. Written for design engineers, programmers and students.

ENHANCING YOUR APPLE II

K0206P \$27.95
Contains fast and easy method for taking apart and understanding machine-language programs. Features programs and other hints for creating hundreds of colours or many patterns on the screen, plus ideas to improve text on high-resolution displays.

TV TYPEWRITER COOKBOOK

J0297P \$14.50
A complete guide to low-cost television display of alphanumeric and graphics data for microprocessor systems, computer hobbyists, television titling, word-processing and video games.

STD BUS INTERFACING

J0164P \$21.75
Explains what the STD bus is, in easy-to-understand language.

Computer Hardware & Techniques

More great books on page 73

Prices subject to change without notice

Electronics Today Book Sales

Electronics for beginners

HI-FI LOUDSPEAKER ENCLOSURES

C0028B \$4.95

Data for building corner reflex, bass reflex, exponential horn, folded horn, tuned port, Klipschorn labyrinth, tuned column, loaded port and multi speaker panoramics. Clear dimensioned diagrams included.

HOW TO BUILD YOUR OWN METAL AND TREASURE LOCATORS

C0036B \$6.95

Electronic and practical details on the simple and inexpensive construction of heterodyne metal locators.

ELECTRONIC PROJECTS FOR BEGINNERS

C0038B \$6.95

This book gives the newcomer to electronics a wide range of easily built projects. Actual components and wiring layouts aid the beginner. Some of the projects may be built without using soldering techniques.

EASY ELECTRONICS: CRYSTAL SET CONSTRUCTION

C0041B \$6.75

For those who wish to participate in the intricacies of electronics more through practical construction than by theoretical study. The circuits are based on those from earlier publications but have been modified to use modern components and home-wound coils.

IC PROJECTS FOR BEGINNERS

C0042B \$6.75

Especially written for the less experienced hobbyist, and offers a range of fairly simple projects based around a number of popular and inexpensive linear and digital ICs. Complete layout and point-to-point wiring diagrams.

BEGINNER'S GUIDE TO BUILDING ELECTRONIC PROJECTS

C0030B \$6.95

Enables total beginners to tackle electronic projects. Includes component identification, tools, soldering, building methods, cases, legends, etc. Practical basic projects are included.

THE WORLD IN MY EARS

N0420C \$9.95

This book would represent the 'basic manual' for anyone interested, or active in, shortwave listening. Written by world-renowned authority and broadcaster, Arthur Cushen, M.B.E., the book is divided into two parts. The first covers the historical development of shortwave broadcasting and the listening hobby that grew up with it. The second part covers the practical aspects: how to start out, how to erect antennas, all about time and time zones, DX clubs, reporting, news sessions, etc.

COMPUTER PROGRAMS FOR AMATEUR RADIO

N0399S \$19.95

The most comprehensive collection of BASIC programs ever published to help radio amateurs cut down on time spent keeping records, doing mathematical calculations, and beaming in on other stations.

RADIO STATIONS GUIDE

N0252B \$5.95

An aid for all those who have a radio receiver. Shows the station site, country, frequency and/or wavelength, as well as Effective Radiated Power of the transmitter and, in some cases, the station's call sign as well.

Amateur radio, dx communications

AMATEUR RADIO MAP OF THE WORLD

N0362R \$4.95

Published by the American Radio Relay League, this giant wall map is fully indexed.

AN INTRODUCTION TO RADIO DXING

N0253B \$6.75

One section is devoted to amateur band reception and the other section covers broadcast band reception, with advice on suitable equipment and the techniques employed when using that equipment. The construction of a number of useful accessories is described.

25 SIMPLE AMATEUR BAND AERIALS

N0286B \$6.95

How to build 25 amateur-band aerials that are simple and inexpensive to construct and perform well. From the simple dipole up to a mini-rhombic.

HOW TO BUILD ADVANCED SHORTWAVE RECEIVERS


N0340B \$6.95

Contains full practical construction details of a number of receivers.



Prices subject to change without notice

Simply fill out the reply-paid card insert and send to:
ETI Book Sales,
140 Joynton Ave, Waterloo NSW 2017
 All phone enquiries: (02) 663-9999, ext 242



Everyone's a Winner in the AVTEK Olympics

GOLD!

Jump in for 5 1/4" Diskettes

Limited quantities of high quality Memorex 5 1/4" SS/DD hard sector diskettes suitable for Micropolis and other hard

sector disk drives. Normally selling for \$55.00 (box of 10) now only:

\$39.50 for box of 10



Get on your Starting Block for these August Specials!!

Multiply your MicroBee's ROM Capacity

The exclusive Avtek MultiProm Interface Kit allows you to extend the ROM capacity of your MicroBee to 44K, or to a total of 308K byaisy chaining up to 6 boards. It takes 2532s or 2764s (can be mixed) and has 11 open collector outputs and eight buffered inputs; the outputs can drive relays etc, the inputs can monitor the status - perfect for alarms, machines, even your model trains!! The address of the ports used for EPROM selection can be changed. You can quickly select between Editor/Assembler, WordBee, Logo, MiniPascal etc. with a few keystrokes.


only \$99⁰⁰

AVTEK MultiModem Outruns Modems costing 2-3 times the Price! Kit Form

AVTEK have slashed the cost of high performance modems with the MultiModem. Using the revolutionary 'World Modem' IC we have engineered a modem which works at both 300 and 1200 baud to both Australian and International standard - all for the price of 300 baud, single standard units with less features!!

Ideal for private line use and Amateur Radio operators. Complete to the last nut and bolt and includes pre-punched and silk-screened front and back panel.

only \$249⁰⁰



Specifications:
Data Standards: CCITT V.21 & V.23, Bell 103 & 202
Data Rates: 300, 600 and 1200BPS
Backward Channel: 75 PBS in conjunction with 1200 BPS
Computer Interface: CCITT V.24 (RS232C)
Power: 240VAC/3W
Front Panel: Mode switch (12 position rotary), Connect Switch (3 position toggle), Tests Switch (3 position toggle), Connect LED, Data Carrier Detect, Received Data, Request to send, Clear to send, Transmit Data, Ring Detect, Test switch off normal, POWER.

Fully Built and Tested Fully Telecom Approved - includes phone

Ready to plug into any telephone socket, includes the phone hardwired into the Modem.

only \$329⁰⁰

2SC935 TV/High Voltage Transistors at Tiny Prices

Thousands of uses in high voltage switching, regulating, Audio etc.

Specs: 300V, 100W, FT 5MHz, Saturation Voltage 1.5V, Equivalent to MJ410, 2N5840. Normally \$3.00-\$5.00.

Now only \$1⁰⁰

Make Your Own Crystal Set!

These high quality, air spaced dual gang tuning capacitors are ideal for experimenters & servicemen etc. Normally selling for over \$7.00, we have limited stocks at

only \$1⁵⁰ each

Plastic type Tuning Gang

Dual gang type. Others are selling these for \$1.50 and more. Sprint in for a real deal:

50c

MultiROM Boards XM-1

Fits inside the MicroBee and lets you select say WORDBEE or EDASM from the keyboard. Suits all Bees with 8000 serial number (or earlier)

\$19⁹⁵


XM-2 As XM-1 but suits all Bees with 9000 (MicroBee IC etc) serial numbers upward. Also responds to PAK1 and PAK2 commands.

\$29⁹⁵

1/2 Price Sale of the Biggest, Fanciest Case on the Market

We are selling the incredible 'Eurocase' (normally selling for \$189) for only \$89.00. This case is a superbly made 4 unit rack frame case, originally made to house S100 computer systems. Made in Germany and built better than a tank!!

was \$189 now \$89⁰⁰



Neutrik Connectors - the Best for Less

Replace your tired Cannon connectors with Neutrik Connectors and get a higher standard of reliability and convenience. Collet type strain relief grip and a touch locking device are just some of the features.

Prices:
3 pin 1-9
Line Male 3.50
Line Female 3.50
Chassis Male 3.20
Chassis Female 3.50



Sprint in for 40% off 400mW Zener Diodes Packs

You normally pay 25c each for these zeners. We are selling them in packs of 10 at a 40% saving! Voltages: 3.3, 3.9, 4.3, 4.7, 5.6, 6.2, 6.8, 7.5, 8.2, 9.1, 10, 11, 12, 13, 15, 18, 20, 22, 24, 27, 30, 33V.

Pack of 10 (all same type) only \$1⁵⁰

Chassis Male 2.50
non locking
Chassis 2.50
Female non locking
Line Male 4.95
right angle
Line Female 4.95
right angle

4 pin
Line Male 4.50
Line Female 5.50
Chassis Male 3.50
Chassis Female 3.50

5 pin
Line Male 6.50
Line Female 7.50
Chassis Male 5.50
Chassis Female 5.50

6 pin
Line Male 8.95
Line Female 10.95
Chassis Male 7.50
Chassis Female 7.50
Mains Type
Line Male 6.50
Line Female 6.50
Chassis Male 6.50
Chassis Female 6.50



AVTEK

(ELECTRONICS) Pty Ltd

119 York Street, Sydney 2000

Phone (02) 267 8777

Mail Orders to: P.O. Box Q302 Queen Victoria Building, Sydney 2000

Postage and Packing

Divide the value of your order by 20(5%) to get post and packing value and then add \$2.00 - it's that simple. All bankcard orders can only be sent to a normal address (not a P.O. Box). All Bankcard orders will be sent by registered post (add \$3 to P&P charges)

All goods in stock and prices correct at time of going to press.

COMPUTER CLUB LIST

Update

This list was compiled courtesy of Your Computer magazine Data Base.

A.C.T.

ACT Micro 80 Users Group, Bill Cushing, 10 Urambi Village, Kambah 2902. (062)31-3630.

ACT VIC-20 Users Association, Chris Groenhout, 25 Kerferd St, Watson 2602. (062)41-2316. Meetings first Monday of each month at Boy's Grammar Scout Hall, Red Hill, 7.30 pm.

ACTARI, Chris McEwan, Co-Ordinator, ACTARI, P.O. Box E112, Canberra 2600. (062)88-7861.

Apple User Group (ACT), Jeff Brock, 1 Buckley Circuit, Kambah 2902. (062)31-3630.

Australian ZX80 Users Group (AZUG), David Brudenall, 19 Godfrey St, Campbell 2601. For ZX80/Microace Owners.

Canberra ACT Sirius User Group, Jim Bland (062)81-2824, (062)81-2832.

Canberra Compucolor Club (CCC), Meets 7.30 pm on first Sunday of every month at the offices of Digital Equipment, 28 Lonsdale St, Braddon ACT.

Canberra Microbee Users Group, Hugh Gibson, Microbee Store, Level 1, Cooleman Court, Weston 2611. (062)88-6384.

Canberra Microbee Users Group, Adrian Van Wierst, 9 McGowan St, Dickson. (062)49-7030.

Canberra Micro-80 User Group, Milt Cottey, 33 Crawford Cres, Flynn 2615. (062)58-8822. Meetings third Monday each month 7.30 pm in the small theatre, Reid TAFE, for System 80, TRS-80 etc.

Canberra Osborne Group, c/o Geoff Cohen, P.O. Box 136, Kippax 2615. (065)54-7608.

Micsig, Registrar, P.O. Box 446, Canberra 2601.

N.S.W.

Albury-Wodonga Dist. Microbee U.G., Eric Eulenstein, 202 Kooba St, Albury 2640. (060)25-1601.

Apple Users Disk Exchange Club, Peter Lopic, 45 Malabar St, Canley Vale 2166.

Apple Users Group, Colin Rutherford, P.O. Box 505, Bankstown 2200. Meets 6.30 pm second Monday of each month (Tue. after pub. hol.) at Sydney Grammar School, Stanley St., Sydney. (02)520-0926.

Atari Computer Enthusiasts, Tony Reeve, P.O. Box 4514, Sydney 2001.

Ausborne, Brian Carney, 477-4492, P.O. Box C530 Clarence St., Sydney 2001. Meetings third Wednesday each month at 6.30 pm in the North Shore Council Chambers, for Osborne users.

Ausbug, Stephen Ford, P.O. Box 62, Londonderry 2753.

Australasia ZX80 Users Group, Tony Mowbray, 87 Murphys Ave., Kieraville 2600. (042)28-5296, for ZX80/81 — Microace owners.

Blue Mountains Microbee Computer Club, Roger Cooper. (047)58-7238.

Blue Mountains Computer Club, Eric Lindsay or T. Macindoe, C/- P.O. Faulconbridge 2776.

Broken Hill Microbee Users Group, Peter Cotter, 533 Radium St, Broken Hill. (080)88-1621.

Central Coast Apple Users

Group, C. W. Lee, 662 The Entrance Road, Wamberal 2260. Meetings first Tuesday each month at the Niagara Park Public School from 7.30 pm. (043)84-3419.

Central Coast Computer Club, Max Maughan, P.O. Box 36, Ettalong Beach 2257. (043)24-2711. First and third Tuesday every month at Applied Technology, West Gosford, for all types of computers.

Commodore Users Group, John Guidice, G.P.O. Box 4721, Sydney 2001.

Compucolor Users Group, Tony Lee, 52 Cowan Road, St. Ives 2075. (02)449-8824.

Cumberland Computer User Group, S. O'Neil, (02)682-3851.

DEC Personal Computer Special Interest Group, Marion Rhydderch, DEC Australia, Northern Tower, Chatswood Plaza, Railway St, Chatswood 2067. (02)412-5252.

A.P.F. Users Group, Norm McMahon, 288 Kissing Point Road, Turramurra 2074. (02)44-2645.

Hawkesbury Microbee Computer Club, Bruce Rennie. (045)67-7329.

HP Desktop Computer Users Group, Dr R. W. Harris, CSIRO Division of Mineral Physics, PMB 7, Sutherland 2232. (02)543-3460.

Hunter U. G. — All Microcomputers, Secretary, P.O. Box 39, Broadmeadow NSW 2298. Meets on the second Wednesday of each month in Room 308, building W, University of Newcastle at 7.45 pm. Membership is primarily Apple II orientated, but anyone with interest in micros welcome.

Illawarra Microbee Computer Club, Ronald Read, 49 Beatus St., Unanderra 2526. (042)71-2384.

Illawarra Super 80 Users Group, Jim O'Grady, Chairman, P.O. Box 1775, Wollongong 2500.

Kaypro Users Group NSW, Harry Richards, 4/2 Bortfield Drive, Chiswick 2046. (02)713-1585. Meets second Tuesday each month at 8.00 pm in the Burwood RSL.

Lotus 1-2-3 User Group, in Sydney, Ron Pollak, (02)29-5316.

Macarthur Computer Association, J. Napier, 23 Athel Tree Cres., Bradbury 2560. Meets first Monday each month at Airds High School, Briar Road, Campbelltown, at 7.30 pm each month, all machines are catered for. (046)25-2055.

Macquarie Microbee Users Group, Brian Thompson, meetings first Monday each month at Denistone East Primary School at 7.30 pm. (02)85-1659 after hours.

MEGS (Microcomputer Enthus. Group), John Whitlock, P.O. Box 1309, Chatswood 2067. Meetings third Monday each month at rear of St. Andrews Presbyterian Church, 37 Anderson St, Chatswood. (02)638-1142.

Mi Computer Club, Norma Jackson, P.O. Box 21, Waterloo 2017. (02)662-8888.

Newcastle Microbee Users Group, Lee Osman, 12 Cleverton Close, Warners Bay 2282. (049)48-8813.

Newcastle Microcomputer Club, Angus Bliss, P.O. Box 293, Hamilton 2303. Meetings second and fourth Monday each month at room G12, Physics Building, Newcastle Uni. (049)67-2433 ext 326 bh.

NSW Primary School Microbee Users Group, Mr Peter Stretton, c/- Hunters Hill Primary School.

Alexandra St, Hunters Hill 2110.

NSW 6800 Users Group, 27 Georgina Ave, Keiraville 2500.

Northern Beaches VIC User Group, E. Tuxford, 161 Barrenjoey Rd, Newport 2106. (02)997-2467.

Northern NSW MICC Chapter, Alen Hartley, Dundurrabin, via Dorrigo 2433. (066)57-8160.

NSW Peach User Club, Daniel Soussi. Weekly meetings on Saturday from 2 pm at 'Cybernetics Research' 120-122 Lawson St, Redfern. (02)698-8286.

OSI Users Group, Nigel Bisset. (02)411-7142.

Pocket Computer Users Club, George Antonijevic (02)683-54296, for those interested in pocket computers, whatever the brand. Meetings held on the first Wednesday of each month at 7.30 pm at the 'Woodstock' Community Centre, Church St, Burwood.

Sorcerer Users Group, P.O. Box E162, St James 2000. Meetings first Tuesday each month at 7th Floor, Datec House, 220 George St., Sydney at 7.30 pm.

Southern Districts Commodore Users Group, Lex Toms, 602-8691, 3 Lucille Cres., Casula 2170. meetings first and third Wednesday each month, API Hall, Currajong Rd., Prestons.

Sutherland Super 80 Group, Jim Treager. (02)525-2018.

Sydcom 64 (C64 User Group), Andrew Farrell, meetings first Tuesday of each month at 6.30 pm above Computerwave, George St., Sydney. (02)99-2640.

Sydney FORTH Group, Peter Tregeagle, 10 Binda Road, Yowie Bay 2228. (02)524-7490, FORTH Computer Language.

Sydney Microbee Users Club, Colin Tringham, 92-6408, P.O. Box C233, Clarence St, Sydney 2000. Meetings third Sat. each month, 1-5 pm, McMahon's Point Hall, Blues Point Rd., North Sydney.

Sydney Peach User Group, Ben Sharif, 261 Northumberland St., Liverpool 2170. (02)601-8493.

Sydney TRS-80 Users Group, meetings second, third and fourth Saturday of each month at Botany. (02)666-4716 bus. hours.

TAG-The Access Group, Bob Dolton, P.O. Box 943, Orange 2800, for Access and Actrix users.

TI Sydney Home Computer U.G., P.O. Box 149, Pennant Hills 2120.

Wagga Microbee Users Group, John Simmons, 47 Undurra Drive, Glenfield 2650. (069)31-1302. Meetings first and third Tuesdays each month in the Tolland-Glenfield Neighbourhood Centre at 8.00 pm.

Wizzard User Group, John Mifsod, 150 Bouganville Road, Blackett 2770. (02)628-0801.

ZX-Spectrum Users Club, Craig Kennedy, P.O. Box 466, Epping 2121.

Victoria

Apple Users Society of Melbourne, D. Halprin, P.O. Box 43, Forest Hill 3131. (03)387-3221.

AT Microcomputer Club, Grant Forest. (03)879-2257 ah, (03)699-2888 bh. This club has been formed for people interested in the Applied Technology DGOS Z80.

Atari User Group Melbourne, Kelvin Eldridge, P.O. Box 173, 3073.

Australian FORTH Interest Group, Tony Latemore, P.O. Box 704, Sale 3850. (051)44-2011.

Australian North Star Users Assoc, P.O. Box 194, Wangaratta 3677.

Ballarat Computer Users Group, Publicity Officer, John Preston. (053)31-4363.

Billanook Computer Forum, Maurie Canterbury, Cardigan Road, Mooroolbark 3138. (03)725-5388.

ABUG 80 (Burwood Users Group), P.O. Box 46, Blackburn South 3130.

CHIP 8, 6800, 1802 User Group, Frank Rees, 27 King St, Boort 3537.

Compucolor Users Group, L. Ferguson, 12 Morphet Avenue, Ascot 3342.

COMX-35 Users Group, Adam Carter, 2 Dougand Circuit, Dingley 3172. Interstate members welcome.

DEC Personal Computer Special Interest Group, see NSW entry.

FORTH Interest Group, Lance Collins, P.O. Box 103, Camberwell 3124. (03)29-2600. Meets on the first Friday of the month.

Geelong Computer Club, Peter McKeon, P.O., Box 93, Geelong 3220.

IBM & Columbia Computer Users Club, Giles Bray, 22/11 Auburn Grove, Hawthorn East 3123.

82-7632, second Tuesday each month, 7.30 pm at the Victorian College of Pharmacy.

Kaypro Users Group of Victoria, George Kunz, P.O. Box 159, Forest Hill 3131. (03)857-5462. Meetings fourth Sunday each month at Burwood State College, Community Resources Centre at 2 pm.

KAOS (Ohio Scientific), David Anear, 49 Millewa Cres., Dallas 3047.

Latrobe Valley Colour Computer U.G., George Francis, 31 Donald St, Morwell 3840. 22-1389, for TRS-80 & MC10 users.

Melbourne Atari Computer Enthusiast, P.O. Box 133, Mulgrave North 3170. Meetings held on first Sunday of each month at 11.40 am at Monash University Rotunda.

Melbourne Lotus 1-2-3 Users Group, Robert Taylor. (03) 267-4800.

Melbourne Microbee Users Group, Pres. Grant Forrest, P.O. Box 157, Nunawading 3131. Meetings 7.00 pm second Wednesday each month at Vic. State College — Burwood Campus, 221 Burwood Highway, Burwood.

Melbourne PC User Group, Stephen Wagen or Christopher Leptos, c/o Pannell Kerr Foster, 14th floor, 500 Bourke St., Melbourne 3000. (03)605-2222 bh.

Melbourne Peach Users Group (MPUG), P.O. Box 191, Rosanna 3084. (03)434-2541.

Melbourne Super 80 Users Group, Sec. Victor Shuttleworth. (03)723-2713.

MICOM, Microcomputer Club of Melb, P.O. Box 60, Canterbury 3126.

Motorola User Group Soc. (MUGS), Clive Allan, 11 Haros Ave., Nunawading 3131. (03)878-1298. Group is interested in 6800/02/09-based computers, particularly if running Flex.

National Mutual Micro Users Group, R. Prewett, NMLA, P.O. Box 2830AA, GPO Melbourne 3001. For National Mutual staff.

National Sinclair User Group, P.O. Box 148, Glen Waverley 3150.

National ZX80 Users Club, 24 Peel St, Collingwood 3066.

NEC Portable Users Group, D. Green, meetings second Wednesday of each month at Myers Computer Centre, Lonsdale St., at 7.30 pm. (03)611-3380.

Northn/Westn Sub. Comp. Users Group, John King (Secretary), 284 Union Road, Moonee Ponds 3039. (03)338-9304. Contact CP/M Data Systems.

Peninsula Computer Club, George Thompson, 3 Patterson St, Bonbeach 3196. 772-2674, second Tuesday each month at Chisholm College, Frankston. Many types of computers are catered for.

Sharp Computer Users Association, The President, 7 Faye St, East Burwood 3151.

Spectravideo Users Group, Mitch Raitt, Fernhill, Tindal's Road, Warrandyte 3113. (03)844-3485.

Sorcerer Computer Users (Australia), Secretary, G.P.O. Box 2402, Melbourne 3001.

TI-99/4A Users Group Melbourne, Wayne Worlodge, 123 Ashburn Grove, Ashburton. (03)25-1832.

Vic. Assoc. of Computer Educators, Arthur Totrall, P.O. Box 69, Whittlesea 3757.

Victorian VZ200 User Group, Luigi Chiodo, 24 Don St, Reservoir 3073. (03)460-3770.

Victorian Wizzard Users Group, Barry Klein, 24 Russell St, Bulleen 3105.

Yarrowonga Computer User Group, Chris Younger, 10 Witt St, Yarrowonga 3730. (057)44-3859. For all machines.

ZX81 Software Exchange, C/- Chips Taens, 5 Muir St, Mt. Waverley 3149.

QLD.

Apple-Q the Brisbane User Group, The Secretary, P.O. Box 721, South Brisbane 4101. Has User Group days every third Sunday of month at Hooper Education Centre, Kuran St, Wavell Heights. Centre is open from 8.30 am till 4.30 pm. Members encouraged to bring Apple along.

Australian Sirius Users Group, P.O. Box 204, Chermiside 4032. (07) 350-2611. Looks after the needs of Sirius One and Victor 9000 computer users. For membership form write to above address.

Basic User Group, Chris Lucey, Cranium Computers, 34 Lawless St, Blackwater 4717.

Brisbane Super 80 Users Group, Gary Gattfield. (08)355-3173.

Brisbane Youth Computer Group, A. Harrison, P.O. Box 396, Sunnybank 4109.

Commodore Computer Users Group Qld, Mrs D. D. Dillan, P.O. Box 127, Stones Corner 4120.

Commodore Users Group, John Egan, P.O. Box 274, Springwood 4127. (07)287-2705. For owners of Pet/CBM and VIC-20 machines. Meetings held on the first Tuesday of the month at 130 Petrie Terrace, Brisbane.

Computer Owner's Group, Betty Adcock, 42 Lucan Ave, Aspley 4034. 263-4268. Second Wednesday each month, 7.45 pm, all kinds of computers are catered for.

DEC Personal Computer Special Interest Group, see NSW entry.

Gold Coast Microbee User Group, Col McLaren, 1-100 Imperial Parade, Labrador 4215. (075) 31-4610. Meetings first Sunday each month, 3.00 pm at the Southport High School.

IREE Microcomputer Interest Group, N. Wilson, P.O. Box 811, Albion 4010.

Mackay Microbee User Group, Geoff Gehring, Box 230, Mackay 4740. (079)42-3214.

Osborne Users Group of Qld Uni, Glen McBride, meetings second Thursday each month, open to all. (07)371-4243.

Superboard Users Group, Ed Richardson, 146 York St, Nundah 4012.

Tandy, Apple, Commodore UG, Chris Lucey, 34 Lawless St, Blackwater 4717.

The Microcomputer Society, The Secretary, P.O. Box 580, Fortitude Valley 4006. Meetings are held on the second Friday of each month in the Old Town Hall, corner Vulture and Graham Streets, Sth Brisbane. Meetings start at 7.30 pm; if main gate is closed use the back stairway.

Townsville MicroBee User Group TMUG, C/- Town and Country Computers, CTL Centre, Anne St, Aitkenvale 4814. Meetings 7.30 pm on second and fourth Monday each month on the ground floor, St Margaret Mary's Secondary School, Crowle St, Hermit Park.

TRS80/System 80 Interest Group Qld, 396-2998. Meetings on the first Sunday of each month at 21 Rodney St, Lindum, at 2 pm.

ZX 81 Club, P. Carswell, 22 Braud St, Bundaberg 4670.

S.A. & NT.

AACC, Adelaide Atari Com-

puter Club, meets at Gilles St Primary School, City, on first Monday (second if first is on public holiday) of each month. Secretary, P.O. Box 333, Norwood 5067.

Adelaide Lotus 1-2-3 User Group, Paul Wragg, Pannell Kerr Foster, GPO Box 1969, Adelaide.

Adelaide Micro User Group, R. G. Stevenson, 36 Sturt St, Adelaide 5000. For TRS-80 and System 80 Users.

Adelaide Osborne Group, Russell Barter, The Secretary, 410 Regency Road, Prospect 5082.

Alice Springs Microbee Users Group, Douglas Craigie, c/- P.O. Box 3230, Alice Springs 5750.

Beebnet, BBC and Econet User Group, M. A. Cowley, P.O. Box 262, Kingswood 5062.

CBM/VIC Users Group Of N.T., Ian Diss. (089)27-9208.

Commodore/VIC Computer Users Assoc, Eddie Hann, 13 Miranda Road, Paralowie 5108. The SA branch meets monthly.

Compucolor-Intercolor User of SA, P.O. Box 86, Torrensville 5031. (08)352-3296.

Darwin Microbee Users Group DBUG, Felino Molina, P.O. Box 3111, Darwin 5794. (089)82-5613 bh, (089)88-1455 ah.

DEC Personal Computer Special Interest Group, see NSW entry.

IBM-PC SA Users' Group, P.O. Box 68, Walkerville 5081.

Kaypro User Group, Myles Wakeham, 100 Pirie St, Adelaide 5000. (08)223-6333. meetings first Tuesday each month.

Microbee Users Group of S.A. MUGSA, The Secretary, GPO Box 767, Adelaide 5001.

NT 80 Computer User Group, R. T. O'Brien, 433 McMillans Road, Jingili, Darwin 5792.

SA Commodore Computers UG, Eddie Hann, The Secretary, P.O. Box 427, North Adelaide 5006. 258-6367. Meetings second Tuesday each month, 7.30 at Royal Caledonian Hall, 379 King William St, Adelaide.

SA Hitachi User Group, Cliff Hignett, 45a Ormond Ave, Daw Park 5041. (08)274-9341.

SA Microprocessor Group Inc. SAMG, The Secretary, P.O. Box 113, Plympton 5038. (08)278-7288.

Sorcerer Users Group of SA,

Don Ide, 14 Scott Road, Newton 5074.

South Australian Apple Users Club, The Secretary, SAAUC, C/- The Bookshelf, 169 Pirie St, Adelaide 5000.

South East Computer Enthusiasts Group, Glenn Mibus, 3 Millard St, Mount Gambier 5290. (087)25-1046. Meetings second and fourth Tuesday of each month from 6.30 pm at Mt Gambier High School Computer Room, for all machines and interested parties.

The Microcomputer Assoc. of the NT, Andy Smith, Darwin Community College, Casuarina 5792.

VZ200 Users Club, 7 Abbott Cres, Malak, Darwin 5793. (089) 27-2830.

WA.

Agriculture Users Group, C/- Mr R. Fenwick, Dept. of Agriculture, Albany 6330. For farmers and the agriculture service industries.

CU West WA Compucolor/Intercolor U.G., John Newman, 8 Hillcrest Drive, Darlington 6070.

DEC Personal Computer Special Interest Group, see NSW entry.

KAOS-W.A., Gerry Ligtermoet, (09)450-5081, 39 Cloister Ave., Manning 6152. For Ohio Scientific Users.

OSWEST-OSborne UsersGroup of WA, (09)330-3439.

Kaypro User Group of WA, Ainslie Sharpe, P.O. Box 91, Claremont 6010. (09)384-5511. meetings second and fourth Mondays of each month in the canteen of the Department of Agriculture, Jarrah Road, South Perth.

Perth 80 Users Group, C. Powell. (09)457-6849. For system 80 and TRS 80 Users.

Perth Hitachi Peach Club, The Secretary, 1 Charf Court, Riverton 6155. (09)367-5880. For Hitachi Peach and 6809s.

Sorcerer Computer Users of Aust, The Secretary, 90 King George St, Perth South 6151. (09)367-6351.

Super 80 Users Group Perth, Garry Black, 19 Bendigo Way, City Beach 6015. (09)385-8813.

The WA Atari Computer Club, Alf Gaebler (Secretary). P.O. Box 7169, Cloisters Square, Perth 6000.

WA Microbee Club, Mike Osborn. (09)447-5366.

VIC-Ups, G. Padfield. (09)451-4629.

WA Wizzard Users Group, John Reid, 13 Wenlock Road, Wattleup 6166. (09)410-2359.

WA ZX Users Group, Phil Taylor. (09)328-4111 bh.

WA University Computer Club, Second Floor, University of WA, Guild Building. (09)386-1455.

Tasmania

DEC Personal Computer Special Interest Group, see NSW entry.

Devonport Computer Interest Group, John Steveson, R.S.D. 422, Sheffield Tasmania 7306. (004)92-3237.

Spectravideo Computer Users Group, W. P. Deckert, 48 Heather St, Launceston 7250. 44-4836. Membership to the club costs \$15 which entitles members to a newsletter and to discounts on computer equipment.

TASBEEB, John Hannon, P.O. Box 25, North Hobart 7000. Meetings first Monday each month at Elizabethan Matriculation College in D Block at 8 pm. (002)34-2704. For BBC computers.

Tasmanian TI User Group, Co-ordinator, 1 Benboyd Court, Rokeby 7019. (002)29-4009. Meetings third Sunday of each month at University of Tasmania, room 373.

TAS-Micro, Peter Deckert, Unit 1/456 West Tamar Road, Riverside, Launceston 7250.

Tasmanian Commodore Users Assoc, Vincent T. Staggard, The Secretary, G.P.O. Box 391D, Hobart 7000. (002)72-0295. Commodore and others.

Tasmanian OSI User Group, David Tasker, 111 Bass Highway, Westbury 7303.

N.Z.


1802 Users Group, P.O. Box 6210, Auckland, New Zealand. For those who own an ETI-660 or a COSMAC VIP, you can contact the 1802 Users Group. Be kind and send them a return addressed envelope and some International Reply Coupons.

Nelson Vic Users Group, Peter Archer, Nelson VIC Users Group, C/- P.O. Box 860, Nelson NZ, for VIC and Commodore.

Wellington Microcomputer Soc. Inc., Lindsay Williams, 2 Pope St, Pimberton, New Zealand.

ZX81 Club, R. Skelton, C/- Harbourside Orchard, Waiuku, New Zealand.

THE ONE YOU'VE BEEN WAITING FOR!



The **Radio Experimenter's Handbook**, Volume 1, from Electronics Today International is 132 pages chock-full of circuits, projects to build, antennas to erect, hints and tips. It covers the field from DX listening to building radioteletype gear, from 'twilight zone' DX to VHF power amplifiers, from building a radio FAX picture decoder to designing loaded and trap dipoles.

Edited by Roger Harrison, VK2ZTB, this book carries a wealth of practical, down-to-earth information useful to anyone interested in the art and science of radio. \$7.95 from your newsagent or through selected electronics suppliers. It is also available mail order through **ETI Book Sales, P.O. Box 227, Waterloo NSW 2017** (please add \$1.75 post and handling when ordering by mail).

```
1 OPEN 3,4
2 CMD 3
3 PRINT"GOLD LOTTO"
4 LIST
5 REM LUCKY LOTTO BY
10 POKE36879,122
15 FORN=1T05
20 Q(N)=INT(RND(1)*40)+1
25 NEXT
30 FORY=1T05
35 FORZ=1T05
40 IFQ(Z)>Q(Z+1)THENR=Q(Z):
   Q(Z)=Q(Z+1):Q(Z+1)=R
```

```
45 NEXT
50 NEXT
55 FORS=1T05
60 IFQ(S)=Q(S+1)THENQ(S)=INT(RND(1)*40)+1:GOTO30
65 NEXT
100 PRINT"J"
110 PRINT"      GOLD LOTTO  "
120 PRINT"000 1  2  3  4  5  6  7"
130 PRINT"00 8  9 10 11 12 13 14"
140 PRINT"015 16 17 18 19 20 21"
150 PRINT"022 23 24 25 26 27 28"
160 PRINT"029 30 31 32 33 34 35"
170 PRINT"036 37 38 39 40"
200 IFQ(1)=10RQ(2)=10RQ(3)=10RQ(4)=10RQ(5)=10RQ(6)=1THENPOKE38488+1,0
205 IFQ(1)=20RQ(2)=20RQ(3)=20RQ(4)=20RQ(5)=20RQ(6)=2THENPOKE38488+4,0
210 IFQ(1)=30RQ(2)=30RQ(3)=30RQ(4)=30RQ(5)=30RQ(6)=3THENPOKE38488+7,0
215 IFQ(1)=40RQ(2)=40RQ(3)=40RQ(4)=40RQ(5)=40RQ(6)=4THENPOKE38488+10,0
220 IFQ(1)=50RQ(2)=50RQ(3)=50RQ(4)=50RQ(5)=50RQ(6)=5THENPOKE38488+13,0
225 IFQ(1)=60RQ(2)=60RQ(3)=60RQ(4)=60RQ(5)=60RQ(6)=6THENPOKE38488+16,0
230 IFQ(1)=70RQ(2)=70RQ(3)=70RQ(4)=70RQ(5)=70RQ(6)=7THENPOKE38488+19,0
235 IFQ(1)=80RQ(2)=80RQ(3)=80RQ(4)=80RQ(5)=80RQ(6)=8THENPOKE38532+1,0
240 IFQ(1)=90RQ(2)=90RQ(3)=90RQ(4)=90RQ(5)=90RQ(6)=9THENPOKE38532+4,0
245 IFQ(1)=100RQ(2)=100RQ(3)=100RQ(4)=100RQ(5)=100RQ(6)=10THENPOKE38538,0:POKE38539,0
250 IFQ(1)=110RQ(2)=110RQ(3)=110RQ(4)=110RQ(5)=110RQ(6)=11THENPOKE38541,0:POKE38542,0
255 IFQ(1)=120RQ(2)=120RQ(3)=120RQ(4)=120RQ(5)=120RQ(6)=12THENPOKE38544,0:POKE38545,0
260 IFQ(1)=130RQ(2)=130RQ(3)=130RQ(4)=130RQ(5)=130RQ(6)=13THENPOKE38547,0:POKE38548,0
265 IFQ(1)=140RQ(2)=140RQ(3)=140RQ(4)=140RQ(5)=140RQ(6)=14THENPOKE38550,0:POKE38551,0
270 IFQ(1)=150RQ(2)=150RQ(3)=150RQ(4)=150RQ(5)=150RQ(6)=15THENPOKE38576,0:POKE38576+1,0
275 IFQ(1)=160RQ(2)=160RQ(3)=160RQ(4)=160RQ(5)=160RQ(6)=16THENPOKE38579,0:POKE38580,0
280 IFQ(1)=170RQ(2)=170RQ(3)=170RQ(4)=170RQ(5)=170RQ(6)=17THENPOKE38582,0:POKE38583,0
285 IFQ(1)=180RQ(2)=180RQ(3)=180RQ(4)=180RQ(5)=180RQ(6)=18THENPOKE38585,0:POKE38586,0
290 IFQ(1)=190RQ(2)=190RQ(3)=190RQ(4)=190RQ(5)=190RQ(6)=19THENPOKE38588,0:POKE38589,0
295 IFQ(1)=200RQ(2)=200RQ(3)=200RQ(4)=200RQ(5)=200RQ(6)=20THENPOKE38591,0:POKE38592,0
300 IFQ(1)=210RQ(2)=210RQ(3)=210RQ(4)=210RQ(5)=210RQ(6)=21THENPOKE38594,0:POKE38595,0
305 IFQ(1)=220RQ(2)=220RQ(3)=220RQ(4)=220RQ(5)=220RQ(6)=22THENPOKE38620,0:POKE38620+1,0
310 IFQ(1)=230RQ(2)=230RQ(3)=230RQ(4)=230RQ(5)=230RQ(6)=23THENPOKE38623,0:POKE38624,0
315 IFQ(1)=240RQ(2)=240RQ(3)=240RQ(4)=240RQ(5)=240RQ(6)=24THENPOKE38626,0:POKE38627,0
320 IFQ(1)=250RQ(2)=250RQ(3)=250RQ(4)=250RQ(5)=250RQ(6)=25THENPOKE38629,0:POKE38630,0
325 IFQ(1)=260RQ(2)=260RQ(3)=260RQ(4)=260RQ(5)=260RQ(6)=26THENPOKE38632,0:POKE38633,0
330 IFQ(1)=270RQ(2)=270RQ(3)=270RQ(4)=270RQ(5)=270RQ(6)=27THENPOKE38635,0:POKE38636,0
335 IFQ(1)=280RQ(2)=280RQ(3)=280RQ(4)=280RQ(5)=280RQ(6)=28THENPOKE38638,0:POKE38639,0
340 IFQ(1)=290RQ(2)=290RQ(3)=290RQ(4)=290RQ(5)=290RQ(6)=29THENPOKE38664,0:POKE38664+1,0
345 IFQ(1)=300RQ(2)=300RQ(3)=300RQ(4)=300RQ(5)=300RQ(6)=30THENPOKE38667,0:POKE38668,0
350 IFQ(1)=310RQ(2)=310RQ(3)=310RQ(4)=310RQ(5)=310RQ(6)=31THENPOKE38670,0:POKE38671,0
355 IFQ(1)=320RQ(2)=320RQ(3)=320RQ(4)=320RQ(5)=320RQ(6)=32THENPOKE38673,0:POKE38674,0
360 IFQ(1)=330RQ(2)=330RQ(3)=330RQ(4)=330RQ(5)=330RQ(6)=33THENPOKE38676,0:POKE38677,0
365 IFQ(1)=340RQ(2)=340RQ(3)=340RQ(4)=340RQ(5)=340RQ(6)=34THENPOKE38679,0:POKE38680,0
370 IFQ(1)=350RQ(2)=350RQ(3)=350RQ(4)=350RQ(5)=350RQ(6)=35THENPOKE38682,0:POKE38683,0
```

LUCKY LOTTO

The object of the 'Lucky Lotto' program for the VIC-20 is to select six random numbers and to display them in the form of a coupon. Line 10 gives the screen a yellow background, while lines 15-20 do the number selection and make sure that no number is repeated. Lines 100-170 print a coupon with red figures, and then lines 200-395 turn the selected numbers black.

D. J. Donoghue, Inhala Qld

COMMODORE COLUMN

```

875 IFQ(1)=360RQ(2)=360RQ(3)=360RQ(4)=360RQ(5)=360RQ(6)=36THENPOKE38708,0:POKE38
708+1,0
880 IFQ(1)=370RQ(2)=370RQ(3)=370RQ(4)=370RQ(5)=370RQ(6)=37THENPOKE38711,0:POKE38
712,0
885 IFQ(1)=380RQ(2)=380RQ(3)=380RQ(4)=380RQ(5)=380RQ(6)=38THENPOKE38714,0:POKE38
715,0
890 IFQ(1)=390RQ(2)=390RQ(3)=390RQ(4)=390RQ(5)=390RQ(6)=39THENPOKE38717,0:POKE38
718,0
895 IFQ(1)=400RQ(2)=400RQ(3)=400RQ(4)=400RQ(5)=400RQ(6)=40THENPOKE38720,0:POKE38
721,0
900 PRINT"GO TO GET NEXT CARD"
910 PRINT"DO HIT ANY KEY"
920 GETA$:IFA$=""THEN420
930 RUN

```

READY.

INVADER MATH

Ric Kube, Waikerie, SA

This game will work with the unexpanded VIC or with the 3K expansion board.

```

10 REM INVADER MATH
20 FORN=7384T07384+15:READA:POKEA,A:NEXT:FORN=7424T07431:POKEA,0:NEXT
30 DATA36,126,219,219,219,126,36,195
40 DATA146,84,56,254,56,84,146,0
50 POKE36869,255:PRINT"Q"TAB(5)"INVADER MATH":POKE36879,8
60 FORA=0T010:POKE36878,13:FORB=255T0128STEP-19:POKE36877,B:POKE36875,B
70 POKE7680+A*23,27:POKE7701+A*21,27:POKE38400+A*23,3
80 POKE38421+A*21,3:FORP=1T0200:NEXT:NEXT:POKE7680+A*23,32:POKE7701+A*21,32:POKE
36878,0:NEXT
90 POKE7910,27:POKE38400+22*11+10,3:POKE36877,0:POKE36875,0
100 PRINT"SHOOT TO SHOOT THE INVADER YOU NEED TO TYPE THE ANSWER TO THE"
110 PRINT"Q:PROBLEM. IF YOU SUCCEEDED, ANOTHER WILL APPEAR SOMEWHERE ELSE FOR YOU TO
SHOOT"
115 PRINT"DO YOU WANT TO ADD OR MULTIPLY"
116 GETA$:IFA$=""THEN116
117 IFA$="A"THENZ2=1:GOTO120
118 IFA$="M"THENZ2=2:GOTO120
119 GOTO116
120 PRINT"PRESS ANY KEY"
121 GETA$:IFA$=""THEN130
122 PRINT"Q"TAB(5)"INVADER MATH"
130 FORA=10T00STEP-1:POKE36878,15:FORB=255T0128STEP-19:POKE36877,B:POKE36875,B
140 POKE7680+A*23,27:POKE7701+A*21,27:POKE38400+A*23,3
150 POKE38421+A*21,3:FORP=1T0200:NEXT:NEXT:POKE7680+A*23,32:POKE7701+A*21,32:POK
E36878,0:NEXT
160 POKE7910,27:POKE38400+22*11+10,3:POKE36877,0:POKE36875,0
170 PRINT"Q:PROBLEM INVADER MATH"
180 S=72:D=0:FORY=1T09:POKE7746+22*Y,186-Y:POKE7966+2*Y,Y+176:NEXT
190 Q=(INT(RND(1)*9)*2)+2:FORR=INT(RND(1)*7)+1T08
200 LA=7768+Q*R*22:POKE36878,15:CO=30720
210 FORL=7768+Q*TLASTEP-22
220 POKE7746+Q*R*22,3:POKE36877,200:POKE36875,155:FORPA=1T015
230 NEXT:POKE36877,0:POKE36875,0:POKE7746+Q*R*22,3:POKE36876,0
240 PRINTTAB(4)"SCORE"0
250 PRINTTAB(4)"HIGH SCORE"HI
260 ANS=0
270 PRINT"YOUR ANSWER IS ":INPUTANS
280 PRINT"
290 IFZ2=1ANDANS=(Q/2)*(9-R)THEN480
300 IFZ2=2ANDANS=(Q/2)*((9-R)THEN480
310 S=S-R:IFC<=0THEN400
320 POKE7768+Q*R*22,32
330 IFR=8THEN510
340 R=R+1:POKE36877,200:POKE36875,155:FORPA=1T015:NEXT:POKE36877,0:POKE36875,0:G
OTO280
350 PRINT"GAME OVER"
360 IFD>HITHENHI=D
370 PRINT"HIGH SCORE: HI"
380 FORN=1T0500:NEXT
390 POKE198,0:PRINT"ANOTHER GAME?"
400 GETA$:IFA$=""THEN450
410 IFA$="Y"THENPOKE36869,240:POKE36879,27:PRINT"Q":END
420 GOTO210
430 POKE7768+Q*R*22,28:POKE7768+Q*R*22,2
440 POKE36877,255:FORL=15T00STEP-2:POKE36878,L:FORM=1T0250:NEXTM,L:POKE36877,0:P
OKE36878,0
450 D=D+1
460 FORN=1T0500:NEXT
470 POKE7768+Q*R*22,32:GOTO230

```

READY.

You need not own a bank to have a personal computer. Look at our prices.


64K Z80 & 6502 CPU IBM look-a-like case detachable keyboard 188 function keys, 10 user define keys \$480




Apple Computer keyboards \$130 + Tax
Boxes \$50 + Tax. Power supplies \$55 + Tax



12" green & amber monitors high frequency, from \$120.00



Teac Floppy disk drives suitable Apple II, with Direct Drive from \$230.00




Dot matrix printers using continuous and sheet paper \$265.00
Daisy wheel printer, letter quality \$475.00



Floppy Disks 5 1/4" and 8" S/S, D/S, S/D & D/D, from \$2.10

Add-on Cards, 80 column, Parallel cards, RS232
Serial card, Disk card (2),
Pal card, Printer card,
Clock card, Eprom writer
card, Speak card.



Also stepping motors
Servo motors
Synchronous motors
Digital Instruments
Presettable counters
Tachymeters & Panel meters
Ring or send 60c postage for free catalogue.

G.C.S. Computers

G.C.S. Sydney — 67 Blackshaw Ave.,
Mortdale. 2223. Phone (02) 570 1225
Wollongong — 46 Charles Road, Fairy
Meadows. Phone (042) 84-5544.
Enquiries from agents and distributors invited.

FOR 30¢ POST AN ORDER TO ONE OF ALTRONICS COMPETITORS

— naturally you won't have a clue as to whether they've got the items you need available. And of course, be prepared to wait, wait, patiently wait sometimes for weeks!
Why waste your valuable cash? Altronics staff are waiting for your call now (up to 6pm eastern standard time).

GO ANYWHERE 12-240V POWER



These great Inverter kits enable you to power 240V appliances from a 12V DC power source. Tremendous for camping, fishing etc. Install into your Car, Boat or Caravan.


A fully regulated and overload protected design, featuring XTAL locked frequency. Use to power hi-fi, TV sets, even electric drills for short time periods.
MANY OF THESE KITS ARE NOW IN USE FOR EMERGENCY LIGHTING PURPOSES.
 ALTRONICS KIT features: Gold plated edge connector and PCB huss; Low age rate XTAL; Sockets for all IC's; High Efficiency Transformer.
 K6750..... (EA JUNE 82) ... **\$199.50**

(\$10 DELIVERY AUSTRALIA WIDE)

40 WATT MODEL

Suits small appliances, ie. Turntables, Tape Decks, Shavers etc. Variable frequency adjustment enables speed control of turntables. Works as a trickle charger when mains power is available.
 EASY CONSTRUCTION — VALUE PLUS

K6700..... **\$55.00**



MICRON SUPER 80

WAS \$699 in 1983

FREE CARTON OF PAPER THIS MONTH CAT D1160 **\$39.50** VALUE



D1174 **\$399**

Your Super 80 printer will enable you to print letters, reports, graphics generated pictures, etc and importantly for the programmer. Hard Copy of program listings.
 Operating under software control from any general purpose micro-computer the Super 80 features 13 different print types including emphasized (LETTER QUALITY) Bidirectional print action ensures smooth, quiet operation.

Superlative

MICRON SERIES II MONITORS

Just arrived, the Fabulous New Micron Amber Non Glare D 1116.

★ 1050 lines resolution at centre screen. ★ 22MHz bandwidth. ★ Video input impedance switch allows networking use. ★ Incredible — repeat incredible — resolution.

SPECIFICATIONS:
 Screen — Green phosphor. **Front Controls** — Power on/off, character brightness/intensity, display centering.
Rear Controls — Background intensity, vertical and horizontal adjustment etc.
Input impedance — Switch 75/10K Ω.
DC Socket — 12V DC output at 1.1 amp — power your micro direct from the monitor.
Bandwidth — 10Hz-22MHz. **Resolution** — 1050 lines minimum at centre screen.

Guaranteed (we mean it) to outperform all other low cost monitors in Australia.

D 1115 Micron 11 GREEN SCREEN **\$199.50**
SAVE \$20


D 1116 Micron 11 AMBER SCREEN **\$210.00**
SAVE \$20

Both D 1115 and D 1116 utilize Non Glare High Grade Monitor Tubes.




Monitor Stand — pans and tilts to any angle — Universal type fits all Monitors.

D 1100 Value Plus **\$29.95**



NEW MODEL DATA CASSETTE

UNCONDITIONALLY GUARANTEED TO SAVE/LOAD THE RAWEST OF DATA EVERYTIME!



D1122..... **\$49.50**

A recorder designed solely for the purposes of data storage now at an unbelievable price
 ★ SLIDE VOLUME CONTROL a must for quick checking of levels.
 ★ TAPE COUNTER a must for easy location of programmes.
 ★ INBUILT PIEZO TRANSDUCER enables you to listen audibly to tape level.
 ★ 6V DC operation - USE WITH M9000 PLUG PACK ensures low hum levels.
 ★ ROBUST CONSTRUCTION OF BOTH INTERNAL MECHANISMS AND EXTERNAL CASE.
 ★ LONG LIFE ALKALINE BATTERY SUPPLIED (4 x AA CELLS)

BONUS OFFER

10 FREE MICRON C20 DATA CASSETTE TAPES (CAT D1141) INCLUDED WITH EVERY DATA CASSETTE PLAYER PURCHASED THIS MONTH


(NOT AVAILABLE FROM DEALERS — SHOP AND MAIL ORDER ONLY)

HITACHI F SERIES SQUARE SCREEN DUAL BEAM CRO

V-212 DC to 20 MHz,
 1 mV/div, DUAL-TRACE

Incredible Offer
 Incredible Offer

20 only be Quick



We're overstocked so we are offering **\$100 off** plus a free Coline 10:1 probe Cat. Q 0153 (\$35 value)

This offer is valid for current stocks only — so here is your chance to treat yourself to an absolutely top piece of test gear that will last you a lifetime.

Q 0152 ~~\$699~~ Now **\$599**

\$100 off and free 10:1 Coline Probe this Month

Oscilloscope Probe Kit

Part No: 900-95-527



ALTRONICS PRINTER PAPER

We searched the world for this superb low cost printer paper. The smooth texture finish is nearly 'Bond' quality. Faintly ruled one side and pure white the other i.e. ideal for all types of printer application.

You could easily pay 50% more elsewhere for equivalent quality.

Two Types Available.

D 1160 240mm Wide 2000 sheets suits Popular printers **\$39.50**

D 1165 380mm Wide 2000 sheets suits Commercial Printers **\$47.50**

INSTANT SUPER TYPE GLUE



New patented easy flow Dispenser and carry tube dispenses only when tube body is depressed - ensures no leaks. Many times the number of bonds over conventional tubes.
 Sticks in seconds. 1000's of uses.

T 3010 **\$2.95** 10 up **\$2.50**

PROFESSIONAL AUTOMATIC WIRE STRIPPER

Automatically adjusts to insulation / wire diameter.
 This absolutely brilliant stripper is the finest we've ever used.



T 1520

\$9.50

TOP QUALITY MAINS LEADS
 MADE IN AUSTRALIA



BE QUICK LIMITED STOCKS

A2400 **\$1.50**

100 up **\$1.20**

OR FOR 15¢ PHONE YOUR ORDER TOLL FREE ON 008-999-007

We will immediately confirm stock availability. We will also confirm the very hour your order will be dispatched (over 95% of orders leave the same day). With Jet Service Delivery we deliver next day to capital cities and suburbs — Country areas please add 24 to 48 hours. Available bankcard holders only — sorry non-bankcard holders must post a cheque or money order — even so, we promise to deliver quicker than any other supplier in Australia.


INSTRUMENT CASES

Our superb instrument cases will give your projects the professional appearance they deserve.

WAS NOW 10+
H0480 \$13.50 \$11.50 \$ 9.50
H0482 \$17.50 \$15.00 \$12.25

OEM's — Manufacturers — Bulk Users. Your product will look like it's straight out of 'Hewlett Packard's' factory with these brilliant low cost cases. Contact our Wholesale Department for Bulk Prices.

H0480
Size: 200W x 160D x 70H




H0482 VENTED
Size: 260W x 190D x 80H

- Internal mounting posts enable a wide combination of PCB's Transformers etc. to be accommodated (screws supplied).
- Removable front and rear panels. Attractive textured finish one side and plain the reverse side. (Enables direct engraving, silk screen printing etc. to plain side).

- Top and bottom split apart for ease of construction or service. Integral feet included.
- Great for test instrument and other high grade projects.
- PCB guide rails provided internally allow vertical PCB positioning to several locations.

QUALITY "SGS"

PRICE SLAUGHTER ON GENUINE HITACHI MOSFETS (PRIME SPEC)



Z1510 2SK 134
Z1512 2SJ 49


\$5.90 EA
\$5.50 10up.

2N3055'S SLASHED



Z1174 **\$1 EA**

DROP PROOF MULTIMETER With overload protection



- 20,000 ohms/Volt DC • 10,000 ohms/Volt AC
- Taut band meter movement • Integral bench stand • Uses 1 x AA cell • Comes complete with battery test leads and instructions.
- **RANGES DC Voltage:** 0.3 3 12 30 120 300 1200 AC voltage 12 30 120 1200 DC current 60uA 3 30 300 mA Resistance 0-5 Meg in 5 ranges
- Battery test Lo 50 mA (1.5V) Hi 250 mA (1.5V)
- With temperature range See right

Q 1030 **\$39.50** **\$29.50**
Q 1035 Carry Case **\$12.50**

TEMPERATURE PROBE

Use with our Q1030 multimeter to measure from -50°C to 250°C — that's right — a full 300°C range. Now you can check heatsink temperatures, transistor and IC cases — even how cold your beer is! Great value

Q 1036 **\$15.00**

POCKET SIZE MULTIMETER WITH MIRRORED SCALE

- 10,000 ohms/Volt DC
- 4,000 ohms/Volt AC • Fuse and diode overload protection
- A total of 19 ranges • Uses 1 x AA cell (included)

Ranges: DC Voltage 0.25, 2.5, 25, 250, 1000 AC voltage 10, 50, 250, 1000 DC current 0.1, 10, 500 mA Resistance 0-10 Meg in 3 ranges

- Safety off position to protect the meter movement. Feature packed




Q 1015 ~~\$19.50~~ **\$15.00**

LABORATORY SERIES MULTIMETER

Superb European styling with quality Beckman style rotary switch. Features mirror backed scale to help eliminate parallax errors.

Ranges: DC Voltage 2.5, 10, 50, 250, 1000 AC voltage 10, 50, 250, 1000 DC current 5, 50, 500 mA and 10A position Battery test 1.5V AA, 1.5V C and D 9V Sensitivity 20,000 ohms/Volt DC Also features dB scale




Q 1020 ~~\$27.50~~ **\$19.95**

10 AMP DC RANGE

UNIVERSAL MULTIMETER PORTABLE WITH BENCH STAND 23 RANGES


- 20,000 ohms/Volt DC • 10,000 ohms/Volt AC • Mirror backed scale
- Overload protected • Unique carry handle doubles as a bench stand
- High-impact resistant case • Uses 1 x AA cell • Comes complete with test leads, instructions and battery. **Ranges:** DC Voltage 0.25, 1, 2.5, 10, 25, 100, 250, 1000 AC voltage 10, 25, 100, 250, 1000 Decibels 20 to +22dB DC current 50, 500uA, 5, 50, 500 mA Ohm meter 0-6 megohms in 4 ranges, 30 ohms centre scale. Size 135 x 91 x 39 mm



Q 1002 ~~\$24.50~~ **\$17.50**
Q 1012 Carry Case **\$3.50**

LABORATORY MULTIMETER

100K ohms/Volt Checks: Transistors Capacitors



Q 1041 Carry Case **\$17.50**

Q 1040 ~~\$89.95~~ **\$74.50**

Massive Savings on our Brilliant Quality Multimeters this Month Save up to 40%

From Tokyo Laboratories, Japan

Remember the days when high grade precision laboratory multimeters were available only from the UK and then they cost a king's ransom? — Well that's history — The new Q 1040 is everything a high quality meter should be PLUS it checks transistor HFE and ICO and measures capacitors from 50 pF to 50 uF.

- 100K ohms/Volt DC Ranges • 8.5 uA movement
- Fuse and diode movement protected • Inbuilt oscillator for capacitance measurement
- Ranges:** DC voltage 250mV 2.5V 10V 50V 250V 1000V AC voltage 5V 10V 50V 250V 1000V DC current 10uA 2.5mA 25mA 500mA 10A AC current 10A Resistance x1, x10, x1K, x10K Transistors NPN: PNP HFE 0-1000 ICO 0-50uA Capacitors 50pF to 50uF, 0.1uF to 50uF

ECONOMY TESTER

OVERLOAD PROTECTED



- High 2000 ohms/Volt sensitivity
- Overload protected
- Dimensions 90 x 60 x 30 mm
- Mirror back scale helps prevent parallax error • Complete with test leads and instructions
- Uses 1 x AA battery (supplied)
- Ranges:** DC and AC 0-10 50 250 1000V Decibels 10 to +22 dB Current 0-100mA Ohms 0-1 Meg in two ranges

Q 1001 ~~\$14.50~~ **\$9.50**
Q 1011 Carry Case **\$2.50**

ALTRONICS 105 STIRLING ST. PERTH — FOR INSTANT SERVICE

008 999 007 TOLL FREE
(09) 328 1599 PERTH METRO AREA & AFTER HOURS RECORDED SERVICE
All Mail Orders: Box 8280, Stirling St. Perth, WA 6000.

ALTRONICS RESELLERS

Please note that resellers may not have all the items advertised in stock, and as resellers have to bear the cost of freight, prices may be slightly higher than advertised. ALTRONICS resellers prices should however represent a considerable saving over our competitors' prices.

phone toll free 6am-8pm — for personal service, or take advantage of our 24 Hour 7 day p/week Bankcard phone order service. Give your name address with postcode, phone number, bankcard number and expiry date then your order — and presto your order will be processed and back to you in a flash. — Please nominate Jetservice if you want overnight delivery.

\$2.50 DELIVERY AUSTRALIA WIDE. We process your order the day received and despatch via Australia Post. Allow approx. 7 days from day you post order to when you receive goods. Weight limited 10kgs.

\$4.50 DELIVERY AUSTRALIA WIDE. We process your order the day received and despatch via Jetservice for delivery next day.

BANKCARD HOLDERS CAN PHONE ORDERS UP TO 8PM (EST) FOR NEXT DAY DELIVERY — SOUNDS INCREDIBLE DOESN'T IT? Alright you cynics just try us! Weight limit 3.5kgs. Jetservice cannot deliver to P.O. box numbers (Australia Post would have a fit).

AUSTRALIA WIDE All orders over 10kgs **\$10.00 HEAVY HEAVY SERVICE** — that is — road express. Delivery time must travel on the heavy service, that is — road express. Delivery time 7 days average.

WA	VICTORIA	QUEENSLAND	SA	NSW	COFFS HARBOUR	
COUNTRY ALBANY BP Electronics ESPERANCE Esperance Communications GERALDTON Geraldton TV and Radio KALGOORLIE Today's Electronics MANDURAH Kathleen's WYALKATCHAM D & J Pearce NT DARWIN Telecom ALICE SPRINGS Ascom Electronics Janner Electronics ACT CITY Electronic Components Scotronics Australia	CITY All Electronic Components Electronics Madgraths Communications SUBURBAN BENTLEIGH Absolute Electronics BOX HILL SOUTH Eastern Communications CHELTENHAM Talking Electronics FOOTSCRAY Acon Electronics SOUTH CROYDON Thruon Electronics COUNTRY BENDIGO Lindree & Johnson MILDURA Electronic and Digital Services SHEPPARTON GV Electronics	CITY Delson P.L. SUBURBAN FORTITUDE VALLEY St. Lucia Electronics PADDINGTON DCO Technics SALISBURY Colourview, Wholesale SLACKS CREEK David Hall Electronics COUNTRY CAIRNS Thompson Instrument Services GLADSTONE Purley Electronics TOOWOOMBA Nambour Electronics PALM BEACH The Electronics Centre ROCKHAMPTON Purley Electronics TOOWOOMBA Hunts Electronics TOWNSVILLE Solex	CITY Protomics Gerard & Goodman SUBURBAN BRIGHTON Brighton Electronics CHRISTIES BEACH Force Electronics KESWICK Freeway Electric Wholesalers PROSPECT Jensen Electronics REYNELLA Force Electronics TASMANIA CITY D & I Agencies GEORGE HARVEY Hobart Launceston	CITY Avtek Electronics David Reid Electronics Jaycar Radio Dispatch SUBURBAN CARLINGFORD Jaycar CONCORD DEE WHY David Ryall ENFIELD Avtek HURSTVILLE Jaycar LEWISHAM PrePak Electronics MATTRAVILLE Creative Electronics COUNTRY ALBURY Webb's Electronics BATHURST Sound of Music BROKEN HILL Crystal TV	COFFS HARBOUR Gulf's Harbour Electronics GOSFORD Jaycar Electronics KURRI KURRI Jaycar NEWCASTLE D.G.E. Systems George Brown & Co. NAAAA Vencom Electronics PENRITH Avtek Electronics PART MACQUARIE Hall of Electronics RAYMOND TERRACE Albark Electronics RICHMOND Vetco Electronics WARRIOR Landmark Communications TES Electronics WINDANG Maden Electronics WINDSOR M & E Electronic Communications	52 5684 24 7946 37 2141 86 1625 69 6399 21 4011 21 2409 83 7440 87 3419 78 4277 65 4622 96 4144 96 5066 77 5935

Altronics Resellers wanted in all States of Australia (including W.A.)

Phone Steve Wroblewski 09 3817233 for Details.

OEM's for bulk rates contact us on 09 3817233 for super competitive rates.

Software Duplication

COMMODORE - APPLE - IBM PC AND MOST OTHER FORMATS

Totally independent software diskette and cassette duplicating service using specialized hi speed duplication equipment.



INDEPENDENT SOFTWARE DUPLICATION

3 Park Avenue, Westmead, New South Wales, 2145
P.O. Box 545, Parramatta N.S.W., 2150
Telephone (02) 635 0704

68000/6500 PRICES SLASHED

68000	6MHz, 64 Pin Dip (8 & 10 MHz avail.)	A\$28.80
65C02P-1	1MHz, Enhanced instruction set	9.90
65C02P-2	2MHz	10.89
6502A	CPU, 40 Pin, Clock, 64K	6.30
6511AQ	Single Chip Micro, CPU, RAM, 2MHz, RS232, Timer	15.57
6541Q	Periph. Controller, RAM, 23 I/O, Host Slave I/F Timer	10.26
6541AQ	2MHz	11.25
6522	VIA 40 Pin, two 8 bit I/O Ports	5.04
65C21	CMOS PIA	7.20
6522A	2MHz	5.58
6532A	COMBO 40 Pin, 2MHz	6.93
6545A-1	CRT Controller	10.35
6551	ACIA 28 Pin, SW Prog. Baud Rate	6.03
65C51	CMOS ACIA	9.62
6551A	2MHz	6.66
6592	Single Chip Printer Controller (for EPSOM Series 200 and 500 Printer)	10.35
2716	2K x 8 EPROM 450nSec	4.36
2532	4K x 8 EPROM	6.05
2732	4K x 8 EPROM	6.05
2764	8K x 8 EPROM	12.03
5213	2K x 8, 5V, EPROM	27.00
QUIP 64	Socket for 6511Q and 6541Q	1.85
CRYSTALS	1.8432MHz, 2.00MHz	2.86
	32.768KHz, 3.686MHz,	1.82
	8.00MHz, 4.00MHz, 12.00MHz	

Plus Sales Tax, Postage and Pack (where applicable). Prepaid orders less 4%.



P.O. Box 6502, Goodna, QLD 4300
BRISBANE — AUSTRALIA
Phone: (07) 288-2455
Telex: AA43778 ENECON

XIDEX PRECISION FLEXIBLE DISKS QUALITY RETAILERS

N.S.W.

DICK SMITH STORES: ALBURY, AUBURN, BANKSTOWN SQUARE, BLAKEHURST, BONDI JUNCTION, BROOKVALE, CHULLORA, GORE HILL, GOSFORD, HORNSBY, LIVERPOOL, NEWCASTLE, NORTH RYDE, PARRAMATTA, PENRITH, RAILWAY SQUARE 2000, BRIDGE ST. SYDNEY, YORK ST. SYDNEY, TAMWORTH, WOLLONGONG.

AUZ ELECTRONICS CO.

248 Merrylands Rd, Merrylands.

COMPUTER GALLERIE, 66 Walker St, North Sydney.

COMPUTER LIGHTHOUSE, 320 High St, Penrith.

COMPUTER VILLAGE

119 Horton St, Port Macquarie.

COMPUTERLAND BURWOOD,

31 Burwood Rd, Burwood.

COMPUTERTIME, 345 Victoria Ave, Chatswood.

GRACE BROS., 77 Marsden St, Parramatta.

NSW INSTITUTE OF TECHNOLOGY, UNION SHOP,

Tower Bldg, One, Broadway.

JAYCAR PTY. LTD.,

117 York St, Sydney.

Carlingford & Pennant Hills Rds., Carlingford.

115-117 Parramatta Rd, Concord.

121 Forest Rd, Hurstville.

PRESTIGE OFFICE EQUIPMENT,

3 Burwood Rd, Burwood.

SOUTHERN CROSS RESOURCES,

461 Pacific Hwy, Artarmon.

UNIVERSITY OF NSW UNION SHOP,

Lower Campus, Anzac Pde, Kensington.

ZAP ELECTRONICS, 60 George St, Parramatta.

Northgate Shopping Centre, Hornsby.

COFFS COPY CENTRE, 17 Park Ave, Coffs Harbour.

COLEMANS BUSINESS, 142 Darling St, Dubbo.

DATA CONCEPTS, 24 Moonee St, Coffs Harbour.

KOPI-KAT, Gang Gang St, Katoomba.

OFFICE DATA SYSTEMS, 100 Victoria St, Taree.

FAIR SOUTH COAST COMPUTER CO.,

106 Auckland St, Bega.

MAGMEDIA, 28 Buffalo Rd, Gladesville.

COMPU — K PTY. LTD., 7 Casino St, Sth. Lismore.

LOGIC SHOP, 330 Pacific Hwy, Crows Nest.

BERESPO COMPUTERS,

1/201 New South Head Rd, Edgecliffe.

PARRY OFFICE SUPPLIES

255 Molesworth St, Lismore

A.C.T.

DICK SMITH STORES: 98 Gladstone St, Fyshwick.

SWAINS PTY. LTD., 65 Gladstone St, Fyshwick.

Garema Place, Civic, Woden Shopping Centre.

Belconnen Hall, 123 Monaro St, Queanbeyan.

BOULEVARD BUSINESS SERVICES,

68 Wollongong St, Fyshwick.

STEVE'S COMMUNICATIONS,

57 Wollongong St, Fyshwick.

COMPUTECH,

Belconnen Church's Centre, Belconnen.

MAGMEDIA, 31 London Circuit, Canberra City.

VICTORIA

MYER HOME AND BUSINESS COMPUTER CENTRES.

DICK SMITH STORES: BALLARAT, BRIGHTON

(EAST), COBURG, FRANKSTON, GEELONG,

MELBOURNE, RICHMOND, SPRINGVALE.

MAGMEDIA, 100 Park St, South Melbourne.

SELECTED TOY WORLD STORES.

METROPOLITAN BUSINESS MACHINES,

338 Sydney Rd, Coburg.

COMPAK, 350 South Rd, Moorabbin.

COMPUTER 2000, 29 Ross Smith Ave, Frankston.

COMPUTER BIZ, 30 Armstrong St, North Ballarat.

ENTERCOM COMPUTER CO.,

136 Bridge Rd, Richmond.

HIGH TECHNOLOGY COMPUTER SYSTEMS,

87 Swan St, Richmond. 290 Bay St, Brighton.

HI TECH OFFICE SYSTEMS,

4 Commercial Rd, Morwell.

Desailly and Cunningham Sts, Sale.

HI FLIGHT COMPUTING SERVICES

110 Mt. Pleasant Rd, Belmont.

HARMON BROS., 359 Moorabool St, Geelong.

602 Sturt St, Ballarat.

HOME COMPUTER SERVICES,

"Junction Park", Kyalite.

devere COMPUTER ACCESSORIES,

294 Kingsway, South Melbourne.

ASTRO EDUCATIONAL SERVICES PTY. LTD.,

1/3 Ruby St, East Burwood.

DATA PARTS,

11 Edward St, Shepparton. 27 Bath Lane, Bendigo.

658 Dean St, Albury. 305 Mair St, Ballarat.

QUEENSLAND

MYER HOME AND BUSINESS COMPUTER CENTRES.

DICK SMITH STORES: BRISBANE, BURANDA,

CHERMSIDE, SOUTHPORT, TOOWOOMBA,

TOWNSVILLE.

MAGMEDIA,

Adelaide and Macrossan Sts, Brisbane.

UPSHOT ELECTRONICS, 135 Abbott St, Cairns.

COMPUTERWORLD, Hermit Pk, Townsville.

SOFTWARE 80, 105 Milton Rd, Milton.

AAB EQUIPMENT, 310 Mulgrave St, Cairns.

COMPSOFT, 537 Boundary St, Spring Hill.

C.P.U. COMPUTER CENTRE,

279 Junction Rd, Clayfield.

SHANNON ROBERTSON, 4 Carrol St, Nambour.

THE UNION CALCULATOR SHOP,

University of Queensland, St. Lucia.

SOUTH AUSTRALIA

MYERS HOME AND BUSINESS COMPUTER CENTRES

DICK SMITH STORES:

ADELAIDE, DARLINGTON, ENFIELD.

MAGMEDIA, 305 Morphett St, Adelaide.

MIKE SANDEMAN COMPUTERS,

9 Todd Mall, Alice Springs.

WESTERN TECHNOLOGY, 2 Clark Terrace, Seaton.

D.C. ELECTRONICS, 182 Gilles St, Adelaide.

LEEDALL OFFICE PRODUCTS,

91a Goodwood Rd., Goodwood.

WESTERN AUSTRALIA

DICK SMITH STORES: CANNINGTON, William St,

Perth. Centreway Arcade, Perth.

MAGMEDIA, 252 Stirling St, Perth.

BACKGAMMON SHOP,

City Centre — Perth.

Carousel Shopping Centre — Albany Hwy,

Cannington.

Mirrabooka Shopping Centre — Yirrigan Drive,

Mirrabooka.

Belmont Forum — Belmont Ave, Belmont.

Garden City Shopping Centre — Risely St,

Booragoon.

ALLIED OFFICE PRODUCTS,

Unit 4, Sandridge Crt, 13 Sandridge Rd, Bunbury.

JAYS BUSINESS EQUIPMENT,

105 Hay St, Subiaco.

GERALDS ELECTRICS, 179 Murray St, Perth.

366 Albany Hwy, Victoria Park.

MICRO BASE, 422 Newcastle St, West Perth.

SOFTWARE CENTRE,

Shop 8, Cremorne Arcade, 576 Hay St, Perth.

AUSTRALIAN COMPUTER ENTERPRISES,

1341 Albany Hwy, Kennington.

BOANS LTD.

COMPUTER AND ELECTRICAL DEPTS., PERTH,

Carousel Garden Centre, Grove Plaza, Innaloo,

Karrinyup, Morley, Albany, Bunbury, Geraldton.

NORTHERN TERRITORY

DICK SMITH STORES: Stuart St., Darwin.

TASMANIA

DICK SMITH STORES: Borrar St., Hobart.


NEW ZEALAND

DICK SMITH STORES: PAPATOETOE,

AVONDALE, NEWMARKET, HAMILTON.

XIDEX PRECISION FLEXIBLE DISKS.

BUY THE
100%
DISK



GET
ONE
FREE!

*Boxes or singles

We believe that Xidex precision disks are the best in the world and to prove it to you, we are offering you **DOUBLE THE PRODUCT** at half the normal price from our participating retailers! *This is a strictly limited offer and has a maximum quantity allowance of 2 boxes or 20 single disk purchases per application. So you had better be fast.

Why you will love Xidex!

- Xidex has superior electronic performance consistently better than all its competitors.
- 50% tighter hub hole diameter to avoid head to disk interchange problems.
- Longer wear via extensive polishing also helps avoid costly head wear.
- Thicker more protective jacket increases disk life and prevention of contamination and temperature damage.
- Quality controlled by 18 exacting tests that really make Xidex 'Precision' disks.
- We want you to have the best and come back to Xidex again and again so we offer you a **10 YEAR WARRANTY** on every disk you purchase.

BEAT THAT!

XIDEX PRECISION FLEXIBLE DISKS

Xidex 5012 — 10030 5 1/4" Single Sided, Double Density, Soft Sectors, 10 Pack, 40 Track Per Inch, (Single pack available)

Xidex 5022 — 10030 5 1/4" Double Sided, Double Density, Soft Sectors, 10 Pack, 40 Track Per Inch, (Single pack available)

Xidex 5012 — 2000 5 1/4" Single Sided, Double Density, Soft Sectors, 10 Pack, 80 Track Per Inch.

Xidex 5022 — 2000 5 1/4" Double Sided, Double Density, Soft Sectors, 10 Pack, 80 Track Per Inch.

Xidex 8012 — 1000 8" Single Sided, Double Density, Soft Sectors, 10 Pack, 40 Track Per Inch.

Xidex 8022 — 1000 8" Double Sided, Double Density, Soft Sectors, 10 Pack, 40 Track Per Inch.

Unique plastic library file each box of 10 disks!!

*Add 20% Sales Tax
PLUS \$1.00 POSTAGE IF APPLICABLE
OFFER ONLY VALID TILL OCTOBER 31ST, 1984 and is only available to customers who fill in the coupon below and present it with order or by mail. Facsimiles of coupon not acceptable.

ORDER FAST!

XIDEX ORDER FORM: PLEASE SUPPLY

NUMBER OF DISKS PURCHASED

5012 — 10030 — 5 1/4" : _____
SS — DD 10PCK — 40TP1 (SP AVAIL.)

5022 — 10030 — 5 1/4" : _____
DS — DD 10PCK — 40TP1 (SP AVAIL.)

5012 — 2000 — 5 1/4" : _____
SS — DD 10PCK — 80TP1

5022 — 2000 — 5 1/4" : _____
DS — DD 10PCK — 80TP1

8012 — 1000 — 8" : _____
SS — DD 10PCK — 40TP1

8022 — 1000 — 8" : _____
DS — DD 10PCK — 40TP1

APPLICATION FORM MUST BE COMPLETED IN FULL TO QUALIFY.
HAVE YOU ADDED SALES TAX AND POSTAGE?

NAME _____

COMPANY NAME _____

ADDRESS _____

POSTCODE _____

TYPE OF SYSTEM _____

USUAL BRAND OR TYPE _____

☐ CASH ☐ CHEQUE ☐ COMPANY ACCOUNT ☐ BANKCARD

PHONE NUMBER _____

SIGNATURE _____

BANKCARD NO. _____

EXPIRY DATE _____

803 Right Little

Single sideband slated for shortwave broadcasters

A recent decision at the World Administrative Radio Conference in Geneva will ensure that shortwave broadcasters will gradually move to single sideband (SSB) transmission over the next two decades.

It's a warning given in ample time so that radio listeners purchasing a new receiver can make certain it is capable of SSB reception.

Millions of listeners throughout the world will have to buy new receivers, or else the voices they hear now will turn to gibberish.

"It's going to be a lot like listening to Donald Duck" (the popular cartoon character) says

Walter Ireland, a communication specialist with the US State Department.

The International Telecommunications Union (ITU), a United Nations agency, recommended the conversion from the double-sideband amplitude modulated (AM) transmission system currently used to single sideband.

The change, under discussion for 10 years, will open up more

space on the crowded shortwave dial, but will also render many existing receivers and transmission equipment obsolete, a spokesman for the International Telecommunications Union in Geneva said.

It will be done gradually over 20 years, so receivers and transmitters designed for the current double-sideband (AM) broadcasts will work for a while, but will eventually become incompatible.

The 20-year duration will permit making the transformation at the lowest cost. Existing receivers have an estimated life-

span of about 10 years, while transmitters are good for about 15.

Although no one knows exactly how many people listen to shortwave, it is estimated that at least 100 million listeners will be affected throughout the world.

The decision to make the changeover was agreed upon at the World Administrative Radio Conference in Geneva earlier this year where 575 delegates from 115 countries attended. A date for starting the changeover is to be set at a follow-up conference in 1986.



World-wide talkback! Douglas Muggeridge, BBC's External Broadcasting Manager, prepares for a world phone-in last December with Margaret Howard.

BBC expands audience

One problem faced by international broadcasters is the difficulty of obtaining an accurate audience figure. Only in North America has the popularity of shortwave stations been recently surveyed.

Incoming mail is the main guideline by which stations estimate their audience. A report that the BBC External Service mail has shown a sharp increase has led to revised figures of their world-wide audience, formerly estimated at around 100 million listeners.

The mail pouring into Bush House, London, home of the BBC World Service, last year was 450,000 letters — an increase of 33 per cent on the

previous year!

Writing to the BBC from the Third World is an expensive undertaking due to the high postage cost and the meager family income. In the Eastern European countries there is always a threat of political reprisal if one writes to a broadcasting station in the West.

The BBC, along with several other international broadcasters, has set up post boxes at embassies, such as Delhi, where listeners can write to the BBC at the cost of only internal postage, as the letters are sent on in bulk from Delhi to London.

In a recent statement, the BBC Managing Director, Douglas Muggeridge, said that there

is certainly evidence of growing numbers of young people listening to the BBC programmes.

Mr Muggeridge concluded, "It is encouraging that more listeners than ever before are sufficiently stimulated by the BBC to send us letters, in many cases at considerable personal cost, either in political or financial terms".

The extra letters came from countries spread across the world, but the bulk of the new mail came from Africa.

The BBC World Service has recently made some frequency adjustments to its service to Australia up to September 29.

The major frequencies remain the same with the service 0600-

Go west

Kensor, of Western Australia, has commenced manufacturing communication equipment for the Australian market.

Kensor is an amalgam of Australian and overseas interests, designed to bring the latest overseas technology to Australia and also export Australian-made products worldwide.


Locally developed products includes VHF radio telemetry equipment and MF non directional beacons. They are also representing Sinclair Radio Laboratories of Canada and Antenna Engineering of Singapore.

For more information contact **Kensor, 12 Hehir St, Belmont WA 6104. (09)478-2333.**

0915 hours UTC on 9510, 9640, 11955, and 15070 kHz. From 0900-1130 hours, 11750 and 21550 kHz carries the broadcast and after this time 9740 and 15310 kHz are the main frequencies.

Morning reception in Australia is available from London, and from 2000 hours UTC 9410, 9570 and 15070 kHz are the primary frequencies. During the early afternoons, at 0300 hours UTC, listeners in Australia should find 15380 kHz providing fair reception.

Tell them you read it in ETI



Test gear

Vicom recently announced the release of a new multi-function communications service monitor produced by IFR of the USA.

Fully portable, the FM1200 covers the range 250 KHz to 1 GHz and features an RS232 interface buss and generator/receiver scan, RF memory, tone memory and programmable display intensity.

With a processor-based system like this, it is possible to display analog test responses digitally. The internal non-volatile memories allow the monitoring and automatic testing capabilities to display the vacuum fluorescent display fre-

quency, frequency error to one hertz resolution, modulation both AM and FM, RF power, SINAD, distortion, signal strength duplex offset and a variety of pulse, tone and tone sequence formats.

A special feature of the FM1200 is its ability to simultaneously generate a fixed output level and simultaneously receive a signal. This duplex testing facility allows testing of repeaters and their associated systems both in 'off air' or separate transmit receive lines.

The unit also contains a signal generator and spectrum analyser.

Further details are available from **Vicom Australia, 57 City Road, South Melbourne Vic. (03)62-6931.**

Receiver shopping guide

One of the main questions asked by the newcomer to shortwave listening is what sort of equipment is available and its range and price. Radio Nederland has issued its seventh edition of its 'Receiver Shopping Guide' and in its 24 pages, it gives details of the main receivers which are available world wide. The sixth edition was published in March, 1983 and was an extensive inventory of receivers with details on their coverage, price, weight etc. and the name of the agent in several countries. Since that edition another 18 shortwave receivers have been added to the world market, and these have moved increasingly to channel selec-

tion, push button system, rather than the conventional knobs and read-out dial. Copies of the 'Receiver Shopping Guide' are available free on request from Media network, Radio Nederland, P.O. Box 222, Hilversum, Holland JG 1200.

Radio Nederland has also produced several other brochures to assist the shortwave listener, and one of these, 'The Booklist', which is now in its 6th edition has a comprehensive coverage of publications, such as books, periodicals and annuals which are of value to the radio listening hobbyist. A pamphlet on aerials both for indoor and outdoor use is also available from Radio Nederland.

1984 GFS catalogue

GFS Electronic Imports now has available its 1984 colour catalogue, continuing 24 pages of communications and electronic equipment.

Fully illustrated and containing complete specifications on all their products this catalogue makes a useful reference for those with any interest in the area of communications.

If you would like a copy contact **GFS Electronic Imports, 17 McKeon Road, Mitcham Vic 3132. (03)873-3777.** Please include \$0.75 for postage.

GFS Electronic Imports

1984
CATALOGUE

24 PAGES OF
ELECTRONICS AND
COMMUNICATION
EQUIPMENT



17 McKeon Road Mitcham, Victoria, 3132
P.O. Box 97, Mitcham, Victoria, 3132.

KILOHERTZ COMMENT

ALASKA: KNLS has made some frequency changes for our winter reception period. This schedule is valid up to September 1 and the broadcast from Anchor Point, Alaska, to the Pacific between 0700 and 0930UTC is on 11 940 kHz. From September 1 this changes to 6100 kHz.

Other broadcasts are in Russian 0930-1200 hours, Chinese 1200-1430 hours, both on 11 940 kHz and changing to 6100 kHz on September 2; Russian to Europe 1500-1730 hours on 11 790 kHz to September 1, then 6085 kHz to September 29, and 6095 kHz to November 3. English from 1730-2000 hours continues on these same frequencies.

FRANCE: Radio France International has English transmission from 0415- 0430 hours and 0445-0500 hours on 7135, 9790 and 11 875 kHz, and again at 1600-1700 hours on 15 315 and 17 795 kHz.

The relay from Montigny, French Guyana is now in operation from three, 500 kW transmitters. It broadcasts from 2200-0200 hours at present and can be received on 15 185 and 15 435 kHz. It is expected that the transmission will be extended with an English news programme from 0330-0400 hours.

NEW ZEALAND: The Radio New Zealand Shortwave Service has moved from 17 705 to 17 710 kHz from 2115-0315 hours, then 11 960 kHz is used between 0330 and 1215 hours.

Other transmissions are from 1800-2100 hours on 11 960 and 15 485 kHz; 2115-0515 hours 15 485 kHz; 0530-1215 hours on

9520 kHz. Both 9520 and 15 485 kHz transmissions are beamed to Australia and Papua New Guinea.

SWEDEN: Radio Sweden International, Stockholm, has English broadcasts from 1100-1130 hours to Australia but the proposed frequency of 15 120 kHz has suffered interference and a complaint from Deutsche Welle has requested a new frequency. Following a telex from Stockholm, the writer has suggested 15 115 kHz.

SWITZERLAND: Berne has changed its frequency for English programming at 0430-0500 hours, replacing 11 715 kHz by 12 035 kHz. The other frequency, 9720 kHz, carries the programme for this English broadcast, which features "Shortwave Listeners Merry-go-round" on the second and fourth Sunday of each month.

TURKEY: Ankara is using 11 755 and 17 815 kHz from 0300 to 0350 hours in English with the first frequency beamed to North America and the second to South East Asia.

YUGOSLAVIA: A difficult signal to receive is Radio Yugoslavia, broadcasting from Belgrade, on 6100 kHz. Its giving best reception with English around 1900-1930 hours. The other frequencies carrying the programme are 7240 and 9620 kHz.

This item was contributed by Arthur Cushen, 212 Earn St, Invercargill New Zealand, who would be pleased to supply additional information on medium and shortwave listening. All items quoted are UTC (GMT) 10 hours behind Sydney time. All frequencies are in kilohertz (kHz).

**BELOW
MANUFACTURER'S
COST!!**

**ONLY
\$125
COMPLETE
MASSIVE SAVING
OF \$74**



Mail Order By
BANKCARD
Via Your Phone

**FULL 90 DAY
WARRANTY**

At \$199 the Voyager Car Computer represented absolutely outstanding value for money. No one else had such a low priced, **FULL FUNCTION** car computer. The Voyager is the only low-cost unit that will give you full consumption (the most important feature in a car computer) in both metric litres/100km **AND** good old **MILES PER GALLON!**
At \$199 many, many hundreds have been sold. **NOW** you can grab one **absolutely complete** for only \$125 — a saving of 37% or \$74!
The Voyager comes absolutely complete with all fitting hardware — even down to a roll of insulation tape! Installation generally takes between 4 and 6 hours depending on vehicle.

or by mail order to:
Jaycar
Box 185
Concord 2137

Jaycar Sydney (City) 264 6688/267 1614
Jaycar Concord 745 3077
Jaycar Carlingford 872 4444
Jaycar Hurstville 570 7000
Zap Electronics Parramatta
Hornsby
Rod Irving (03) 347 9257
Melb A'Becket St (03) 489 8131
Northcote (09) 328 1599
Altronics Perth

Spare Flow Sensors: Jaycar will be supporting this product for many years to come. To avoid problems changing cars, why not buy a spare fuel flow sensor? They are about the only things that wear out


Cat. XC2036 **ONLY \$29.50**

AS REVIEWED
OCT '82
EA (p.26-28)
ETI NOV '82 (p.26)

CAT. XC2010

**NEW IMPROVED
MODEL!**

VOYAGER OPERATING FEATURES



PERSONAL COMMUNICATOR

With the **BUILT-IN WORDBEE** in ROM as well as **MICROWORLD BASIC** and **NETWORKING**, the Personal Communicator is a powerful home computer ideal for virtually any home use from wordprocessing, spreadsheet analysis, education and even experimentation with the computer concepts as they evolve during the year.

Supplied with basic manual, network manual and Wordbee manual.

Cat. XC-4100 **\$499.00**

ADVANCED PERSONAL COMPUTER

Now for the first time in Australia, the Microbee Series 2 Advanced Personal Computer with 400K disk drive. Then add bundled world class software such as CP/M, MICROSOFT BASIC, WORDSTAR and a powerful library of support programs and you will have some idea as to why the Microbee Series 2 Advanced Personal Computer is the most powerful and best price/performance computer in its class. What's more any existing Microbee owner can convert his Microbee to the Series 2 APC at any time.

Supplied with Wordstar training manual, Wordstar reference manual, Multiplan manual, disc operating manual, Microworld BASIC manual.

Cat. XC-4200 **APC WITH SINGLE DISC DRIVE \$1595.00**

128K BUSINESS MACHINE

Special software makes full use of the additional RAM to generate a friendly 'shell', Disc Buffer, RAM Drive and other state of the art features. Bundled software will include Wordstar 3.3, Multiplan, Microsoft BASIC, Microworld BASIC, 128K Utilities and now Mailmerge (Wordstar utility) and Wordplus (spelling checker and dictionary). This machine is an ideal small business computer.

Cat. XC-4250 **128K WITH DUAL DISC DRIVES \$1995.00**

Microbee



**CIVILIZATION
DISCOVERS XIDEX.**



XIDEX FLOPPY DISC

★ GIVEAWAY ★

**BUY ONE, GET ONE FREE
BUY 20, GET 20 FREE**

This unbelievable "two for the price of one" special is on for JULY, AUGUST and SEPTEMBER ONLY.

HERE'S WHAT TO DO -

Buy a copy of Australian Personal Computer, Australian Arts & Education, Today Computing, Your Computer or Electronics Today. Cut out the coupon from the Xidex advertisement and bring it into Jaycar. You may purchase up to 2 boxes (20 discs) and receive 2 boxes (20 discs) free on the one coupon. The coupon must be filled out correctly and presented at the time of purchase. Mail order customers may send the coupon in with their order. Copies of the form are ineligible.

Single Sided Double Density 5 1/4"

Cat. XC-4775 1-9 **\$5.50 ea Box 10 \$54.50**

Double Sided Double Density 5 1/4"

Cat. XC-4770 1-9 **\$5.95 ea Box 10 \$59.50**

**Jaycar
ELECTRONICS**

Incorporating
ELECTRONIC AGENCIES

NUMBER 1 FOR KITS

SHOWROOMS

SYDNEY

117 YORK STREET

Tel: (02) 264 6688 & (02) 267 1614

Telex: 72293

CARLINGFORD

Cnr. CARLINGFORD & PENNANT
HILLS ROAD

Tel: (02) 872 4444

CONCORD

115-117 PARRAMATTA ROAD

Tel: (02) 745 3077

HURSTVILLE

121 FOREST ROAD

Tel: (02) 570 7000

**MAIL ORDERS
& CORRESPONDENCE**

P.O. BOX 185
CONCORD, 2137

Tel: (02) 745 3077

Cat. No.	Description	WAS	SALE	SAVE	XS-8012	Account Manager	\$15.95	\$9.95	\$6.00
XR-6580	Mydas (1 ROM) Editor Assembler	\$45.95	\$33.00	\$12.95	XS-8200	Marlin (Adventure)	\$25.00	\$16.50	\$8.50
XR-6582	Mydas (2 ROM) Editor Assembler	\$45.95	\$33.00	\$12.95	XS-8400	Data Bee	\$19.95	\$14.95	\$5.00
XR-6585	Forth (1 ROM) Mytek	\$45.95	\$33.00	\$12.95	XS-8610	Printers Mate	\$17.50	\$12.50	\$5.00
XR-6587	Forth (2 ROM) Mytek	\$45.95	\$33.00	\$12.95	XS-8613	Bee Copy	\$14.95	\$9.95	\$5.00
XS-7000	Asteroids Plus - Mytek	\$22.00	\$17.50	\$7.00					
XS-7002	Touch Type Tutor - Mytek	\$22.00	\$15.50	\$6.50					
XS-7004	Machine Code Tutor - Mytek	\$27.50	\$19.50	\$8.00	XD-9504	Defender - Mytek	\$29.50	\$21.50	\$8.00
XS-7005	Basic Tutorial - Mytek	\$22.00	\$15.50	\$6.50	XD-9505	Chopper - Mytek	\$27.00	\$20.00	\$7.00
XS-7008	Ghost Muncher/Kilopede	\$21.00	\$15.50	\$5.50	XD-9506	King Kong - Mytek	\$27.00	\$20.00	\$7.00
XS-7010	Frogger - Mytek	\$18.50	\$14.00	\$4.50	XD-9507	Emu Jaust - Mytek	\$27.00	\$20.00	\$7.00
XS-7011	Defender - Mytek	\$24.50	\$17.50	\$7.00	XD-9508	Starstriker - Mytek	\$33.00	\$22.50	\$10.50
XS-7013	King Kong - Mytek	\$22.00	\$15.50	\$6.50	XD-9509	Machine Code Tutor	\$33.00	\$22.50	\$10.50
XS-7014	Chopper - Mytek	\$22.00	\$15.50	\$6.50	XD-9510	Basic Tutor	\$27.50	\$20.00	\$7.50
XS-7015	Emu Jaust - Mytek	\$18.50	\$14.00	\$4.50	XD-9511	Ghost Muncher/Kilopede	\$26.00	\$20.00	\$6.00
XS-7020	Chess - Mytek	\$22.00	\$15.50	\$6.50	XD-9800	Accounts Manager	\$21.95	\$15.00	\$6.95
XS-7022	Galaxian - Mytek	\$21.00	\$15.50	\$5.50	XD-9801	Assets	\$21.95	\$15.00	\$6.95
XS-7500	Space Invaders	\$14.95	\$11.50	\$3.45	XD-9802	Budget	\$21.95	\$15.00	\$6.95
XS-7507	Robot Man	\$14.95	\$11.50	\$3.45	XD-9803	DX Log	\$21.95	\$15.00	\$6.95
XS-7539	Eye of Min	\$14.95	\$11.50	\$3.45	XD-9804	File Index System	\$21.95	\$15.00	\$6.95
XS-8001	Financial Manager	\$15.95	\$9.95	\$6.00	XD-9805	Financial Manager	\$21.95	\$15.00	\$6.95
XS-8002	Card Index System	\$9.95	\$7.50	\$2.45	XD-9806	Log	\$21.95	\$15.00	\$6.95
XS-8003	File Index System	\$15.95	\$9.95	\$6.00	XD-9807	Stock Supervisor	\$21.95	\$15.00	\$6.95
XS-8004	Basic Decoder	\$15.95	\$9.95	\$6.00	XD-9809	CPM Utilities	\$21.95	\$15.00	\$6.95
XS-8005	Budget Spreadsheet	\$15.95	\$9.95	\$6.00					
XS-8006	Stock Supervisor	\$15.95	\$9.95	\$6.00					
XS-8007	Log	\$15.95	\$9.95	\$6.00					
XS-8008	Assets - Household Register	\$15.95	\$9.95	\$6.00					
XS-8011	Data Manager	\$15.95	\$9.95	\$6.00					

MICROBEE SOFTWARE SALE

We are overstocked on quality software. Now is the time to grab the program you've been thinking about. There's even some disc based software. This sale is limited to August ONLY and some of our stores may not have all the items listed - get in early and SAVE.



Full descriptions of software are available in our catalogue, or by phoning one of our stores.
KEEP WATCHING OUR ADS FOR NEW GENERATION MICROBEE SOFTWARE

JAYCAR - WELCOMES YOU TO A WONDERLAND OF ELECTRONICS

HOBBY ELECTRONICS

KITS - This range of simple kits are ideal for the beginner in electronics. All kits come complete with instructions and are easy to build. No need to purchase an expensive book just to build one project.
For August ONLY when you purchase a hobby electronics kit ask for your FREE

"Kit Constructors Reference Manual"

POST & PACKING CHARGES

\$5 - \$9.99	\$1.50
\$10 - \$24.99	\$3.20
\$25 - \$49.99	\$4.50
\$50 - \$99.99	\$6.50
\$100 - \$198	\$8.00
Over \$199	\$10.00

COMET ROAD FREIGHT ANYWHERE IN AUSTRALIA ONLY \$12.00

SHOP HOURS

CARLINGFORD, CONCORD & HURSTVILLE

Mon - Fri: 9 am - 5:30 pm
Sat: 9 am - 12 pm

Thurs Night: 8:30 pm (Not Concord)

SHOP HOURS SYDNEY

Mon - Fri: 8:30 am - 5:30 pm
Sat: 8:30 am - 12 pm
Thurs Night: 8:30 pm

MAIL ORDER BY



GUITAR PHASER This guitar phaser is housed in a die cast box. It incorporates a rate control thereby being able to vary the phasing speed.

Cat. KS-8102 \$26.50

TRANSISTOR TESTER The transistor tester allows you to check transistors and at the same time will tell you the approximate gain of the transistor under test.

Cat. KS-8103 \$9.50

AM TUNER This is a very simple design using only a small handful of components. Circuit is based on the popular ZN414 radio IC. A crystal earpiece is needed in order to hear the sound.

Cat. KS-8104 \$7.50

BENCH AMPLIFIER If you ever need to test whether a pre-amp is functioning correctly this is the ideal project to test it with. It can amplify signals as low as a few millivolts to an audible level.

Cat. KS-8105 \$9.75

RADIO MICROPHONE This project allows you to transmit over the FM waves. You need to have an FM radio in order to hear what the radio microphone is picking up.

Cat. KS-8106 \$6.50

ELECTRONIC DIE Fed up with rolling a die? Then this project allows you to do it electronically. Push a switch and the LEDs will light up, release the switch and a random number will remain displayed.

Cat. KS-8107 \$5.95

POWER SUPPLY Gives you a choice of 6 DC voltages from 1.5V to 12V. A 12 volt DC plug pack is necessary to run the unit. Recommended plug pack is MP-3012.

Cat. KS-8108 \$11.95

UNMISTAKABELL This project gives the most unusual doorbell sound you've ever heard. Hence the name 'Unmistakabel'.

Cat. KS-8110 \$6.95

OHMMETER This Ohm meter has a linear scale for easy reading. Will measure resistor values up to 1M ohm. Can also be used to check continuity and diodes.

Cat. KS-8111 \$19.95

MICROMIXER This mixer has two inputs, one for a microphone and the other for a musical instrument. Thereby allowing you to mix speech and music together. Each input has its own level control.

Cat. KS-8112 \$12.00

DIGITAL COUNTER & DISPLAY This is a three digit counter therefore allowing you to count in hundreds. A decimal point is also available.

Cat. KS-8114 \$13.95

REACTION TESTER This project is designed to be used with the digital counter KS-8114 project. It allows you to test peoples reaction times, for example how long does it take for a person to react to a needle being pushed into the skin.

Cat. KS-8115 \$6.95

OP AMP TESTER Just like the name says this project allows you to test all those op amps you have sitting around on your work bench - just to see if they are working still.

Cat. KS-8116 \$3.95

HOUSE & CAR ALARM This alarm can be adapted to protect either a car or house. It has 4 normally closed input or trigger points. It has a relay on board which once triggered pulses at approximately one second intervals.

Cat. KS-8117 \$16.95

SCRATCH & HISS FILTER This project will reduce the sound of scratches on your record and hiss on your tape. There are two filter settings.

Cat. KS-8121 \$9.50

ALIEN INVADERS This game is very simple to learn. There are two rows of LEDs. One records your score the other shows the advancing aliens. What you have to do is press a switch at the right time to zap the alien. The more you hit the faster they advance.

Cat. KS-8123 \$13.95

NiCad CHARGER this NiCad battery charger has five current ranges and can be used with several different battery sizes. You will require a 9V or 12V DC plug pack to run the unit, our Cat. No. MP-3012.

Cat. KS-8126 \$9.95

SIREN This simple project produces a siren sound. It runs off a 9V battery. It comes supplied with a small 8 ohm speaker.


Cat. KS-8127 \$3.95

FOG HORN This project simulates the sound of a ship fog horn. It is assembled on a small piece of matrix board. Small 8 ohm speaker is included.

Cat. KS-8128 \$6.70

SIMPLE TIMER This project can be used for reminder purposes. The circuit is set for 3 minutes but can easily be modified for a shorter or longer period.

Cat. KS-8129 \$6.95



How the

BBC and CIA

Keep Tabs on the World

Arthur Cushen, MBE

212 Earn St, Invercargill, New Zealand

If you want to *really* know what's going on in the world — listen to what it's saying! This is how the BBC's superlative news service is kept abreast of world affairs and how America's Central Intelligence Agency keeps Washington and the President informed.

LISTENING to news bulletins in some 40 languages is a major role of the BBC monitoring service. By eavesdropping on local broadcasting, the main news stories of the day are often first revealed.

Particularly today, with political unrest, rapid changes of government and the unstable situation in many countries, radio is the first means of learning of events as they happen.

Local broadcasting, via radio, is not confined to the population within a country. There is little possibility of using radio as a means of releasing information to the local people without it being heard by keen news monitors somewhere in the world.

I have had many occasions when I've been able to supply Radio New Zealand, or the private commercial networks, actual recordings of announcements, giving the

first news of a sensational government move or the death of a world figure.

It is a matter of knowing when and where to listen that gives the keen shortwave listener an advantage and if one is news conscious, then the chances of being at the right spot on the radio dial when a news story breaks is a distinct possibility.

BBC monitoring service

The continued expansion of world broadcasting has a more immediate impact on the monitoring service, than on any other part of the BBC as it represents a direct increase in the task of listening and reporting. The job of the BBC monitoring service is to provide speedy and accurate reports of significant news and comment from foreign broadcasting stations in all parts of the world.

It is a national service, supplying information not only to the BBC itself, but also to government departments, the press, and other bodies concerned with international affairs. It works in close collaboration with its United States counterpart under an exchange agreement, which means virtually world-wide coverage. In return for its own extensive product, the monitoring service is able to receive and supply to its customers material from stations principally in the Far East and Latin America which are received by United States monitors.

The service is based at Caversham, near Reading, and has two main parts — Reception, which is responsible for listening, and Transcription and Output which selects and edits material for sending out by teleprinter and printed documents to numerous recipients. There is also a small unit in Nairobi with the primary task of monitoring broadcasts directed to or emanating from East and Central Africa.

Technical facilities are provided by the BBC Engineering Division, and include a separate receiving station at Crowsley Park in Oxfordshire.

In the reception unit, voice broadcasts are listened to live, to ensure the speediest reporting of important news, and recorded so that the monitor playing back the recording can secure the greatest accuracy in translation. A high degree of linguistic and translating ability is naturally required from the individual monitor. Subject to general directives, the monitor is expected to exercise judgements in the primary selection of material.

Receivers

The BBC monitoring service is world-renowned for its use of news bulletins from foreign stations.

These are incorporated in BBC news or the World Information Bulletin released each week and based on listening by the monitoring service.

The equipment used is of the highest quality and, having visited the monitoring ▶



A bird in Bush House is worth . . . Much of the news gathered by the BBC Monitoring Service is fed to the newsroom in Bush House. This photo shows the newsroom where more than 250 news programmes are prepared every day for broadcast on the BBC's External Services. They are compiled in a newsroom which, with an editorial staff of well over a hundred, is the biggest in the BBC and one of the largest in the world.



Listen to the world! A section of the listening room at the BBC Monitoring Service at Caversham Park.

WIRELESS INSTITUTE OF AUSTRALIA

FOUNDED 1910

The W.I.A. represents the
Radio Amateur at Local,
National and International
level and offers the following
services:

- ★ Monthly "AMATEUR RADIO" Magazine, included in membership fee.
- ★ Most REPEATERS have their licence, power and site cost paid by the institute.
- ★ World wide QSL-service.
- ★ Assistance to members in legal problems arising out of the pursuit of their hobby.
- ★ A Weekly Sunday Broadcast to Amateurs and Short Wave Listeners.
- ★ Assistance in dealing with Interference Problems (TVI-RFI etc.)
- ★ Novice and full call courses.
- ★ Trial Novice and AOCF theory exam papers.
- ★ Advice on Radio Mast approvals
- ★ The ONLY representation of the RADIO AMATEUR in legislative matters.



Join the 8,600 Amateur
members in the W.I.A. by
forwarding this coupon to:

W.I.A. P.O. BOX 300,
CAULFIELD SOUTH, VIC. 3162

Please forward a membership
application form and further details
to:

Mr, Mrs, Miss, Ms

Address

Callsign

Postcode



COMMUNICATIONS TODAY

service, I can vouch for the high standard of equipment and the aerial systems.

According to Chris Greenway, the manager of the monitoring station, the best receiver is the Racal 1772. The monitoring service's standard receiver is the Racal 1792 which costs about A\$10 000 on the open market. It is fully synthesised, has 99 memories and is very stable in operation.

The BBC also has examples of the 30-year-old GEC BRT 400 and the Racal RA17 from the late fifties. Chris Greenway rated the Racal a very nice piece of DX gear when he was interviewed for the Austrian Radio Panorama programme recently.

There is a choice of five aerial types for connection to each monitor's receiver — an 80 m beveridge, 77 sloping V, 60 rhombic, 60 beveridge and a 57 rhombic. Beveridge aerials are positioned at 20 degree intervals around the compass. DXing of unknown transmissions is achieved quickly via the post office which takes a bearing and telexes its opposite number in an appropriate country, asking it to do likewise; the bearings are phoned back to the BBC, so that the location can be identified.

CIA monitoring service

In the United States a similar organisation to the BBC monitoring service exists, though its listening information is not available to the general public. In a recent *New York Times* report, comment was made that the first indications that something important is stirring in foreign capitals are often the whispers, rumours and fragmentary dispatches of friend and foe alike reported by radio and television broadcasts around the world.

Twenty four hours a day, broadcasts are monitored by a little known arm of the Central Intelligence Agency, the Foreign Broadcast Information Service (FBIS). When rumours foreshadowing a major announcement in Moscow began to circulate, analysis at the intelligence agency tuned into the FBIS. What they heard was confusion.

The FBIS sifts items for news at its central office in Rosslyn, Virginia. Agents in the field glean news daily from foreign radio and television broadcasts and from newspapers. The material is compiled for eight daily reports on the world's regions which are published each weekday. Foreign broadcasts sometimes reach Washington before word can be relayed by the CIA's more active gatherers of information.

In the case of the recent death of Soviet leader, Yuri Andropov, agency officials said in response to questions from the press that they had heard nothing of unusual activity in Moscow. Those monitors who follow Radio Moscow closely found that there was a sudden switch of programme material and the playing of classical music in

place of their regular programming as they did when Leonid Breshnev, the previous Soviet leader, died in 1982.

This example is typical of a major news story monitored by the various listening services. Monitoring enables the radio services to often be aware hours before the official announcement of major world events.

Listening equipment

Readers may be interested in the equipment used by the writer in his work as a technical representative for many international stations.

The monitoring of BBC signals is confined to a domestic type receiver. The Sony ICF2001, which is widely used throughout the world, is the basis on which BBC reception is graded in New Zealand. BBC engineers like to receive reports in a domestic situation so that the reception is typical of that experienced by any listener.

Since first commencing to monitor the BBC in 1942 an Ekco 7-tube receiver was used, which was later replaced by an Eddystone 840A. Since 1980 three Sony ICF 2001 receivers have been used for all monitoring work. This covers not only the BBC, but Radio Canada International, Voice of America and Radio Sweden reported on a weekly basis. Vatican Radio, Radio Netherland and the Italian Radio are reported monthly.

The aerial consists of a conventional inverted-L, 10 metres high and 30 metres long. In all, six aerials are fed into a push-button system from a 20 metre lattice tower in my property. These include a trapped, multi-band dipole and several long wire aerials running across neighbours' properties to a mast further down the street.

For DX listening I have the choice of a Racal RA17, Hallicrafters SX122, McKay Dymek DR22, Allied SX190 and several other receivers. As I am blind, all incoming signals are recorded and from this information the reception report to the distant radio station is prepared. The final typed copy is produced by one of the office staff.

As well as aerials, an earth is essential. Mine is in the form of a large concrete pipe set in the ground, filled with rocks, surrounding a copper pipe. It is kept in a damp condition, providing a good earth to all receivers.

The recording equipment includes two Telefunken reel-to-reel recorders, as well as several tape decks including JVC and AIWA models. A phone line is fed into the recorders so that news bulletins and information of value to local and national radio services can be fed to stations in Invercargill or as far afield as Auckland.

The monitoring of signals both in war time and peace has given me a unique place in radio history providing many news stories hours ahead of conventional information received by radio services or the press. ●

EVEN A CASUAL shortwave listener soon comes to realise that all is not well with sound broadcasting in the high frequency bands between 3-30 MHz. Tuning across the dial from 60 to 13 metres reveals many frequency channels that are occupied by more than one transmitter. The result is frequently an unintelligible cacophony of sound which destroys the utility of the channels for all. Although most of the transmissions attempt to convey meaning through modulation in one of the world's many languages, there is the occasional emission which deliberately aims to destroy the intelligibility of signals upon which it is imposed.

There are around 150 nations in the world today. Many of these have shortwave transmitting facilities. The high frequency band, through ionospheric reflections, offers an economical and accessible way of conveying to the rest of the world a country's unique philosophy on life. Whether it be an espousal of politics or religion, an attempt to teach a language or simple medical facts, ethnic entertainment, or merely a desire to present a view of world news compatible with one's ideology, HF broadcasting, given the right conditions, is an ideal medium for use by even the smallest nations. Unfortunately, conditions are not always ideal.

The ionosphere, upon which all long distance terrestrial transmissions depend, is a function of many variables. Its reflective properties depend on geographical position, time of day, season, transmission frequency, and the periodic and capricious nature of its sustainer, the Sun. To cope with all these variables, many national administrations operate multiple services, with several transmitters spread not only over adjacent bands, but also within the one band. Only in this manner can they be relatively assured of reasonable coverage of their desired target areas.

Unfortunately, there are simply just not enough HF broadcasting channels to accommodate this practice without significant mutual interference. This is particularly true during the years of low solar output; a time when the maximum useable frequencies (MUFs) on all transmissions paths are reduced.

To overcome some of these problems, what may be regarded as a rather radical area has recently been reconsidered. In a draft report to the CCIR (International Radio Consultative Committee) the USA last year proposed the use of satellites as platforms for shortwave sound broadcasting transmitters.

The idea is not entirely new, as feasibility studies of this concept were made in the early 1970s. However, at that stage it was decided that power requirements alone were too great to warrant further consideration. (It is generally regarded that a signal of 500 to 1000 μ V at the input of a small portable receiver is required to give a good quality broadcast signal in a noisy urban environment. Such a signal level can only be achieved by a geosynchronous satellite transmitter with a power output of around one quarter of a megawatt!)

If the power requirements can be met there are some definite advantages (and also some disadvantages) to be had from a

Last year the USA proposed the use of satellites as platforms for shortwave sound broadcasting transmitters. These could relieve the congestion and interference now experienced by ground-based international shortwave broadcasters. This article outlines the requirements and possible performance of such a system.

SATELLITES AND SHORTWAVE



John Kennewell

Learmonth Solar Observatory, Ionospheric Prediction Service

space-based shortwave transmitter. For it is the very frequencies that are useless for ground originated, ionospherically reflected signals that can propagate from space, through the ionosphere, to the ground. Consideration of exactly what these frequencies involve both an interesting physical and geometrical problem, and also helps to quantify the discussion into actual system parameters.

Upon reflection

When a swept frequency signal is directed from the ground vertically toward the ionosphere there is found to be a critical frequency, f_c , which separates the behaviour of the signal. Frequencies below f_c are reflected by the layer in question, whereas frequencies above f_c pass essentially undeviated through the layer. If the signal is not vertically incident upon the ionospheric layer, the maximum frequency, f , that is then reflected is given by




$$f = \frac{f_c}{\cos i}$$

where i is the angle that the signal makes with the normal to the layer (Figure 1).

In actuality, the reflection of an oblique radio wave by the ionosphere is a gradual process; see Figure 2(a). As the wave penetrates into the ionised layer, it encounters a greater density of electrons which cause the wave to be progressively bent or refracted.

If the wave frequency is not too high this refraction leads to the equivalent of reflection. If, on the other hand, the frequency is too high to allow reflection, it will travel past the level of maximum ionization and be refracted back onto a path parallel to the original incident wave. This is shown for an idealised homogeneous ionospheric layer in Figure 2(b).

Note that the transmitted ray is parallel to, but slightly displaced from, the projection of the incident ray. This displacement increases with the thickness of the refracting layer and also as the wave frequency



approaches the oblique critical frequency. It is assumed to be negligible (and in practice is negligible for high orbit satellites) in the following discussion.

The sky's the limit

In applying the above points to a signal propagating from a satellite to a receiver on the ground we simply invoke the principle of reciprocity. That is, if the transmitted frequency is too low, it will be reflected by the ionosphere back into space. The problem reduces to finding the minimum frequency, for any given path, above which the ionosphere will appear transparent to the satellite signal. All discussions will consider only satellites located well above the ionosphere.

From the time of the first Sputnik, the Soviets have been using frequencies near 20 MHz, and more lately 15 MHz, for

telemetry purposes. These satellites, however, usually orbit *within* the ionosphere and their signals are subject to ducting which can result in reception at their antipodal points. This phenomenon is quite complex to analyse, is not very predictable, and thus will not be considered here.

The geometry relating to the satellite-to-ground propagation path is shown in Figure 3. The transmitted signal strikes the ionospheric layer at point I with an incidence angle of i . It is this angle together with the critical layer frequency, f_c , at this point that will determine whether or not the satellite signal, f , will pass through to the ground station. Unfortunately, the angle i is not something that is readily available for computation. What is required is an expression relating the minimum transmittable frequency, f , to the distance 'a' that the ground

station, E, lies (measured along the ground) from the satellite sub-point, P.

With the aid of some trigonometry this can be done to produce a satellite HF propagation equation. The equation, including its derivation (for those interested) is given in the accompanying box. To be useful, however, the implications of this equation need to be presented visually.

Before looking at some tabular results from the satellite HF propagation equation, it is useful to consider the portion of the earth's surface that can be seen by satellites at different heights. This is shown in Figure 4. The limit of satellite optical visibility is given both as an angle measure along a great circle path, and a ground distance along the same path. The actual distance appropriate to radio frequencies will be somewhat larger due to refraction effects by the Earth's surface. This can be generally simulated by using a value for the Earth's radius, R , that is 4/3 the actual value of 6370 km.

Some results

Using the values of Figure 4, the satellite equation may be used to compute minimum propagable frequencies within this area. This is done in Table 1 opposite.

All computations were done assuming that the principal ionospheric refracting layer was 300 km above the surface. This layer is the F2 layer in the daytime, and the F layer at night. It is interesting to note that although the lower altitude satellites have a more limited ground coverage, the lowest frequency that can be employed at the edges of the area serviced is 3.4 times the ionospheric critical frequency at the point of penetration. This number is independent of satellite height. It is obvious, of course, that a wider range of frequencies may be used by the higher satellites to service stations within the coverage area.

An alternative presentation of data is shown in Figure 5. This shows the minimum useable frequencies for a satellite in geosynchronous orbit, assuming a uniform ionospheric layer at 300 km with a critical frequency of 10 MHz across the hemisphere. This is, of course, not realistic but it serves as a first basis for discussion. In actuality the critical frequency is determined in a good part by the angle that the Sun's rays make with the point in question.

The critical frequency is thus highest for the point directly below the Sun and falls off on either side longitude-wise, and also with latitude. Ten MHz is a good approximate value for the maximum critical frequencies experienced at times of moderate sunspot number (e.g: $R=50$), rising to around 15 MHz or higher when the sunspot number is high (e.g: $R=150$). These values will occur directly at the sub-solar point.

If, at a particular time, this was to be coincident with the sub-satellite point, the contours of Figure 5 would be correct for the central part of the graph, but would be more open at greater angular distances. This change, reflecting the diminished critical frequencies away from the sub-solar point, would also mean that the last contour (around the limit of the visibility circle) would also be at a lower frequency (e.g: 20 MHz).

P is the satellite sub-point, the point on the Earth's surface immediately below the satellite.
S is the satellite transmitting the signal (at height h)
E is the ground receiver
I is the point at which the signal passes through the principal ionospheric refracting layer (at height d)
R is the Earth's radius
The minimum frequency that can be propagated from S to E is given by $f = f_c \sin i$ where f_c is the ionospheric critical frequency at point I. Any frequency lower than this will be reflected back into space.





Figure 3. Geometry for signal propagation from a satellite to the ground.

Earth's radius $R = 6370$ km
 $s = R\theta$

$$\cos \theta_{\max} = \frac{R}{R+h}$$

$$\theta_{\max} = \cos^{-1} \left(\frac{R}{R+h} \right)$$



h(km)	θ_{\max}	s(km)
1000	30°	3200
2000	40°	4100
5000	56°	5300
10 000	67°	5900
18 000	75°	6150
36 000	81°	6300

Figure 4. The maximum portion of the earth's surface that can be seen by a satellite of altitude 'h' km.

SATELLITE HF PROPAGATION EQUATION

The geometry of the satellite propagation path is shown in Figure 3. The problem is to find the minimum frequency that will propagate from the satellite at S to a ground receiver at E, a distance a from the sub-satellite point P. The ionospheric critical frequency at I is f_c .

In triangle CSI the rule of sines yields $\frac{R+h}{\sin i} = \frac{R+d}{\sin \theta}$

Similarly, in triangle CSE we have $\frac{R}{\sin \theta} = \frac{r}{\sin \Theta}$

The above two equations combine to eliminate θ giving $r = \frac{R(R+h) \sin \Theta}{(R+d) \sin i}$

The cosine rule in CSE also gives $r^2 = (R+h)^2 + R^2 - 2R(R+h) \cos \Theta$

Equating the two expressions for r, the satellite to receiver distance, gives

$$\frac{\sin^2 \Theta}{\sin^2 i} = \left(\frac{R+d}{R} \right)^2 + \left(\frac{R+d}{R+h} \right)^2 - \frac{2(R+d)^2}{R(R+h)} \cos \Theta$$

The incidence angle i is related to the frequencies f and f_c by the relation $\sin^2 i = 1 - \cos^2 i = 1 - f_c^2/f^2$

Thus the above equation can be rewritten:

$$\frac{f_c}{f} = \sqrt{1 - \frac{\sin^2 \Theta}{\left(\frac{R+d}{R} \right)^2 \left\{ 1 + \left(\frac{R}{R+h} \right)^2 - \frac{2R}{R+h} \cos \Theta \right\}}}$$

Now $\Theta = a/R$ and if we let $\alpha = \frac{R}{R+h}$ and $\beta = \frac{R+d}{R}$ we have the final form of the satellite HF propagation equation:

$$\frac{f_c}{f} = \sqrt{1 - \frac{\sin^2(a/R)}{\beta^2(1+\alpha^2) - 2\alpha\beta \cos(a/R)}}$$

$\theta^\circ \backslash h$	1000 km	2000 km	5000 km	10 000 km	18 000 km	36 000 km
0	1.0	1.0	1.0	1.0	1.0	1.0
10	1.6	1.2	1.1	1.0	1.0	1.0
20	2.8	1.9	1.3	1.2	1.1	1.1
30	3.4	2.8	1.7	1.4	1.3	1.2
40		3.4	2.4	1.8	1.5	1.4
50			3.2	2.4	1.9	1.7
56			3.4	2.8	2.3	1.9
60				3.1	2.6	2.2
67				3.4	3.1	2.6
70					3.3	2.8
75					3.4	3.2
80						3.4
81						3.4

TABLE 1. f/f_c values for various satellite heights h (km) and various ground ranges θ° . (θ is the angular distance from the receiver to the sub-satellite point). The ionospheric layer is assumed to be at 300 km.

If the sub-solar point was to the left of the diagram, the central left contours would be unchanged but the ones to the right would be spread further apart. An egg-shaped pattern would result with the 'fat' end of the egg on the right or eastern side of the hemisphere.

Factors affecting

Apart from shielding of the satellite signal by the F-layer there are three other factors to be considered. The first one of these is

the phenomenon of sporadic-E. At certain times of the day during the summer months, patchy intense regions of ionization form at around the 100 km level. This sporadic-E can occasionally have such a high critical frequency that, in effect, blankets the F-layer from ground signals (Figure 6).

A satellite signal that passed through the F-layer might very infrequently be blocked by such ionization. Because of the irregularity of this phenomenon, it has been estimated that, in the worst case, a 26 MHz signal transmitted from geosynchronous





Figure 6. An ionogram showing 'blanketing' type sporadic-E. The higher F region echo at 300 km is obscured by the lower sporadic-E layer at about 5 MHz.

Operating frequency	26 MHz
Modulation type	AM (A3)
Transmitter power	16 kW
Antenna gain	40 dB
Antenna size (diameter)	500 metres
Antenna beamwidth	2°
Signal received by a receiver with a simple dipole or whip antenna	500-1000 μV
Received power	-78 dBW
Receiver noise environment	-122 dBW
Signal-to-noise ratio	44 dB

Figure 7. USA proposal specifications for a geosynchronous sound HF broadcasting system.

orbit should be shielded for no more than 5% of the time. This would only apply at certain times of the year in selected geographical locations.

The second factor to be considered is shortwave fade due to solar flares. This normally occurs to a signal propagating from a ground-based transmitter via the ionosphere. When a large solar flare occurs, the increased X-ray emission from the sun causes intense ionization of the D-region (50-80 km). This can then absorb any HF signal attempting passage through it. Exactly the same phenomenon will occur to a satellite generated HF signal, although use of the higher frequencies i.e. 26 MHz will reduce the extent and frequency of the problem.

The final factor is concerned with polarisation. Any plane-polarised signal passing through an ionised layer will have its plane of polarisation rotated. This rotation can amount to several hundred revolutions for the signals we are discussing, and changes continuously. If the antennas used by both satellite transmitter and ground receivers are linearly polarised significant fading will occur. The simple solution is to employ a circularly polarised transmitting antenna.

Proposed system

Figure 7 gives details of the satellite HF broadcasting system which has been proposed by the USA. It is significant to note that it still requires 16 kW of transmitting power. The required antenna gain also limits (because of its directionality) the area that can be serviced. The massive size of the antenna, one-half a kilometre in diameter, would appear to be not a feasible proposition to construct. However, new lightweight space construction techniques, developed primarily in connection with potential space solar power stations, have now made it possible to consider such large structures.

Within the realm?

The advantage of HF satellite broadcasting is that a relatively large area may be serviced by a high quality signal, relatively free from fading. Interference from ground based (ionospherically propagated) signals would be nil by nature of the mutually exclusive propagation modes of the different types of signal (although a strategically placed satellite, using a similar orbit, could certainly cause problems).

Although the concept could only be employed by a very limited number of present world administrations, these are the same nations currently emit the greatest number of HF transmissions. Translation of these transmissions to higher, and currently little used, HF broadcast bands would do much to alleviate current shortwave congestion.

Studies conducted show that the 26 MHz band should be useable for satellite broadcasting at most times. When solar output is low, the useable bands might extend through 21 and 17 MHz to as low as 15 MHz. One may well ask why the 88-108 MHz FM broadcast band has not been suggested for a similar type of satellite broadcast service. Although there are some associated technical problems, I believe the answer lies more in the political arena. ●

BANKCARD HOLDERS — PHONE ALTRONICS TOLL FREE 008-999-007 FOR NEXT DAY JETSERVICE DELIVERY

BANKCARD HOLDERS — PHONE ALTRONICS TOLL FREE 008-999-007 FOR NEXT DAY JETSERVICE DELIVERY

\$100,000 STOCKTAKE SALE

We are absolutely up to the rafters with direct import electronic products, and with more and more shipments due this month we must clear excess stock levels right now. So here is your chance to save a fortune - but please note 1st come, 1st served - these prices will definitely not be offered again. Phone your order Toll Free today 008 999 007 (up to 6pm) and remember with Altronics Famous Jetservice delivery we deliver next day to capital cities and suburbs (please allow 24 - 48 hours extra for country areas).

MICRON 30 WATT

This brilliant little 30 watt iron is just the 'bees knees' for the electronics hobbyist, electrician or home handyman. We searched the world for a low cost yet quality iron which met the criteria of * light-weight * screw in interchangeable tips * tip temperature maintains within the limits suitable for electronic work and also small household jobs * and of course fully S.E.C. tested and approved.



1000's Sold
This Month Only
\$9.50 T 2430

6A/400V DIODE BRIDGE

PRICE SLASHED

Z 0134. **\$1.75**


10 SEC. RED BAR GRAPH MODULE

SAVE 35% Z 0180 **\$2.50**
NOW 1.60



HOLE PUNCH SET Fantastic Value

A must for every enthusiast or serviceman. Cuts holes in metal up to 1.6 mm (16 gauge). Set of 5 punches and tapered reamer.




T2360. **\$12.50**
NOW **\$16.00**

DE-SOLDER BRAID



T1230. **\$1**

"MICROBEE KEYBOARD"



Microbee is a registered trademark of Applied Technology Pty. Ltd.

Now
ONLY \$19.50

D1510

\$29.95

Full 60 Key Qwerty Computer Keyboard exactly the same type that has been used with the famous Microbee Computer SPST Keys Complete with mounting plate. (Fully Assembled).

DIRECT IMPORT PRICE ON QUALITY JOYSTICKS

SELF CENTERING TYPE * HEAVY DUTY SUCTION CUPS - STAYS IN PLACE * SILVER PLATED SWITCH CONTACTS PISTOL GRIP * VERY RESPONSIVE

TO SUIT COMMODORE VIC-20, ATARI, etc.

FOR MICROBEE

D1410. **\$12.50**

D1420. **\$19.50**

SAVE 1/3



TRANSFORMERS

MAINS MINI POWER

240V 612.5V CT at 150 MA
SEC Certified to ASC 126

Now **\$2.95**

M 2851 **\$3.95**

MAINS LOW POWER MULTITAPPED

Primary 240V AC
Secondary volts 6.3, 7.5, 8.5, 9.5, 12.6, 15 V
Max. secondary current 1 amp. SEC Certified to ASC 126.

M 2155

Now
\$4.95



MAINS MEDIUM POWER

240V Primary
6, 9, 12, 15V Secondary at 2 amps

M 2156 **\$7.95**

Now **6.50**



MAINS MEDIUM POWER

Primary: 240 V AC
Secondary: volts 15, 17.5, 20, 24, 27.5, 30 V
Secondary current 1 amp
SEC Cert. to ASC 126.

M 6672
\$7.50



MICROPHONE TRANSFORMER MU-METAL SHIELDED CAN

Primary: 200 OHM
Secondary: 50 K OHM

A high quality item eminently suited to mixers, PA amplifiers and where an ultra low "hum" pickup level is desired.

M 0701. **Now \$16.00**
10 or more **\$15.00 ea.**



BRIDGING/ISOLATING TRANSFORMER MU-METAL SHIELD CAN

Use for coupling audio modules - prevents earth loops, hum etc. Essential coupling device where DC isolation is required.

Nominal Impedance
Radio 10K/10K (1:1)

M 0702. **Now \$16.00**
10 or more **\$15.00 ea.**

DALO PEN

Etch resistant ink

Makes PC artwork a breeze

T 0033. **\$2.50**

FERRIC CHLORIDE BEADS 200G


200 gram pack makes 1 litre - a powerful fast etching solution



H 0800 **Now 1.60**

DESIGN BREADBOARD


80 x 127 x 2.5mm spacing. Silver plated. Takes all IC sockets to 40 pin. Inbuilt buss bars.



H 0706. **\$2.95** **\$2.50**

VERO TYPE STRIP BOARD

Alpha numeric grid. Pre drilled 9mm, 2.5mm spacing, 95mm wide. 3 handy lengths.



H 0711 95 x 304. **\$3.40**
H 0712 95 x 152. **\$1.95**
H 0714 95 x 76. **\$1.25**

PLUG IN PC BOARD

60 x 100 x 2.5mm spacing. Silver plated. One of the handiest boards of all - build up professional modules on this plug in board. Great for prototypes. 24 way edge connector.



H 0710
\$1.95

\$1.75

PC BOARD BLANK

Single sided copper clad. **NOW**

H 0750 75 x 150 **.95**
H 0751 150 x 150 **1.95**
H 0752 300 x 300 **3.95**

AT DOUBLE THE PRICE OUR DAINICHI HIGH FIDELITY SPEAKERS WOULD STILL REPRESENT OUTSTANDING VALUE

Altronics have teamed up with one of Japan's most respected speaker designer/manufacturers (Dainichi manufacture OEM speakers for Pioneer) The result, an outstanding range of pure fidelity speakers available to you at IMPORT PRICES for which we will no doubt incur the wrath of our competitors.

CONE TWEETER 50 WATT

50 watt max. power 8 OHM Z.

Amazing performance budget price. Frequency response 2 KHZ-18 KHZ. 110mm Diam. Hole centres 79mm. Australia's best value at this price.



C 3020. **\$8.95**

Now **\$5.95**

DOMTWEETER 60 WATT

60 watt max. power.

Silky smooth frequency response. 1.5 KHZ to 20 KHZ. Wide Angle dispersion. Massive power handling capacity. Diam. 94mm. High spectrum. Purity, incredible low price!



C 3010. **\$19.50**

Now **15.00**

MIDRANGE 50 WATT

Midrange clarity that has to be heard to be appreciated!

Absolutely 1st class reproduction of mid-range - piano, vocal, guitar, violin etc. Huge 50 watts max. input. 8 OHM. Frequency response 700 - 5 KHZ. Value Plus!



C 3030. **\$22.50**

Now **17.50**

WOOFER 307 mm (12 in.)

40 watts max. power 8 OHM.

Roll edge cone suspension. Resonant to 30 HZ. Frequency range 30-2 KHZ. Smooth faithful bass speaker. Ideal Hi-Fi replacement. 48mm voice coil.



C 3040. **\$42.50**

Now **35.00**

L PAD LEVEL CONTROLS



Fully Sealed Type. For use with speaker x over systems.

Now

C 4010 Mid **\$3.50**
C 4012 High **\$3.50**



CROSSTOVERS

C 4003 3-way Network
C 4002 2-way Network

Impedance 8 Ω 8 Ω
Crossover 800, 5KHz, 6dB/oct 5000Hz, 6dB/oct
Input power 80W 60W

Now **15.00** Now **5.00**

OUR POWER RATINGS

are conservative RMS ratings NOT music power or peak power ratings that some manufacturers quote.

ELECTRIC FENCE

Ref: EA September 1982

Mains or battery powered electric fence controller. Kit does not contain automotive ignition coil which is required.

Cat. KA-1109 \$15.00

TEMP. PROBE

Ref: ETI June 1983

A simple kit that can turn your multimeter into a temperature probe. Range -55°C to $+150^{\circ}\text{C}$ with 0.5°C accuracy. Probe case is a simple BIC pen case.

Cat. KB-4033 \$19.50

LED VOLTMETER

Ref: ETI 326

Get an instant 'low' or 'high' condition of your car battery from a row of LEDs. Will give constant indication of battery condition.

Cat. KB-4017 \$12.99

LCD CAPACITANCE METER

Ref: EA March 1982

Measure from 1pF to $19.99\mu\text{F}$ in just 3 ranges. Jaycar supply the total kit.

Cat. KA-1420 \$74.50

MOTOR SPEED CONTROLLER

Ref: ETI 1515

This controller enables you to control the speed of motors found in drills, saws, grinders, blenders etc.

Cat. KB-4031 \$19.95

CAR ALARM

Ref: ETI 084

Senses voltage drop and then switches a relay on to control the cars horn (or siren). Use external switch or key switch to turn on and off (not supplied).

Cat. KB-4018 \$12.50

"SPARKRIGHT" AT-40 CAR ALARM

IMPORTED FROM THE U.K.

Deluxe kit with many features including: 10 amp output relay, accessory loop, horn relay and headlamp output, auto alarm disable etc. Great value.



Cat. KJ-6662 \$39.95

"SPARKRIGHT" SX2000

IMPORTED FROM THE U.K.

A contact breaker triggered reactive discharge system that will fit all 12V negative earth vehicles utilising coil and contact breaker ignition. Gives the most efficient combustion of air/fuel ratios.

Cat. KJ-6650 \$59.00



DIRECT CONNECT MODEM

Ref: ETI 644 October 1982

This unit is a full duplex auto answer/auto originate unit. An incredible array of features including selectable Baud rate, software controlled etc.

Cat. KB-4600 SHORTFORM - PCB plus all components \$169

Cat. KB-4602 FULL KIT - In case with optional audio monitor and signal strength meter \$199

12V 300mA Plugpack to suit - Cat. MP-3010 \$9.95

TRANSISTOR ASSISTED IGNITION

Ref: EA January 1983

Latest version of this popular kit - includes die cast case, TO-3 transistor covers etc. Beware of kits supplied with flimsy sheet metal boxes!

Cat. KA-1506 \$35.00

DELUXE EPROM BURNER

Ref: ETI 668 February 1983

Plugs into the Microbee I/O port and enables you to save programs in any of 5 different EPROMs (2716, 2732, 2532, 2732A & 2764). Deluxe kit includes 5 "Personality" plugs, case, front panel, mains transformer, fuse, 240V plug etc. plus 2 sockets with extra long pins and extra components for 2764 programming.

Cat. KB-4651 \$55.00

TELEPRINTER (TTY) INTERFACE

Ref: ETI 672 October 1983

Adapt cheap 2nd hand teletype machines to a low cost computer printer with this kit. Includes all parts excepting a 240/110V transformer which is available.

Cat. KB-4672 \$13.95

UHF - VHF TV CONVERTER

Ref: ETI May 1981

This kit will convert a UHF signal either from a TV station or from a UHF VCR down to an unoccupied VHF TV channel. Kit contains all parts except for the optional vernier and tuning gang.

Cat. KA-4552 \$32.50

MICROWAVE LEAK DETECTOR

Ref: ETI 724

Gives a positive indication of the seal on your microwave oven - adds to your peace of mind!

Cat. KB-4013 \$14.95

UNIVERSAL DC-DC INVERTER

Ref: ETI 1509 September 1982

Can be used to run high power amps from a 12V battery, running 12V equipment from 24/32V etc. Kit includes basic components.

Cat. KA-4019 \$35.00

NICAD FLOAT CHARGER

Ref: ETI 268 March 1982

Simple to build, cheap and safe to use. Will bring a battery from full discharge to full charge in 12 hours plus maintain a 'trickle' charge to keep it topped up.

Cat. KB-4029 \$7.95

METRONOME

This kit gives an output of between 30 and 160 beats per minute. Inbuilt speaker, level control and LED beat indicators. The kit is complete.

Cat. KA-1400 \$16.95

STEREO SYNTHESISER

Ref: EA September 1982

By employing a Bucket Brigade IC and Comb Filtering a very realistic stereo sound spatial effect can be obtained. Ideal for use with mono VCRs and other mono units that would benefit from 'stereo'.

Cat. KA-1476 SHORTFORM \$39.50

Cat. KA-1478 FULL KIT \$57.50

Jaycar
ELECTRONICS

Incorporating
ELECTRONIC AGENCIES

NUMBER 1 FOR KITS

SHOWROOMS

SYDNEY

117 YORK STREET

Tel: (02) 264 6688 & (02) 267 1614

Telex: 72293

CARLINGFORD

Cnr. CARLINGFORD & PENNANT
HILLS ROAD

Tel: (02) 872 4444

CONCORD

115-117 PARRAMATTA ROAD

Tel: (02) 745 3077

HURSTVILLE

121 FOREST ROAD

Tel: (02) 570 7000

MAIL ORDERS
& CORRESPONDENCE

P.O. BOX 185

CONCORD, 2137

Tel: (02) 745 3077

"SPARKRIGHT" TX2002

IMPORTED FROM THE U.K.

The ultimate system - reactive discharge, contactless or contact triggered, auxiliary backup circuit, clip to coil fitting, four connections only and will fit over 500 cars. The kit to improve your car.

Cat. KJ-6652 \$115.00



DISCONTINUED KITS

Limited Quantities

PHOTON TORPEDO Great game for the kids, or kids at heart!
Cat. KA-1370

**WAS \$29.50 NOW \$19.50
SAVE \$10.00** ★

CUDLIPI CRICKET A great fun kit. Hide it in a room and when there is a noise, it chirps. If it's quiet, Cudlipp is quiet.
Cat. KA-1406

**WAS \$12.50 NOW \$7.50
SAVE \$5.00**

**DIGITAL STORAGE
CRO ADAPTOR**

Cat. KA-1408

**WAS \$110 NOW \$85
SAVE \$25.00**

LOW FUEL WARNING You'll never run out of petrol with this kit fitted to your vehicle.
Cat. KA-1090

**WAS \$15.00 NOW \$10.00
SAVE \$5.00**



SOUND BENDER If you want to sound like Darth Vader or his mates, you can with this kit.
Cat. KE-4036

**WAS \$27.75 NOW \$19.75
SAVE \$8.00** ★

LOW OHMS METER

Measures low resistance, e.g. speakers and is suitable for measuring low resistors.
Cat. KE-4560

**WAS \$29.50 NOW \$22.50
SAVE \$7.00**



PARALLEL PRINTER INTERFACE

Ref: ETI October 1983

Allows you to connect your Microbee to a printer having "Parallel" or "Centronics" input. Kit includes R/angle DB15 plug.

Cat. KE-4671 \$15.00
Centronics plug to suit Cat. PP-0890 \$14.95

VIDEO MODULATOR

Ref: ETI 760 October 1981

High stability (low drift) unit designed to give good RF drive to colour TV's. A must if you're using your colour TV with a computer.

Cat. KB-4554 \$17.95

PREAMPLIFIER

Ref: ETI 471 June 1979

The heart of the ETI4000 system. High performance stereo unit with 4 inputs, filters, mute, loudness, stereo mono and tape monitor switches; bass, treble, volume and balance controls.

Cat. KE-4022 \$47.90

LOUDSPEAKER PROTECTOR

Ref: ETI 494 October 1982

Single channel unit powered by the signal to your speakers. Prevent damage to your expensive speakers.

Cat. KE-4023 \$18.50

★ GRAPHIC EQUALISER 2010 MK IIA

A 10 band equaliser, rack mounted for your Hi Fi system. Improves the sound of your system in relation to room acoustics. See the Jaycar catalogue for more detailed description of this unit.

Cat. KJ-6535 \$139.00

GUITAR BOOSTER

Ref: EA June 1982

Inexpensive preamplifier enables you to use your guitar with your own home Hi Fi system. Complete kit supplied and it runs on a safe 9V battery.

Cat. KA-1450 \$17.50

FLUORESCENT LAMP STARTER

Ref: EA October 1982

This kit replaces the starter in your fluoro lamp. Eliminates flicker and improves lamp life. Does not include starter case.

Cat. KA-1480 \$5.00

WIDEBAND AM TUNER

Ref: EA Dec/Jan 1982/1983

The Playmaster AM Tuner is a true broad bandwidth superhet design kit. Excellent performance plus Jaycar's usual excellence in kit presentation.

Cat. KA-1498 \$249.00

ALIGNMENT KIT FOR ABOVE TUNER

Ref: EA February 1983

This simple module generates 2 spot frequencies (600 Hz and 1300kHz) and buffers your multimeter. Enables you to align the Playmaster AM tuner.

Cat. KA-1515 **FREE WITH ABOVE KIT** .. \$7.95

SUBWOOFER AMP

Ref: EA July 1982

100W rms drive capability coupled with low-pass filter and MOSFET technology. Amp will take line level (1V) or can be connected directly to sub-woofer speaker.

Cat. KA-1452 \$79.00

"VOX RELAY"

Ref: EA April 1982

This voice operated relay (VOX) can be used to turn on tape recorders or transmitters and of course turn them off. Use with high or low impedance microphone or high level line input.

Cat. KA-1432 \$14.50

POST & PACKING CHARGES

\$5 - \$9.99	\$1.50
\$10 - \$24.99	\$3.20
\$25 - \$49.99	\$4.50
\$50 - \$99.99	\$6.50
\$100 - \$198	\$8.00
Over \$199	\$10.00

**COMET ROAD FREIGHT
ANYWHERE IN AUSTRALIA
ONLY \$12.00**

SHOP HOURS

CARLINGFORD, CONCORD &
HURSTVILLE

Mon - Fri: 9 am - 5.30 pm

Sat: 9 am - 12 pm

Thurs Night: 8.30 pm (Not Concord)

SHOP HOURS SYDNEY

Mon - Fri: 8.30 am - 5.30 pm

Sat: 8.30 am - 12 pm

Thurs Night: 8.30 pm

MAIL ORDER BY

 bankcard

VIA YOUR
PHONE



MasterCard

VISA

SHOP AROUND

ETI-807 Tug-O-War

Good practice for the games arcade aficionado! Great amusement for wet, wintery weekends. Components for this project are generally readily obtainable. Unlike you'd expect, Dick Smith stores don't stock all the parts. You'll be able to buy all the LEDs and some of the ICs from D.S.E., but not the 74154, 74LS193 or 74LS123. The pushbuttons, switches and mechanical etc parts are stocked by virtually every electronic components supplier worthy of the name, including Dick Smith stores (we've given D.S.E. catalogue numbers in the parts list for reference).

If you want to make *everything* yourself and wish to use film transparencies of the front panel and pc board artworks, then the set can be obtained for \$8.00 post paid from:

ETI-807 Artwork
ETI Magazine
PO Box 227
Waterloo NSW 2017


Make sure, when ordering, that you ask for positive or negative film, according to what your photoresist requires. Make out your cheque or money order to 'ETI Artwork Sales'.

Kits for this project may be stocked by **All Electronic Components** and **Rod Irving Electronics**, both in Melbourne.

ETI-1410 Bass Guitar Amp

The complete project construction will be finalised next month. All the components are pretty well off-the-shelf from most electronics retailers, with the exception perhaps of the potentiometers. We used 16 mm diameter types with standard 6.5 mm shafts. These are distributed by Soanar, known as "V16L" types. Standard 23 mm diameter pots may be used, but the pc board cannot then be directly attached to them. The connections will have to be made using short lengths of tinned copper wire.

Printed circuit boards should be available from the usual suppliers. If you're making your own, then film transparencies of the artwork for the ETI-1410a and b boards can be obtained for \$7.00 from:



ETI-1410a/b Artwork
ETI Magazine
PO Box 227
Waterloo NSW 2017

Make out your cheque or money order to 'ETI Artwork Sales' and ensure you specify positive or negative film, according to what your photoresist requires. If you want to wait till next month, a complete set of art-

work, including the front panel, will cost \$20.

More details next month.

ETI-1524 Mousetrap

While this project is hardly likely to stem the plague currently sweeping the eastern states, it will certainly clean the rotten rodents out of the house.

There are some unusual com-

ponents in this project, but with a little resourcefulness, you should be able to locate them. The 2 μ 7/400 V (250 Vac) capacitor needs to be mains-rated, metallised poly or mylar type. 'Greencaps' of this value and rating (or even 630 V) are available, though we specified a Siemens type B32231. These types of capacitor feature a self-healing action should a 'punch-through' occur in the dielectric between the 'plates', which consist of a very thin layer of metal deposited on the dielectric film which is then 'wound up' to make the capacitor. If the dielectric breaks down at a stress point, then the arc between the plates vaporises the metallisation (similar to what happens in a fuse) leaving a clear area around the dielectric punch-through, thus 'healing' the breakdown. The capacitor in this application is quite highly stressed, so it is essential to get one of the appropriate type. Apart from the Siemens type specified (try **Promark** for them), Elna greencaps (distributed by **Soanar**) may be used, or Roederstein MKP series (distributed by **Mayer Krieger**).

The MR856 fast recovery diode is not a common component with electronics retailers. However, it is a Motorola part, distributed by **VSI**. Ask your favourite supplier if he'll get some in.

The RCA-made SCR (Q3), the S2600M, is distributed by **AWA Microelectronics**. In Sydney, try **Semikron** in Burwood or **Geoff Wood Electronics** in Rozelle. The C122E (by G.E.) or TIC126E (by T.I.) may be substituted. All the other semiconductors are bog-standard everywhere, as they say.

The ferrite aerial rod used for the core of T2 is stocked by Dick Smith (cat. no. L-1401), amongst others. It's not really critical, providing you use something of similar dimensions.

If you're making your own pc board, you can obtain a same-size **photostat** of the artwork by sending us a stamped, self-addressed A4-sized (same size as the magazine page) envelope. Address it to:

ETI-1524 Artwork Photostat
PO Box 227
Waterloo NSW 2017

If you want a same-size film transparency of the artwork, to


NEW 'DELUXE' INSTRUMENT CASES

This swish-looking new instrument case from Perth-based Altronics Distributors continues the line of "Jack-Tec" boxes introduced by the company last year.


This model is larger than the earlier model. Overall, it measures 260 mm wide, stands 85 mm high and is 190 mm deep. The usable height of the front and rear panels is 73 mm which allows mounting common meters like the Minipa MU45 or University TD66, etc. A speaker vent on the base allows direct mounting of a standard 57 mm (2 1/4") speaker.

Internal mounting posts enable a wide range of pc boards and transformers to be accommodated. Guide rails for pc boards are also provided internally to allow vertical positioning of boards at several locations. The front and rear panels are removable and feature a textured finish on one side, smooth the other. This enables direct engraving or screen printing on the plain side.

The top and bottom split apart, as for the earlier model, and extra plastic or aluminium front and rear panels are available. Four rubber feet are moulded into the case bottom. Full details from **Altronics Distributors, Box 8280, Stirling St, Perth WA 6000**.



DIRECTIONAL ANTENNAS



KENSOR PTY. LTD.
12 Hehir Street, Belmont 6104,
West Australia
Telephone : 4782333 Telex : AA95914

NEW

DC/AC DIAGNOSTIC CURRENT METER



The H.E.M.E. 1000 is a revolutionary new instrument and a powerful new diagnostic tool for use by engineers and designers involved in setting up ac and dc motors, variable speed drives, motor vehicles, battery powered equipment, welding equipment, electroplating apparatus or equipment where surge current values are of paramount importance.

sole agents

WARSASH PTY. LTD.

P.O. Box 217
DOUBLE BAY
N.S.W. 2028
Sydney (02) 30-6815
TELEX 24271


DIGITAL LCD READOUT, ACCURATE MEASUREMENTS, DC AND AC CURRENTS, AUTORANGING.

0-200 and 0-1000 AMPS, RESOLUTION 0.1 and 1A, ACCURACY $\pm 1\%$ of RANGE, SURGE and HOLD, ANALOGUE O/P SOCKET, LEADS & CASE SUPPLIED.

It handles WORKSHOP/FIELD SERVICE and SYSTEMS SETTING-UP.


or stockists in:
ADELAIDE (08) 42-6655
BRISBANE (07) 369-1277
HOBART (002) 23-1755
MACKAY (079) 51-3155
MELBOURNE (03) 82-5363
NEWCASTLE (049) 52-8066
PERTH (09) 381-6000
WOLLONGONG (042) 28-6020

HEAT SINKS



Clip and Save

Clip-on Thermalloy "Slip Clip" heat sinks and save assembly time, board space, and heat sinks costs. They require no mounting hardware, PC board drilling, or adhesives, and clamp firmly to the device for maximum heat transfer. "Slip Clips" are available for TO-202, TO-220, TO-126, Motorola case 90 and most other popular case styles.



Plastic Power Coolers

New low profile heat sinks save board space

The 6073B is 19 mm square and just 9.5 mm high. It cools SCR's and transistors in TO-220, Motorola Case 70 and Case 90 packages. Dissipates 21° C/watt in natural convection. Available in Black Anodized and Pre-Black Anodized finish.



Thermalloy

Number one in Semiconductor Accessories.
TECHNICAL INFORMATION AVAILABLE ON REQUEST.

SOANAR


SOANAR ELECTRONICS PTY. LTD.

INCORPORATED IN VICTORIA

30-32 Lexton Road, Box Hill, Vic., 3128, Australia.

VICTORIA: 8950222 QUEENSLAND: 852 1131
N.S.W.: 789 6744 WEST AUST: 381 9522
Sth. AUST: 2970811 TASMANIA: 31 6533

SHOP AROUND



use directly with your photoresist, then you can obtain it for \$10 post paid by sending a cheque or money order, made out to 'ETI Artwork Sales', addressed as follows:

**ETI-1524 Mousetrap
Artwork Film**
PO Box 227
Waterloo NSW 2017

Make sure you specify whether you want a positive or negative to suit the photoresist you'll be using.

Kits for this project may be stocked by **All Electronic Components** and **Rod Irving Electronic** in Melbourne.

ETI-738 25 W UHF Booster

We have been advised that **Dick Smith Electronics** will be stocking this project as a kit. **Geoff Wood Electronics** in Sydney has the individual parts in stock. Geoff is the source supplier of the SRF1078/2N6136 Motorola RF power transistor used in the project.

Project pricing

We have been advised that, in recent issues, our project pricing has been a little on the low side. We base our price estimates, and that's all they are — **estimates**, not "official" or "recom-

mended" prices, on the latest catalogues or price lists obtainable at time of going to press. However, as there is some 6-8 weeks delay between when the prices are calculated and when the magazine appears in the newsagents and shops, cost and component price movements in the meantime can, and have, markedly affect our estimates. **Please don't blame your supplier** if his price is above our price estimate shown in the project parts list. Nobody's trying to "rip you off".

We're currently pushing our project price estimates up by 10-12% at the time they're calculated, just to cover the situation, which can only be described as 'fluid'.

Ready-made pc boards

You can obtain ready-made pc boards, and sometimes front panels, from the following suppliers:

All Electronic Components
118 Lonsdale St
Melbourne Vic 3000

RCS Radio
651 Forest Rd
Bexley NSW 2207

Acetronics
112 Robertson Rd
Bass Hill NSW 2197
(02)645-1241

Billco Electronics
Shop 2, 31 Pultney St
Dandenong Vic 2175



Jaetronics
58 Appian Drive
St Albans Vic 3021

Jaycar
117 York St
Sydney NSW 2000

Jemal Products
PO Box 168
Victoria Park WA 6100

Mini Tech
PO Box 9194
Auckland NZ

Rod Irving Electronics
425 High St
Northcote Vic 3070



QUARTZ CRYSTAL CLOCK MOVEMENT



\$14.95

- Very compact and reliable
- Self starting one-second stepping motor has strong torque
- Powered by 1.5V AA battery that lasts for one year
- Supplied with two sets of hands, one short and one long
- ± 15 second/month accuracy
- 56mm square, 15mm deep
- Complete with data sheet, instructions and wall hanger bracket.

Cat. XC-0100

JAYCAR JVE-1 VIDEO DETAIL ENHANCER

SPECIFICATIONS:

- Maximum enhancement not less than +8.3dB @ 2MHz
- Enhance disabled (Bypass) response, DC to 5MHz -0.5 +1.0dB
- Colour subcarrier 0dB notch frequency, tunable to 4.43-MHz. $-/+0.5$ dB, all settings
- Amplifier group delay, less than 0.075us
- Signal handling capability not less than 1.35 volts p-p. (Sync. is clipped first)
- Power 12V AC @ 100mA
- Controls: ON/OFF, ENHANCE, ENHANCE/BYPASS SWITCH
- CORE/GAMMA CONTROL
- Input connector, RCA socket
- Output connector, RCA socket x 3

DESIGN FEATURES:

- A unity gain notch at the colour subcarrier frequency, whose purpose is to prevent chrominance to luminance errors at high enhance levels.
- A closed loop configuration with lead lag compensation to achieve stable, well defined gain.
- DC coupling, eliminating large capacitors in series with the video signal and achieving DC response for applications requiring it.
- Low output impedance prior to termination resistors, enabling up to three outputs to exist and be used or left unterminated.



- A level dependent closed loop response or Gamma control ('Core').
- Clip on negative going signals at -67 volts into 75 ohms to prevent sync. errors owing to overshoot.

Cat. AV-6501

\$69.95

12 Volt AC plugpack

Cat. MP-3020 **\$16.95**

NEW - MOTORCYCLE \$39.95

INTERCOM (Ref: EA March 1984)

Now you can talk freely and safely to your pillion passenger with this handy kit!

Cat. KA-1533

ASK FOR A NEW CATALOGUE!!

Mail Order customers, if you have not seen our new catalogue, boy are you missing out! If, (or when) you next buy from us by mail order just ask for a catalogue. It will be sent FREE with your order! If you have one and want one for a friend, that's fine too! Just ask!

MAGAZINE BINDER

Keep your precious (and expensive!) magazines protected and in order for easy reference. Smart royal blue colour with gold lettering. Heavy gauge, richly chromed metal fittings.

Cat. BB-7000

\$4.95 ea

10 up **\$4.50 ea**

GEL RECHARGEABLE BATTERIES

Ideal for alarms or anywhere where constant use depletes batteries quickly.

Cat. SB-2480	12 volt 1.2A/H	\$22.95
Cat. SB-2483	6 volt 8A/H	\$18.95
Cat. SB-2486	12 volt 5A/H	\$29.95

WILDCARDS

Volume One

A potpourri of application notes and tips for the Microbee Personal Computer

NEW MICROBEE BOOKS

WILDCARDS VOL. 3 - Another in the series of Wildcard books with even more in Vol. 3. Large section on assembly language using a game as an example with an assortment of business programs, utilities and graphics.

Cat. XB-9012 **\$16.00**

WILDCARDS VOL. 1 - A potpourri of application notes and tips for the Microbee. This book has received rave reviews from all computer publications. A must for all Microbee owners.

Cat. XB-9010 **\$15.00**

WILDCARDS VOL. 2 - A continuation from Vol. 1 - again a must for all Microbee owners.

Cat. XB-9011 **\$16.00**

WORDSTAR REFERENCE MANUAL

- This manual provides a standby reference to most Wordstar operations. It provides a quick and easy guide to all codes and instructions - a necessity for serious Wordstar users.

Cat. XB-9004 **\$29.95**

WORDSTAR TRAINING MANUAL

- This manual takes you step-by-step through Wordstar operations, such as BLOCK MOVES, SAVING TO DISC, FILE MANIPULATION, PRINTER CODES and their operations. It shows clearly how to operate Wordstar with the use of diagrams and examples to help you use Wordstar to its fullest. An excellent book.

Cat. XB-9005 **\$27.50**

WORDSTAR INSTALLATION MANUAL

- This manual teaches you to modify Wordstar to your needs.

Cat. XB-9006 **\$18.50**



INSIDE CP/M - A GUIDE FOR USERS & PROGRAMMERS

This is one of the most informative books on CP/M available and is commonly referred to as the "CP/M Users Bible". Divided into 2 sections. One being a tutorial including set up operation of CP/M, the other being a quick and easy reference guide to CP/M. A must for all CP/M users.

Cat. XB-9007 **\$41.95**

DISK SYSTEM MANUAL

- This manual explains all about Microbee disk drive systems from setting up through to operation. Contains a wealth of information.

Cat. XB-9009 **\$22.50**

MICROSOFT™ MULTIPLAN MANUAL

- This book runs through the operation of Multiplan with examples to allow any business to use Multiplan to the best of their advantage. If you have not got this book then you have not got the best out of Multiplan.

Cat. XB-9016 **\$29.95**

FORTH USERS MANUAL

- This manual covers the use of FORTH as a language and with tutorials on FORTH, sound and the screen editor, it makes an excellent book to have by your side.

Cat. XB-9017 **\$7.95**

PASCAL - STEP INTO A NEW LANGUAGE

- This book is a tutorial on PASCAL and the editor. A good introduction to the PASCAL user.

Cat. XB-9018 **\$7.95**

INFRA-RED MOVEMENT DETECTOR

The infra-red or IR detector for short, falls into the Black magic category. It basically is a high gain passive tuned receiver of a particular IR band. The heart of the unit consists of a high gain lens (antenna?) which has a "Commutated" field of view. Its reception pattern is comb-like, but highly tuned to the IR wavelength of human bodies.

When a human passes within proximity of the pickup area, the lens will selectively pick up IR radiation and then not. Movement across the pickup area will result in a series of pulses sent to a detector circuit. IR detectors are very reliable as they do not transmit and will not respond to non heat radiating objects. Curtains, for example, can wave about without tripping the alarm. Even the cat is unlikely to trip the unit.


The "Arrowhead" is the latest of a series of IR detectors that we have sold. It represents the latest developments.

FEATURES:

- 12V DC powered
- Small 4 1/2" x 2" x 1 1/2"
- Double sensor
- Computerised OC to lower failure rate
- Built in test lamp
- Tamper switch included
- Alarm output SPST 30V DC @ 1A

Cat. LA-5017

\$129.50



**Jaycar
ELECTRONICS**

SEE OUR DOUBLE PAGE ADS FOR FULL JAYCAR DETAILS

LETTERS

Fee for service

Dear Sir,

I am an electronics enthusiast who, like many others, has turned a hobby into a profession. But, unfortunately, I have to make a living out of it.

Other professionals, such as medical practitioners and lawyers, have built up a mystique over the years. An appointment has to be made well in advance and any problem requires more than one visit. These professions have standard fixed fees, no under or overcharging.

The GP's work is only clerical in nature but they have convinced the community that they are indispensable. If electronics types withdrew their services for a year they would not be noticed.

Trades, such as plumbers and washing machine servicemen, charge fees like \$80 as a minimum and undercharging does not happen; plumbers simply do not turn up to jobs without the chance of maximum payment. If you do not believe this, find out the charges for yourself.

Electronics repairmen, the part of our industry visible to the public, do not make a good living. Many customers seek repairs without intending to make payment. Quotes result in wasted time. For the enthusiast, 'friends' seek repairs and usually offer heaps of praise but no payment, even for components.

Most electronics people are weak and introverted. They may have interesting work but they will not get anywhere, especially if they (we) do not know how to charge for services!

L. W. Brown
Burwood, Vic

Linear tracking T/Ts

Dear Sir,

In ETI, Dec 1983, the article which reviewed six linear tracking turntables stated that the cost of engineering these turntables far outweighs the benefits.

I have owned conventional turntables but now own a Sony linear tracking turntable and find that the benefits of these turntables, and the ease of obtaining state-of-the-art reproduction, far outweighs the cost of superb engineering.

The linear tracking arm is very easy to set up and provides state-of-the-art reproduction with a Denon 305 and absolute accuracy of alignment. This is, of course, contrary to the article and I find it against progress and the advice needed by audiophiles.

These turntables are very reasonably priced. The reason for low, low resonance response on the Sony is an anti-resonator, not mentioned in your article. I am sure someone has not heard music in the state-of-the-art.

R. B. Manson
Launceston, Tas.

I agree with your sentiments that when the Sony linear tracking turntable is properly set up, as yours undoubtedly is, it obviously provides you with an extremely good performance. However, the words I used and their specific intent were a little different from the abbreviated statement in your letter.

My measurements and observations showed clearly that for a linear tracking turntable to exceed the best performance of a pivoted tone arm turntable requires sophisticated engineering. I can only justify such complexity when it achieves improvements and performances that the less complex system is unable to provide. While the best of the systems came close to providing such improvements, the less expensive ones did not.

It is obvious that linear tracking turntables are being promoted by marketing personnel as a new gimmick to improve sales. However, they have only achieved the following attributes:

1. The low cost linear tracking turntables are undoubtedly neater, smaller and more functional than conventional pivoted arm turntables. These units do not appear to offer any significant improvements in technical performance as a result of the change to the 'linear tracking' principle.

2. The more expensive examples of the linear tracking turntables are more attractive, exciting and generally larger than the conventional pivoted tone arm turntable. Our investigations have not shown that their technical performance is significantly improved in either trackability or in reduced distortion.

Louis Challis
Kings Cross, NSW

Questions on CD

Dear Sir,

I am a regular reader of your excellent magazine and find it very interesting.

I thought I would point out a few errors in the article on compact disc players published in ETI, February 1984 on page 37. It is stated that the Technics SL-P8 is the first unit from Technics. This is incorrect as Technics released the SL-P10 well before the SL-P8. Perhaps the SL-P10 was not sold in Australia but it was certainly available in New Zealand prior to the SL-P8. Australia may have been behind NZ in compact disc players.

the other error that I thought I would point out is that the SL-P8 is provided with a remote control unit. If the writer of the article had taken the trouble to read the instruction book he would have seen that the remote control unit is a standard accessory of the SL-P8.

S. J. Jepson
Otaka, NZ

Thank you for your letter regarding the CD players review in the February '84 issue of ETI. However, I wish to take issue with your criticisms. Firstly, the SL-P8 was the first player released in Australia by Technics. The SL-P10 was not released generally here,

according to the information supplied by National Panasonic Australia. I personally saw one, and had a demonstration, at the Technics factory in Osaka, in Japan, in July 1982, and subsequently wrote a news item on it in the August 1982 issue, page 117. At the end of this item I said "No date has been set for the unit's release in Australia". In fact, it was not released. Undoubtedly, units were obtainable at some outlets, but likely not purchased through National Panasonic here. Hence, the SLP-8 was the first Technics CD player released here. I might add that this information was included because that was the position given to us by Technics!

As regards the remote control, I draw your attention to page 41, Feb. '84 issue, centre column, second last paragraph. "... from a remote control unit which was not supplied with the unit we received." Our reviewer, Louis Challis, noted that an infrared remote control was available for the unit, but that we did not receive it. He did take the trouble to read the instruction book, as he always does, however, you did not take the trouble to read the article closely enough.

I trust you continue to find ETI excellent reading.

Roger Harrison
Editor, ETI

More Mac

Dear Dregs,

You're right — Mac Rame will have you in knots until someone explains it is a special string command for use in networking.

Mac Rame should only be used with the Mac Kerel software which forms a trap for any data stream that looks a bit fishy.

Mac Indoe is another useful routine; it sets the pitch for computer generated sound effects. For the Scots there is a special export grade called MacCrimmon¹ for use with the electronic bagpipes (recently seen on ABC-TV).

And speaking of the Scots, rumour has it that there will be an erasable ROM supplied for this market under the description Mac Clean. Apparently there is still further work to be done on the Mac Abre effect associated with erased ROM.

In the communications field high hopes are held for Mac Ula, an applications configured system for predicting sun spot activity.

The oil exploration industry is eagerly awaiting the correction of a little slip in the application package Mac Assar, which has resulted in vast reserves of hair oil.

Incidentally, I tried to teach your April Dregs to a neighbour's parrot that used to scream all day "Polly wants an Apple"; now it sits silently on its perch, over-Mac-Awed!

Now wouldn't that give you the Mac Pip! — a condition worse than finding a bug in your Apple.

Keith R. Groom
Oakleigh Sth, Vic.

(1) For details of Mac Crimmon see 'Oxford Companion To Music', under 'Bagpipes'.

MINI-MART For Sale/Wanted/ Swap/Join

AUDIO

WANTED: Reel-to-reel tape deck, 4 or 8 track. Groenhout, 25 Kerferd St, Watson ACT (062)412-316.

SALE: INSTRUMENT SPEAKERS HP 38 cm 18 cm \$25, \$50 for both. Also one Albicord telephone answering machine \$20. Chris (03)459-6141.

SALE: CONCRETE SPEAKER BOXES. Two only to suit ETI Series 4000/1, 4-way per project. These are the actual units described in July 1981 issue, \$450. Gareth Angton, 11 Moldavia Walk, Osbourne SA (08) 248-1406.

COMPUTERS

SALE: MICROBEE 32K IC \$460 ono. Soft-good condition. 64K ROM board \$70. 64K ROM \$30. J. Magnussen, 28 Chorley Cheltenham NSW 2119. (02)86-1653.

SALE: MICROBEE 32K with 4 MHz convert-black and white monitor, cassette deck, tape, manual and tapes, only \$450. Phone 5-6480.

SALE: MICROBEE 32K, 4 MHz. EDASM, Denshi Green monitor, Joystick, chess, K. Lau, 7 Jindaless Place, Killara NSW (02)498-7270.

FOR SALE: ACT VIC-20 bimonthly magazine. Many interesting articles and programs. August issue \$2. Bimonthly \$12 per year. Chris Groenhout, 25 Kerferd St, Watson ACT 2602.

WANTED: REPLACEMENT COPIES of bundled software for Kaypro 2 damaged while moving. Write to Box 337, Kingcote SA 5223. (0848)2-2631.

FOR SALE: SUPER 80 ASSEMBLER \$15, disassembler \$9. Vintage new receiving and ham radio valves. Send SASE for types and prices. R. Vowels, 93 Park Drive, Parkville Vic. 3052.

WANTED: VIC 20. Working condition unexpanded model. Will consider other peripherals and software. Must be realistically priced. Brown. P.O. Box 5451, Cairns Qld 4870.

FOR SALE: TANDY 3-6-9 V solar cell \$5. Tandy MC-10 computer \$75. ETI-660, colour, 3K RAM \$80. TI59 programmable calculator \$50. B. Begg, 18 Sturt Ave, Toorak Gardens SA 5065. (08)31-0310.

FOR SALE: MONITOR, b/w portable deluxe, 12 inch CRT, excellent condition. Asking \$100. Contact E. Brover, 8 Pentlowe Avenue, Lower Tempelstowe Vic 3107. (03)850-1090.

FOR SALE: DGZ80 CPU \$100, ETI-640 VDU \$80. 32K static RAM \$150. 12K BASIC ROM PCB \$80. Power supply, ten-slot motherboard and case \$90. L. Donkin, P.O. Box 135, West Mackay Qld 4740.

ATTENTION VZ200 users. Would you like to be on my data base mailing list? It is a sort of mail based club. John D'Alton, 39 Agnes St, Toowong Qld. 4066. (060)371-3707.

SWAP PERSONAL COMPUTER. User group urgently seeks other enthusiasts. Please write for information on this newly established national club. John Paulic, P.O. Box 79, Gosnells WA 6110. (09)398-6303.

FOR SALE: \$100 BOARD. Ithaca Audio Z80 CPU \$70. WMC MEM-Z 16K RAM \$60. DG640 VDU \$80. (03)584-4749. W. R. Crowther, 52 Wallingford St, Cheltenham.

FOR SALE: ZX 81 SPECIAL built into real keyboard 32K RAM with TV, printer, cassette. Regulated power supply, good software. H. Veevers, 2/31 Mill St, Carlton NSW 2218. (02)586-1507. \$475 ono.


COMMUNICATIONS


FOR SALE: FACSIMILE transceiver, Rank Xerox 400 complete with Telecom attachments, handbook, paper. In good condition and working order. \$800. 8 Beagle St, Darwin NT 5790 (089)81-2761.

WANTED: TIME MARK GENERATOR and copy of radio and electronic laboratory handbook by Scroggie and Johnstone. David, P.O. Box 316, Manly NSW 2095. (02)938-3417.

MISCELLANEOUS

FOR SALE: 150 volumes of EA and ETI from 1976 to 1982. Most in plastic binders. Russell, (052)43-0741.



PROUDLY
AUSTRALIAN 

ALARM & SECURITY
AUDIO
COAXIAL
COMMUNICATION
COMPUTER
CONTROL
DIRECT BURIAL
FIRE ALARM

- HIGH TEMPERATURE
- INSTRUMENTATION
- MICROPHONE
- MULTI CONDUCTOR
- TEFLON
- HOOK UP
- TRAFFIC SIGNAL
- AIRCRAFT

Millions of metres of electronic wire and cable are just a phone call away.

ACME HAS WHAT YOU NEED ...

IN THE RIGHT QUANTITY ...

AT THE RIGHT PRICE ...

CALL NOW
FOR INFORMATION

ACME ELECTRONICS SYDNEY 648 2255
ACME ELECTRONICS BRISBANE 44 4131
J.G. THOMAS PERTH 272 7122

ACME ELECTRONICS

A Division of JAMES HARDIE ELECTRICAL (Hardie Trading Ltd. - Inc. in Vic.)

2-18 Canterbury Road, Kilsyth, 3137. 729 8999 AA 35786

- NEIL MULLER P/L ADELAIDE 272 8011
- ELECTRONIC COMPONENTS CANBERRA 80 4654
- W.P. MARTIN HOBART 34 2811



WE HAVE BEEN exercising our minds on mouse traps for the last month or so, and no doubt you will have seen the results of this strenuous deliberation in our article on mouse dispatching. Didn't it strike you as somehow comforting to know that, at the heart of all the hi-tech'ery was the most low-tech of baits, a mouldy old bit of cheese?

But the Japanese are about to change all that. (Now you know how the Swiss watchmakers felt when someone first said "digital" to them). It seems that one Yosuke Watanabe, from the Ikari research labs has discovered that what rats love most is other rats. What is more, one rat knows where the other rats are because they all emit an ultrasonic whistle on 24 kHz. Ain't mateship wonderful?

The above facts all came to light when Watanabe was trying to find out why rats are attracted to computer installations. The problem has got worse in recent months because Japan has been experiencing a rat plague. (No cats). In fact, things are getting so bad that it is estimated that one computer failure in three in Tokyo is now caused by rats either eating through cables or urinating on connections.

A solution to the problem has not been long in forthcoming. Ikari plan to build an upmarket version of our project in this issue. It will have an ultrasonic transmitter tuned to 24 kHz, which will attract the rats, a vacuum cleaner that will suck them off the floor, and finally a gassing and disinfection station where the *coup de grace* will be administered. The idea is that the contraption would be built into the building to completely protect the computer.

At least ours is cheaper.

Pass the pintpot

It's not only in Tokyo that they're having problems. New York hosted the conference of the American Association for the Advancement of Science (AAAS) recently. It seems that a real problem has been detected at the conference.

The Hilton hotel, where the conference was held, has decided to introduce plastic beer mugs. Now anyone unfortunate enough to have drunk from one of these monstrosities will know that (a) the beer tastes awful and (b) they don't weigh as much as your ordinary common-as-grass glass tankard.

The second of these is a problem because it means that experienced drinkers have a lot of trouble knowing how much anti-gravity force to apply to the plastic glass when addressing the beer to the input port. If you're lucky, you wind up dribbling down the front of your shirt. If you're unlucky, you splash the guy behind. If you're *really* unlucky, the guy behind is a seven foot gorilla with a squint!

It appears that the British press corps, who descended on the AAAS conference *en masse* had just such a few incidents, which caused quite a few un-scholarly moments. No wonder Ronny and Maggie have so much to chat about.

A 'wetwork'?

Finally, it's good to know we aren't the only people in the world who suffer from the dreaded typo. They're the bane of this industry. Recently we learned, for instance, that the Dulmont Magnum, that most portable of Australian macro computers, is to be sold in the US via a 'newtwork'. That's a network of web-footed computer salesmen.

Why have they got webbed feet? From splashing about in bars serving beer in plastic tankards!



OVER THE HORIZON BUT NOT OUT OF YOUR REACH

At altitude, the radar capability of the F/A 18 Hornet enables it to look down over the curvature of the earth's surface and see targets far beyond normal radar range.

This is just one of the advanced systems that make the Hornet such an outstanding military aircraft.

State of the art aviation technology in communications, laser guidance and detection, multiple target tracking, mission computers, advanced electronics.

To keep it flying as it should we need technically minded young men and women to train as Electronics Technicians.

If you have successfully completed

at least year 10 with passes in English, Maths and Science (physics content) and you would like a full-time career working with the very latest in aviation technology, contact us now.

If you are an Australian citizen (or eligible to become one), aged 17-34, telephone your nearest Air Force Careers Adviser on: Sydney (02) 219 5555, Newcastle (049) 25 476, Wollongong (042) 28 6492, Parramatta (02) 635 1511, Canberra (062) 82 2333, Melbourne (03) 697 9755, Geelong (052) 21 1588, Brisbane (07) 226 2626, Townsville (077) 72 4566, Adelaide (08) 212 1455, Perth (09) 325 6222, Hobart (002) 34 7077, Launceston (003) 31 1005, or write to Box XYZ in your capital city.



JOIN AUSTRALIA'S AIR FORCE.



How to invest in Yamaha, without living beyond your means.

Yamaha's new top-of-the-range Cassette decks, the K-1000 and K-2000, incorporate the most advanced, state-of-the-art studio component technology at prices \$200 to \$300 less than comparable equipment.

Indeed, they compare favourably in significant performance areas with any cassette decks at any price.

Both decks have been painstakingly designed and uncompromisingly engineered for optimum functionality and reproduction performance.

Each employs a specially designed two-motor, direct drive transport mechanism for

smooth, silent precision, and three low-impedance heads which features a unique Sendust formulation to ensure superb, long lasting reproduction quality. Plus the heads have a lifetime warranty.

The two decks utilise Yamaha's unique Linear Electromagnetic Transduction system which extends linearity to the point where the signal is transferred from the head to the tape—a previously uncontrollable area in the recording chain.

High performance features on both decks also include dbx and Dolby-B* noise reduction, ORBIT

(Optimum Record Bias Tuning), a microcomputer controlled Linear Counter, expanded range level meters and a number of auto memory functions.

For Yamaha the K-1000 and K-2000 cassette decks are a natural progression in 95 years of outstanding accomplishments in musical instruments and audio componentry.

For you they represent the finest natural sound recording and reproduction at a surprisingly affordable cost.

Your Yamaha dealer can show you the full range of Yamaha Cassette decks starting at around \$200. If you'd like further information just complete and post the coupon below.

*Dolby is the registered trade mark of Dolby Laboratories



K-1000

K-2000

I'd like further technical information on the new K-1000 and K-2000 cassette decks.

Name

Address

Postcode

Send to: Yamaha Hi-Fi Division,
Rose Music Pty. Ltd.,
17-33 Market Street, South Melbourne,
Victoria 3205.

